

---

# Native Tree Report

---

# 23333

# Saddle Peak Road

County of Los Angeles

APN# 4438-039-001

PREPARED FOR:

**Golden Palace  
Construction Company, Inc.**

20225 Lorenzana Drive  
Woodland Hills, California 91364  
Contact: Mr. Nemotollah Mostajer  
(818) 599-5310

PREPARED BY:



4165 E. Thousand Oaks Boulevard, Suite 290  
Westlake Village, California 91362  
Contact: Mr. Jim Anderson, Principal Biologist  
(818) 879-4700

**August 2022**  
Revised March 2023

# **NATIVE TREE REPORT**

**23333 Saddle Peak Road  
County of Los Angeles**

**APN# 4438-039-001**

---

*Prepared for:*

**GOLDEN PALACE CONSTRUCTION COMPANY, INC.**

20225 Lorenzana Drive  
Woodland Hills, California 91364  
Contact: Mr. Nematollah Mostajer  
(818) 599-5310

*Prepared by:*

**ENVICOM CORPORATION**  
4165 E. Thousand Oaks Blvd., Suite 290  
Westlake Village, California 91362  
Contact: Mr. Jim Anderson  
(818) 879-4700

August 2022  
Revised March 2023

<b><u>SECTION</u></b>	<b><u>PAGE</u></b>
<b>I. BACKGROUND INFORMATION</b>	<b>1</b>
<b>II. ENVIRONMENTAL SETTING AND SITE OBSERVATIONS</b>	<b>4</b>
<b>III. TREE SURVEY RESULTS</b>	<b>5</b>
<b>IV. PROJECT IMPACTS</b>	<b>6</b>
<b>V. MITIGATION MEASURES</b>	<b>10</b>
<b>VI. TREE PROTECTION MEASURES</b>	<b>11</b>

**TABLES**

Table 1	Tree Survey Data	5
Table 2	Impacts – Prior Fill Placement and Proposed Restoration Activities	9
Table 3	Tree Mitigation	11

**FIGURES**

Figure 1	Regional Location Map	2
Figure 2	Tree Location and Impact Map	3

**PLATES**

Plate 1	Photos of Protected Trees in the Survey Area	7
Plate 2	Photos of Protected Trees in the Survey Area	8

**APPENDICES**

Appendix 1	Restoration (Fill Removal) and Erosion Control Plans, ACE Civil Engineering and SMS Geotechnical Solutions, March 3, 2023
Appendix 2	Field Observation Definitions
Appendix 3	Tree Survey Data Forms

---

## I. BACKGROUND INFORMATION

### *Property Owner/Applicant Information*

The property owner is:

Mr. Nemotollah Mostajer  
Golden Palace Construction Company, Inc.  
20225 Lorenzana Drive  
Woodland Hills, CA 91364  
(818) 599-5310

### *Preparer Information*

The preparer of this Native Tree Report is:

Envicom Corporation (Envicom)  
4165 E. Thousand Oaks Blvd., Ste. 290  
Westlake Village, CA 91362  
Contact: Mr. Jim Anderson, Principal Biologist  
(818) 879-4700 ext. 234

### *Project Location*

The project site is located at 23333 Saddle Peak Road (APN# 4438-039-001) within a rural area of unincorporated Los Angeles County in the Santa Monica Mountains (see **Figure 1, Regional Location Map**). The property is in the Coastal Zone and is subject to the Santa Monica Mountains Local Coastal Program (Santa Monica Mountains LCP).


### *Project Description*

As required by the County of Los Angeles (County), the project involves removal and disposal of undocumented fill from a slope as well as a graded pad area, and restoration of all disturbed areas on the subject property to native habitat, including removal of invasive plant species. **Appendix 1** provides a restoration (fill removal) and erosion control plans prepared by ACE Civil Engineering and SMS Geotechnical Solutions, March 3, 2023, which illustrate the locations of the fill dirt to be removed. The undocumented fill, the proposed restoration area, and the proposed invasive plant species removals are shown on **Figure 2, Tree Location and Impact Map**.

### *Assignment*

The County has required preparation of a Native Tree Report to document protected native trees located within or adjacent to the undocumented fill dirt and the proposed restoration area. Protected native trees include trees meeting criteria for protection pursuant to the Santa Monica Mountains LCP.

The Santa Monica Mountains Local Implementation Plan (LIP) requires the Native Tree Report to include a survey map and to identify the existing health of each native tree, potential impacts of development on each native tree, and whether each tree is proposed to be removed, to have substantial encroachment into its root protection zone, or minor encroachment. The report shall also contain recommendations or avoiding, minimizing, and/or mitigating native tree impacts.



Sources: ESRI, World Street Map, 2016.

23333 SADDLE PEAK ROAD - NATIVE TREE REPORT

# Regional Location Map





FIGURE 1





Source: Valtus Imagery Services; Hexagon Imagery Program (HxIP), 2017.

---

This report identifies protected native trees located within and immediately adjacent to the proposed restoration area and evaluates the potential impacts to protected trees and mitigation requirements.

### ***Method of Field Evaluation***

The Santa Monica Mountains Land Use Plan and LIP define protected trees as all oaks (*Quercus* sp.) and native trees measuring  $\geq 6''$  in diameter, or a combination of any two (2) trunks measuring a total of  $\geq 8''$  or more in diameter (measured 4.5' above ground). Pursuant to the LIP, Envicom Principal Biologist Jim Anderson and Staff Biologist Cameron Cesa conducted a survey and evaluation of all protected trees within the survey area on June 9, 2022. A silver aluminum tree tag marked with an identifying number was affixed to the north side of each surveyed tree. Global Positioning System (GPS) coordinates of the trunks of the protected trees were georeferenced using a Trimble GEOXH 6000 Series with sub-meter accuracy, and canopy extents were delineated in the field using recent aerial imagery. Visual inspections and measurements recorded included the following:

- 1) Tree species;
- 2) Form including canopy extent and trunk diameter at 4.5 feet above grade;
- 3) Physical condition; and,
- 4) Tree health rating.

Additional information was collected for oak trees, such as additional physical data, vigor, and aesthetics. **Appendix 2** provides an overview of field observation definitions and grading criteria.

## **II. ENVIRONMENTAL SETTING AND SITE OBSERVATIONS**

The site is located at the upper elevations on the southern flank of the Santa Monica Mountains on a drainage divide separating the Topanga Creek Watershed and the Las Flores Canyon Watershed. The western portion of the site is bisected by Saddle Peak Road. The site is undeveloped. There is a flat graded pad and a short, unimproved dirt road at the site. The graded pad can be accessed from Saddle Peak Road via the unimproved dirt road (the south entrance) or via a separate gate (the north entrance) located just west of the pad. There is a chain link fence with large wooden posts to discourage unauthorized access to the property, which runs along the western margin of the pad and dirt road generally parallel to Saddle Peak Road.

The topography of the site ranges from flat to moderately steep with elevations ranging from approximately 2,330 to 2,485 feet. The soils are of the Zuma Ridge-Kawenga association, 30 to 75 percent slopes, which consist of loam over bedrock, which formed from residuum and colluvium derived from sandstone. There are sandstone rock outcrops along Saddle Peak Road. The average high/low summer temperatures in the upper elevation inland foothills of the Santa Monica Mountains are 80/50°F, average high/low winter temperatures are 70/40°F, and precipitation is approximately 18 to 23 inches per year. Vegetation at the site consists predominantly of chaparral, stands of introduced trees, and disturbed areas such as the graded pad, which are ruderal and contain non-native grasses and forbs. Based on a review of aerial imagery, the site does not appear to have been burned in a wildfire for many years.

There is an ephemeral drainage on the subject property and another just south of the property. These drainages do not support riparian vegetation but rather are crossed by the same type of chaparral or scrub habitats found on the surrounding slopes. Both drainages flow in a general west to east direction.

The undocumented fill dirt was placed at the graded pad and on the slope near the south entrance to the property. The graded pad is flat while the entrance slope is moderately steep, and both are currently vegetated predominately with non-native grasses and forbs.

The site is surrounded by undeveloped, relatively pristine natural habitats. There is rural residential development to the southeast, and a microwave tower and utility station to the northeast.

### III. TREE SURVEY RESULTS

Within the survey area, there are a total of nine (9) protected native trees, including six (6) scrub oaks (*Quercus berberidifolia*), two (2) laurel sumacs (*Malosma laurina*), and one (1) toyon (*Heteromeles arbutifolia*). Figure 2, Tree Location and Impacts Map provides the GPS-acquired location of each protected tree as well as their canopy extents and Protected Zones. The Protected Zone is defined as the area within the dripline and extending a minimum of five (5) feet outside the dripline or 15 feet from the trunk of a tree, whichever is greater (LIP subsection K of Section 22.44.1920). Photographs provided below on **Plates 1 and 2, Photos of Protected Trees in the Survey Area** document the visual condition of each tree. **Table 1, Tree Survey Data** provides the data collected for each protected native tree, including species, diameter, health rating, notes on physical condition, and whether the tree is a heritage tree. Additional information was collected for oak trees, which is provided on forms in **Appendix 3**. None of the protected trees are heritage trees.

Four (4) of the scrub oaks (Tree #s 1 – 4) located adjacent to the unimproved dirt road comprise a small Los Angeles County oak woodland. The extent of this Los Angeles County oak woodland including the canopies and sphere of influence (SI) are shown on Figure 2. An oak woodland is defined by the County as “an oak tree stand, including its understory, which consists of two or more oak trees of at least five inches in diameter measured at 4.5 feet above mean natural grade, with greater than 10% canopy cover, or that may have historically supported greater than 10% canopy cover as early as January 1, 2005.” Los Angeles County oak woodlands also include Spheres of Influence (SIs), or buffers, around the oak trees.

**Table 1**  
**Tree Survey Data**

Tree #	Species	Trunk Diameter (inches)*	Heritage Tree	Health Rating	Notes
1	Scrub Oak	6.5, 8.3	No	B	Confirmed by digging to be a multi-stemmed tree rather than two separate trees. There is a chain link fence beneath tree canopy. “B” rating aesthetics and conformity (aesthetics and conformity ratings provided for oak trees).
2	Scrub Oak	6.3	No	A	Chain link fence beneath tree canopy. “B” rating aesthetics and conformity.
3	Scrub Oak	6.2, 2.8	No	B	Lower, smaller mainstem shaded and possibly dying, and appears to have been cut previously. Chain link fence beneath tree canopy. “B” rating aesthetics and conformity.
4	Scrub Oak	6.4	No	A	“B” rating aesthetics and conformity. There is a chain link fence within the Protected Zone.



Tree #	Species	Trunk Diameter (inches)*	Heritage Tree	Health Rating	Notes
5	Laurel Sumac	7.9, 6.3	No	B	Significant sap exudation along main stems but canopy in good condition. Some of the lower branches have been removed, although not recently. There is some debris piled near the base of the tree.
6	Scrub Oak	6.2	No	B	“B” rating aesthetics and conformity. There is another scrub oak trunk close to this tree, but since the diameter at breast height of this trunk is 4.9” it is not a LA County oak woodland.
7	Scrub Oak	4.1, 4.1	No	A	“A” rating aesthetics and conformity.
8	Laurel Sumac	5.0, 3.6	No	C	Significant dieback of branches and twigs.
9	Toyon	5.5, 4.8	No	A	Relatively wide canopy extent and in excellent condition. Chain link fence outside canopy but within Protected Zone.

\* For trees with multiple trunks the DBH for the two (2) largest trunks are provided.

#### IV. PROJECT IMPACTS

The project involves removal of undocumented fill from two locations including at the graded pad and a slope near the south entrance to the property as well as restoration of disturbed areas to native habitat, including removal of invasive species. Existing chain link fencing will also be removed as part of the restoration of the site. **Appendix 1** provides restoration (fill removal) and erosion control plans prepared by ACE Civil Engineering and SMS Geotechnical Solutions, which show the locations of the fill dirt to be removed. Other than to remove the fill dirt and contour areas where the fill dirt is removed, no grading or use of heavy equipment is proposed. The proposed restoration area and invasive plant species removals are shown on Figure 2, Tree Location and Impact Map. The restoration of the site is addressed in a restoration plan prepared by Envicom Corporation (August 2022, revised March 2023).

The impacts evaluated for protected trees include potential impacts caused by the original placement of the undocumented fill dirt, which was based on field surveys and a review of aerial imagery available on Google Earth, as well as potential impacts that could occur when the fill dirt is removed, and the site restored to native habitat. The potential impacts from the original installation of the chain link fencing as well as the impacts that could occur when the chain link fence is removed are also evaluated. Impacts to protected trees at the site are summarized in **Table 2, Impacts – Prior Fill Placement and Proposed Restoration Activities**.

No protected trees have been removed or will be removed by the project. Tree #5 was encroached upon by placement of fill, which was deposited within 23% of its Protected Zone. Tree #5 is located at the northern margin of the entrance slope. Tree #5 would also be encroached to remove the fill from its Protected Zone, which would be accomplished using hand tools. No protected trees other than Tree #5 were encroached by the placement of fill dirt, and no other protected trees would be encroached during removal of fill. Removal of the debris within the understory of Tree #5 can be accomplished by hand and would not impact this tree.

Tree #s 1 – 4 and Tree #9 were encroached upon by installation of the chain link fencing, which affected less than 10% of each of their Protected Zones. These trees do not appear adversely affected by the fence, which has been in place for many years to discourage unauthorized access to the property. Some excavation and ground disturbance would be necessary to remove the metal and wooden fence posts as well as the



Tree #1



Tree #2



Tree #3



Tree #4



Tree #5



Tree #6



Tree #7



Tree #8



Tree #9

chain link portion of the fencing, which would be accomplished using hand tools. Therefore, Tree #s 1 – 4 and Tree #9 would be encroached during removal of the chain link fencing, which would also affect less than 10% of each of their Protected Zones. As stated, Tree #s 1 – 4 constitute a small scrub oak woodland. The impact of the fencing and its removal would not significantly affect the woodland, given its moderately degraded condition as well as the low severity of impact of these activities.

The canopies and/or Protected Zones of Tree #s 1 – 3, 5, 6, and 7 as well as the canopy and SI of the Los Angeles County oak woodland overlap disturbed areas at the site and therefore would be within the habitat restoration area. Tree #s 4, 8 and 9 do not overlap disturbed areas at the site, although Tree #s 4 and 9 overlap disturbed areas within the Saddle Peak Road right-of-way. As proposed, habitat restoration activities within the canopies, Protected Zones, and the SI of these protected trees and the oak woodland would be limited to removal of non-native and invasive species and spreading native seed, as necessary. Other than the removal of fill from the Protected Zone of Tree #5 and removal of fencing from within the Protected Zones of Tree #s 1 – 4 and Tree #9, there would be no ground disturbance or irrigation within the canopies or Protected Zones of protected trees or oak woodlands during restoration of the site.

**Table 2**  
**Impacts – Prior Fill Placement and Proposed Restoration Activities**

Tree #	Species	Presumed Impact of Fill Placement	Impact of Proposed Restoration Activities
1	Scrub Oak ( <i>Quercus berberidifolia</i> )	No Impact. This protected tree is not located where the fill was placed.	Potential Impact. The canopy and Protected Zone of Tree #1 would be encroached upon to remove the chain link fencing. This would affect less than 10% of the Protected Zone. Except for weed removals and spreading native seed no habitat restoration activities would be conducted within the canopy or Protected Zone of this tree.
2	Scrub Oak ( <i>Quercus berberidifolia</i> )	No impact. This protected tree is not located where the fill was placed.	Potential Impact. The canopy and Protected Zone of Tree #2 would be encroached upon to remove the chain link fencing. This would affect less than 10% of the Protected Zone. Except for weed removals and spreading native seed no habitat restoration activities would be conducted within the canopy or Protected Zone of this tree.
3	Scrub Oak ( <i>Quercus berberidifolia</i> )	No impact. This protected tree is not located where the fill was placed.	Potential Impact. The canopy and Protected Zone of Tree #3 would be encroached upon to remove the chain link fencing. This would affect less than 10% of the Protected Zone. Except for weed removals and spreading native seed no habitat restoration activities would be conducted within the canopy or Protected Zone of this tree.

Tree #	Species	Presumed Impact of Fill Placement	Impact of Proposed Restoration Activities
4	Scrub Oak ( <i>Quercus berberidifolia</i> )	No impact. This protected tree is not located where the fill was placed.	Potential Impact. The Protected Zone of Tree #4 would be encroached upon to remove the chain link fencing. This would affect less than 10% of the Protected Zone. Except for weed removals and spreading native seed no habitat restoration activities would be conducted within the canopy or Protected Zone of this tree.
5	Laurel Sumac ( <i>Malosma laurina</i> )	Potential Impact. The canopy and Protected Zone of Tree #5 was encroached upon by the placement of fill at the slope near the south entrance to the property. The fill placement impacted 23% of the Protected Zone of this tree. The tree does not appear to have been adversely impacted by the fill.	Potential Impact. The canopy and Protected Zone of Tree #5 would be encroached upon to remove the fill from the slope near the south entrance to the property. This would affect 23% of the Protected Zone. Except for weed removals and spreading native seed no other habitat restoration activities would be conducted within the canopy or Protected Zone of this tree.
6	Scrub Oak ( <i>Quercus berberidifolia</i> )	No impact. This protected tree is not located where the fill was placed.	No Impact. This protected native tree would not be impacted. Except for weed removals and spreading native seed no habitat restoration activities would be conducted within the canopy or Protected Zone of this tree.
7	Scrub Oak ( <i>Quercus berberidifolia</i> )	No impact. This protected tree is not located where the fill was placed.	No Impact. This protected native tree would not be impacted. Except for weed removals and spreading native seed no habitat restoration activities would be conducted within the canopy or Protected Zone of this tree.
8	Laurel Sumac ( <i>Malosma laurina</i> )	No impact. This protected tree is not located where the fill was placed.	No Impact. This protected native tree would not be impacted. Except for weed removals and spreading native seed no habitat restoration activities would be conducted within the canopy or Protected Zone of this tree.
9	Toyon ( <i>Heteromeles arbutifolia</i> )	No impact. This protected tree is not located where the fill was placed.	Potential Impact. The Protected Zone of Tree #9 would be encroached upon to remove the chain link fencing. This would affect less than 10% of the Protected Zone. Except for weed removals and spreading native seed no habitat restoration activities would be conducted within the canopy or Protected Zone of this tree.

## V. MITIGATION MEASURES

The placement of fill as well as the removal of the fill would encroach upon 23% of the Protected Zone of Tree #5, a laurel sumac. The removal of fill within the Protected Zone of Tree #5 shall be conducted using

hand tools. The LIP requires a 5:1 mitigation ratio for encroachments impacting 10% to 30% of the Protected Zone. To compensate for the encroachment into 23% of the Protected Zone of Tree #5, five (5) laurel sumac shrubs shall be provided onsite in accordance with the planting, monitoring, and reporting requirements specified in subsection K of Section 22.44.1920 of the LIP. **Table 3, Tree Mitigation** identifies the mitigation offset for the tree that would be impacted.

The original installation of the chain link fence as well as the removal of the chain link fencing would encroach into less than 10% of the Protected Zone of Tree #s 1 – 4 and Tree #9, which include four scrub oaks and a toyon. The removal of the fencing within the Protected Zone of these trees shall be conducted using hand tools. If roots are encountered while removing the fencing, roots shall be cut and managed in accordance with ANSI A-300 Standard Practices for Root Management. Because these activities would encroach into less than 10% of the Protection Zone of these trees, only monitoring and no replacement is required for impacts to these trees by subsection K of Section 22.44.1920 of the LIP.

The LIP requires that any encroachment of less than 30% into the Protected Zone of a protected tree be monitored annually for a period of not less than 10 years, and an annual monitoring report shall be submitted for review by the County for each of the 10 years. Should Trees #1, 2, 3, 4, 5, or 9 be lost or worsen in health or vigor because of project activities, the applicant shall mitigate the impact at a 10:1 ratio with seedling-sized trees.

**Table 3  
Tree Mitigation**

Tree #	Species	Trunk Diameter (inches)	Mitigation Offsets
5	Laurel Sumac	7.9, 6.3	5:1

The five (5) laurel sumac trees required to compensate for the encroachment impact to Tree #5 will be incorporated into the restoration plan prepared for the project, which shall include a native tree replacement planting program. The native tree replacement planting program shall specify replacement tree locations, tree or seedling size, planting specifications, and a monitoring program to ensure that the replacement planting program is successful, including performance standards and procedures for periodic monitoring and implementation of corrective measures in the event that the health of replacement trees declines.

**VI. TREE PROTECTION MEASURES**

The following tree protection measures are recommended to preserve the health of protected oaks and native trees on-site:

- 1) The applicant shall retain the services of a qualified independent biological consultant or arborist, approved by the Director to monitor the condition of protected native trees that are within or adjacent to the project area.
- 2) Before the commencement of project activities, temporary protective fencing shall be installed at the limits of the Protected Zones of oak and native trees within or adjacent to the project area that could be disturbed during project activities, including access routes and staging areas. The fencing shall be maintained in place for the duration of project activities that could impact the tree. If any breach in the protective fencing occurs, all work shall be suspended until the fence is repaired or replaced.
- 3) Soil levels within Protected Zones of oak and native trees shall be maintained at natural grade.

- 
- 4) Prune deadwood, broken branches and recommended structural pruning in accordance with International Society of Arboriculture, Pruning Standards and ANSI A-300 Pruning Guidelines.
  - 5) Cut roots in accordance with International Society of Arboriculture and ANSI A-300 Standard Practices for Root Management.
  - 6) Remove all trash and debris from the Protected Zones of oak and native trees. No materials are to be stored or discarded within the Protected Zone of any oak or native tree.
  - 7) All work performed within the Protected Zone of any oak or native tree shall be accomplished with hand tools only and must be monitored by the contracted biologist.
  - 8) The leaf-litter build-up under the canopy of the trees is ideal for healthy tree growth and root development. Do not alter or remove if possible. A 3-inch layer of mulch may be advisable in settings where leaf-litter has been lost.
  - 9) Do not remove the tags numbering each protected oak and native tree on the site.
  - 10) No vehicles shall be parked within the Protected Zone of any oak or native tree.

# **APPENDIX 1**

**Restoration (Fill Removal) and Erosion Control Plans,  
ACE Civil Engineering and SMS Geotechnical Solutions,  
March 3, 2023**



GENERAL NOTES

1. ALL GRADING AND CONSTRUCTION SHALL CONFORM TO THE 2017 COUNTY OF LOS ANGELES BUILDING CODES AND THE STATE MODEL WATER EFFICIENCY LANDSCAPE ORDINANCE UNLESS SPECIFICALLY NOTED ON THESE PLANS.

INSPECTION NOTES

16. THE PERMITTEE OR HIS AGENT SHALL NOTIFY THE BUILDING OFFICIAL AT LEAST ONE WORKING DAY IN ADVANCE OF REQUIRED INSPECTIONS AT FOLLOWING STAGES OF THE WORK (SECTION J105.7 OF THE BUILDING CODE):

DRAINAGE NOTES

22. ROOF DRAINAGE MUST BE DIVERTED FROM GRADED SLOPES.
23. PROVISIONS SHALL BE MADE FOR CONTINGUOUS DRAINAGE AT ALL TIMES.

AGENCY NOTES

26. AN ENCROACHMENT PERMIT FROM COUNTY OF LOS ANGELES DEPARTMENT OF PUBLIC WORKS (CALTRANS) (CITY OF \_\_\_\_\_) IS REQUIRED FOR ALL WORK WITHIN OR AFFECTING ROAD RIGHT OF WAY.

GENERAL GEOTECHNICAL NOTES

31. ALL WORK MUST BE IN COMPLIANCE WITH THE RECOMMENDATIONS INCLUDED IN THE GEOTECHNICAL CONSULTANT'S REPORT(S) AND THE APPROVED GRADING PLANS AND SPECIFICATIONS.

FILL NOTES

37. ALL FILL SHALL BE COMPACTED TO THE FOLLOWING MINIMUM RELATIVE COMPACTION CRITERIA:
a. 90 PERCENT OF MAXIMUM DRY DENSITY WITHIN 40 FEET BELOW FINISH GRADE.

PLANTING AND IRRIGATION NOTES

47. PLANTING AND IRRIGATION ON GRADED SLOPES MUST COMPLY WITH THE FOLLOWING MINIMUM GUIDELINES:
a. THE SURFACE OF ALL CUT SLOPES MORE THAN 4 FEET IN HEIGHT AND FILL SLOPES MORE THAN 3 FEET IN HEIGHT SHALL BE PROTECTED AGAINST EROSION BY PLANTING WITH GRASS OR GRASS/LEGUME PLANTS.

PUBLIC RIGHT OF WAY AND EASEMENTS

ENGINEER/SURVEYOR'S STATEMENT REGARDING THE PRESENCE OF MONUMENTS WITHIN PROJECT LIMITS

I HEREBY ATTEST THAT I HAVE LOCATED AND REFERENCED ON THESE PLANS THE MONUMENTS EXISTING PRIOR TO CONSTRUCTION TO ENSURE PERPETUATION OF THEIR LOCATION IN ACCORDANCE WITH SECTION 8771 OF THE BUSINESS AND PROFESSIONS CODE.

ENGINEER/SURVEYOR SEAL & SIGNATURE DATE 3-3-2023

PRIVATE/UTILITY EASEMENT

25. ANY PROPOSED WORK WITHIN A PRIVATE/UTILITY EASEMENT OR ACCESS EASEMENT REQUIRES PERMISSION LETTERS AND/OR COVENANTS FROM EASEMENT HOLDER. PERMISSION FROM THE EASEMENT HOLDER MAY NOT BE REQUIRED IF IT CAN BE SHOWN THE PROPOSED CONSTRUCTION WORK IS CONSISTENT AND IN CONFORMANCE WITH THE INTENDED EASEMENT USE.


THE FOLLOWING NOTE SHALL BE ADDED TO THE GRADING PLAN:

"GAS CIVIL ENGINEER/LAND SURVEYOR OF THIS PROJECT, I HAVE IDENTIFIED THE LOCATION OF ALL EASEMENTS WHICH ARE DEPICTED ON THESE PLANS. I HAVE REVIEWED THE PROPOSED EASEMENT DOCUMENTS AND VERIFIED THE PROPOSED CONSTRUCTION DOES NOT CONTACT OR INTERFERE WITH THE INTENDED EASEMENT USE."

CIVIL ENGINEER/LAND SURVEYOR (STAMP AND SIGNATURE) DATE 3-3-2023

UTILITIES

26. UTILITIES SUCH AS WATER, ELECTRICAL, PLUMBING, MECHANICAL, AND SEWER SHOWN ON GRADING PLANS MAY REQUIRE A SEPARATE PERMIT. A NOTE ON GRADING AND UTILITY PLANS WHICH LABELS THE UTILITIES ARE PROVIDED FOR REFERENCE ONLY AND SEPARATE PERMITS MAY BE REQUIRED.



Vicinity Map

Table with 3 columns: #, DATE, SUMMARY. Row 1: 1, 3-3-2023, updated plan.

Restoration Plan. 23333 SADDLE PEAK RD, MALIBU CA 90625. OWNER: NEMATOLLAH MOSTAJER.

GOLDEN PALACE CONSTRUCTION CO. INC. 20225 LOREZANA DR., Woodland Hills, CA 91364. PH: (818) 868-3530 CELL: (818) 599-5310

PRIVATE ENGINEER'S NOTES TO CONTRACTOR

THE EXISTANCE AND LOCATION OF ANY UNDERGROUND UTILITY PIPES, CONDUITS OR STRUCTURES SHOWN ON THESE PLANS IS OBTAINED BY A SEARCH OF THE AVAILABLE RECORDS, TO THE BEST OF OUR KNOWLEDGE THERE ARE NO EXISTING UTILITIES EXCEPT AS SHOWN ON THESE PLANS.

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITION DURING THE COURSE OF CONSTRUCTION OF THIS REQUIREMENT.

Scope of the restoration work

To remove all dumped dirt on the slope and the stockpile on the pad area that was documented by the latest survey map Done by Steve Opdahl Surveying on 8-14-2019 to be removed from the site to the local dump site with the soil engineer supervision

Professional Engineer Seal for Mike Masoodnia, State of California, License No. 40922, dated 3-3-2023.

LEGAL DESCRIPTION

Lot 1 tract 34964 record per Map Book Pagees 89to96 PARCEL Number (APN) 4438-039-001

LEGENT:

- EXISTING CONTOUR 90
PROPOSED CONTOURS (70)
TOP OF CURB TC
FLOW LINE FL

SHEET INDEX


Table with 2 columns: GRADING, GENERAL GRADING NOTES. Row 1: G-1of3, GRADING PLAN. Row 2: G-2of3, GRADING PLAN. Row 3: G-3of3, GRADING DETAIL.

ACE CIVIL ENGINEERING MIKE Masoodnia 18377 Beach Blvd, Suite 211 Huntington Beach, CA 92648 818 468 9020

SMS Geotechnical Solutions, INC. 5931 Leeon Place, Suite # 109 Carlsbad, CA 92010 S.Mehdi S.Shariati 760-331-8738

DRAWN BY: C.G. DATE: 9-16-2019. PROJECT: 14-081. SHEET NO. G 1of2. GENERAL NOTES

ATTACHMENTS



REVISIONS		
#	DATE	SUMMARY
1	3-3-2023	updated plan

**Restoration Plan**  
 23333 SADDLE PEAK RD.  
 MALIBU, CA 90265

DESCRIPTION:

OWNER:  
**NEMATOLLAH MOSTAJER**  
 20225 LORENZANA DR.  
 Woodland Hills, CA 91364  
 CELL: (818) 599-5310

**GOLDEN PALACE CONSTRUCTION CO. INC.**

20225 LORENZANA DR.  
 Woodland Hills, CA 91364  
 PH: (818) 888-3530 CELL: (818) 599-5310  
 Email: goldenpccc@aol.com; nmostajer@yahoo.com

**LEGAL DESCRIPTION.**  
 LOT 1 TRACT 34964 recorded per MAP BOOK 1088 Page 89 to 96

**ACE CIVIL ENGINEERING**  
 MIKE Masoodnia  
 18377 Beach Blvd. Suite 211  
 Huntington Beach CA 92648  
 818 468 9020




**SMS Geotechnical Solutions, INC.**  
 5931 Sea Lion Place, Suite # 109  
 Carlsbad, CA 92010  
 S.Mehdi s.Shariat 760 - 331 - 8738

DRAWN BY: C.G. DATE: 9-16-2019  
 CHECKED BY: PROJECT: 14-081

**Restoration Plan**

SCALE: 1/16"=1'

SHEET NO.  
 G 2 of 2



**SECTION A-A**  
 Scale: 1"=20' Vert.  
 1"=30' Horz.

**BENCHMARK:**

DESIGNATION: DY12411  
 ELEVATION: 2413.60'  
 DESCRIPTION: E'LY EDGE OF 2" IRON PIPE, UP 1" W/ CONCRETE PLUG AND DPW TAG

Project No. GI-7-14-8  
 March 3, 2023

**SMS GEOTECHNICAL SOLUTIONS, INC.**  
 Consulting Geotechnical Engineers  
 5931 Sea Lion Place, Suite 109  
 Carlsbad, California 92010  
 Office: 760-602-7815  
 smsgeosol.inc@gmail.com

Mr. Nemat Mostajer  
 225 Lorenza Drive  
 Woodland Hills, California 91364

Geotechnical Update Letter  
 Proposed Slope Restoration project, 23333 Saddle Peak Road, Malibu, California Page 2

We appreciate this opportunity to be of service to you again. Should you have any questions concerning this update letter, please do not hesitate to contact this office. Reference to our Project No. GI-7-14-8 will help to expedite our response to your inquiries.

**SMS Geotechnical Solutions, Inc.**

Mehdi S. Shariat, GE #2885  
 Distribution: Addressee (email)  
 ACE Engineering (email)



IN AREA OF CRITICAL DESIGN, TOPOGRAPHICAL FEATURES SHOULD BE VERIFIED PRIOR TO FINAL DESIGN.

SURVEY MONUMENTS FOUND IN THE COURSE OF THIS SURVEY ARE SET BY OTHERS, AND HAVE BEEN USED AS REFERENCE FOR THE PLOTTING OF RECORD BOUNDARY INFORMATION.

THIS SURVEY WAS PREPARED WITHOUT THE BENEFIT OF A TITLE REPORT. EASEMENTS, IF ANY, ARE NOT SHOWN ON THIS MAP.

BUILDING MEASUREMENTS ARE NOT TO FOUNDATION, UNLESS NOTED, AND ARE MEASURED TO BUILDING EXTERIOR. I.E. STUCCO, WOOD SIDING AND/OR BRICK VENEER.

**GEOTECHNICAL UPDATE LETTER, PROPOSED SLOPE RESTORATION PROJECT, 23333 SADDLE PEAK ROAD, MALIBU, CALIFORNIA (APN 4438-039-001)**

This letter is to confirm that geotechnical conditions at the above-referenced property have remained substantially unchanged. The following reports prepared by this office in support of the project (the reference reports are on file with our firm and copies can be obtained upon request), are still valid.



1. "Clarification Letter And Response to Review Comments, Proposed Site Restoration, 23333 Saddle Peak Road, Malibu, California (APN 4438-039-001)," Project No. GI-7-14-8, dated January 8, 2020.
2. "Geotechnical Update Letter, Proposed Slope Restoration, 23333 Saddle Peak Road, Malibu, California (APN 4438-039-001)," Project No. GI-7-14-8, dated May 7, 2019.
3. Response to Geotechnical Review Comments, Proposed Slope Restoration, 23333 Saddle Peak Road, Malibu, California, Project No. GI-7-14-8, dated July 10, 2015.
4. "Geotechnical Plan Review Update, Proposed Slope Restoration, 23333 Saddle Peak Road, Malibu, California (APN 4438-039-001)," Project No. GI-7-14-8, dated May 4, 2015.
5. Geotechnical Investigation Update And Response to County of Los Angeles Reviews, Existing Graded Residential Building Pad, 23333 Saddle Peak Road, Malibu, California (APN 4438-039-001)," Project No. GI-7-14-8, dated September 8, 2014.

All conclusions and recommendations provided the referenced report stayed unchanged and should be considered in the project designs and implemented during the construction phase, where appropriate and as applicable.


**LEGEND:**

- EXISTING CONTOURS ..... 100
- PROPOSED CONTOURS ..... (100)
- TOP OF CURB ..... T.C.
- FLOW LINE ..... F.L.
- CARAC® FLOOR ..... G.F.
- BACK OF WALL ..... B.W.
- FINISHED SURFACE ..... F.S.
- TOP OF GRATE ..... T.G.
- TOP OF WALL ..... T.W.
- CATCH BASIN ..... C.B.
- DAYLIGHT ..... D.L.





**SECTION A-A**  
Scale: 1"=20' Vert.  
1"=30' Horz.



**BENCHMARK:**  
DESIGNATION: DY12411  
ELEVATION: 2413.60'  
DESCRIPTION: ELY EDGE OF 2" IRON PIPE, UP 1" W/ CONCRETE PLUG AND DPW TAG

- EROSION AND SEDIMENT CONTROL PLAN (ESCP) GENERAL NOTES:**
- In case of emergency, call Mr. Nemat Mostajer at 818-599-5310
  - Total Disturbed Area: 4850 S.F. WDD# 1 Risk Level 1 2 3 (circle one as determined by State General Permit for sites greater than 1 acre)
  - A stand-by crew for emergency work shall be available at all times during the rainy season (November 1 to April 15). Necessary materials shall be available on-site and stockpiled at convenient locations to facilitate rapid construction of emergency devices when rain is imminent.
  - Erosion control devices shown on this plan may be removed when approved by the Building Official if the grading operation has progressed to the point where they are no longer required.
  - Graded areas adjacent to fill slopes located at the site perimeter must drain away from the top of slope at the conclusion of each working day. All loose soils and debris that may create a potential hazard to off-site property shall be stabilized or removed from the site on a daily basis.
  - All silt and debris shall be removed from all devices within 24 hours after each rainstorm and be disposed of properly.
  - A guard shall be posted on the site whenever the depth of water in any device exceeds two feet. The device shall be drained or pumped dry within 24 hours after each rainstorm. Pumping and draining of all basins and drainage devices must comply with the appropriate BMP for dewatering operations.
  - The placement of additional devices to reduce erosion damage and contain pollutants within the site is left to the discretion of the Field Engineer. Additional devices as needed shall be installed to retain sediments and other pollutants on site.
  - Detrital basins may not be removed or made inoperable between November 1 and April 15 of the following year without the approval of the Building Official.
  - Storm Water Pollution and Erosion Control devices are to be modified, as needed, as the project progresses, the design and placement of these devices is the responsibility of the field engineer. Plans representing changes must be submitted for approval if requested by the Building Official.
  - Every effort should be made to eliminate the discharge of non-storm water from the project sites at all times.
  - Eroded sediments and other pollutants must be retained on-site and may not be transported from the site via sheet flow, swales, area drains, natural drainage courses, or wind.
  - Stockpiles of earth and other construction-related materials must be protected from being transported from the site by the forces of wind or water.
  - Fuels, oils, solvents, and other toxic materials must be stored in accordance with their listing and are not to contaminate the soils and surface waters. All approved storage containers are to be protected from the weather. Spills must be cleaned up immediately and disposed of in a proper manner. Spills may not be washed into the drainage system.
  - Excess or waste concrete may not be washed into the public way or any other drainage system. Provisions shall be made to retain concrete wastes on-site until they can be disposed of as solid waste.
  - Developers/contractors are responsible to inspect all Erosion Control Devices and BMPs are installed and functioning properly if there is a 50% or greater probability of predicted precipitation, and after actual precipitation. A construction site inspection checklist and inspection log shall be maintained at the project site at all times and available for review by the Building Official (copies of the self-inspection check list and inspection logs are available upon request).

- Trash and construction-related solid wastes must be deposited into a covered receptacle to prevent contamination of rainwater and disposal by wind.
  - Sediments and other materials may not be tracked from the site by vehicle traffic. The construction entrance roadways must be stabilized so as to inhibit sediments from being deposited into the public way. Accidental depositions must be swept up immediately and may not be washed down by rain or other means.
  - Any slopes with disturbed soils or denuded of vegetation must be stabilized so as to inhibit erosion by wind and water.
  - As the engineer/QSD of record, I have selected appropriate BMPs to effectively minimize the negative impacts of this project's construction activities on storm water quality. The project owner and contractor are aware that the selected BMPs must be installed, monitored, and maintained to ensure their effectiveness.
- Civil Engineer/QSD Signature: *[Signature]* Date: 11-15-19
- As the project owner or authorized agent of the owner, I certify that this document and all attachments were prepared under my direction or supervision in accordance with the system designed to ensure that a qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is true, accurate, and reflects current conditions, or failing to properly and/or adequately implement the ESCP may result in revocation of grading and/or other permits or other sanctions provided by law.
- Mr. Nemat Mostajer  
Owner or Authorized Representative (Permittee) Date: 11-20-19
- Developers/contractors are responsible to inspect all Erosion Control Devices and BMPs are installed and functioning properly as required by the State Construction General Permit. A construction site inspection checklist and inspection log shall be maintained at the project site at all times and available for review by the Building Official.
  - The following BMPs from the "2009 Construction BMP Handbook/Portal" must be implemented for all construction activities as applicable. As an alternative, details from "Caltrans Stormwater Quality Handbooks, Construction Site Best Management Practices (BMP) Manual" may be used. Additional measures may be required if deemed appropriate by the Building Official.

- EROSION CONTROL**
- EC1 - SCHEDULING
  - EC2 - PRESERVATION OF EXISTING VEGETATION
  - EC3 - HYDRAULIC MULCH
  - EC4 - HYDROSEEDING
  - EC5 - SOIL BINGERS
  - EC6 - STRAW MULCH
  - EC7 - GEOTEXTILES & MATS
  - EC8 - WOOD MULCHING
  - EC9 - EARTH DIMES AND DRAINAGE SWALES
  - EC10 - VELOCITY DISSIPATION DEVICES
  - EC11 - SLOPE DRAINS
  - EC12 - STREAMBANK STABILIZATION
  - EC13 - RESERVED
  - EC14 - COMPOST BLANKETS
  - EC15 - SOIL PREPARATION/ROUGHENING
  - EC16 - NON-VEGETATED STABILIZATION
- TEMPORARY TRACKING CONTROL**
- T1 - STABILIZED CONSTRUCTION ENTRANCE EXIT
  - T2 - STABILIZED CONSTRUCTION ROADWAY
  - T3 - ENTRANCE/OUTLET TIRE WASH
- NON-STORMWATER MANAGEMENT**
- NS1 - WATER CONSERVATION PRACTICES
  - NS2 - DEWATERING OPERATIONS
  - NS3 - PAVING AND GRINDING OPERATIONS
  - NS4 - TEMPORARY STREAM CROSSING
  - NS5 - CLEAR WATER DIVERSION
  - NS6 - ILLICIT CONNECTION/DISCHARGE
  - NS7 - POTABLE WATER IRRIGATION
  - NS8 - VEHICLE AND EQUIPMENT CLEANING
  - NS9 - VEHICLE AND EQUIPMENT FUELING
  - NS10 - VEHICLE AND EQUIPMENT MAINTENANCE
  - NS11 - PILE DRIVING OPERATIONS
  - NS12 - CONCRETE CURING
  - NS13 - CONCRETE FINISHING
  - NS14 - MATERIAL AND EQUIPMENT USE
  - NS15 - DEMOLITION ADJACENT TO WATER
  - NS16 - TEMPORARY BATCH PLANTS
- WASTE MANAGEMENT & MATERIAL POLLUTION CONTROL**
- WM1 - MATERIAL DELIVERY AND STORAGE
  - WM2 - MATERIAL USE
  - WM3 - STOCKPILE MANAGEMENT
  - WM4 - SPILL PREVENTION AND CONTROL
  - WM5 - SOIL WASTE MANAGEMENT
  - WM6 - HAZARDOUS WASTE MANAGEMENT
  - WM7 - CONTAMINATION SOIL MANAGEMENT
  - WM8 - CONCRETE WASTE MANAGEMENT
  - WM9 - SANITARY/SEPTIC WASTE MANAGEMENT
  - WM10 - LIQUID WASTE MANAGEMENT
- WIND EROSION CONTROL**
- WE1 - WIND EROSION CONTROL

IN AREA OF CRITICAL DESIGN, TOPOGRAPHICAL FEATURES SHOULD BE VERIFIED PRIOR TO FINAL DESIGN.

SURVEY MONUMENTS FOUND IN THE COURSE OF THIS SURVEY ARE SET BY OTHERS, AND HAVE BEEN USED AS REFERENCE FOR THE PLOTTING OF RECORD BOUNDARY INFORMATION.

THIS SURVEY WAS PREPARED WITHOUT THE BENEFIT OF A TITLE REPORT, EASEMENTS, IF ANY, ARE NOT SHOWN ON THIS MAP.

BUILDING MEASUREMENTS ARE NOT TO FOUNDATION, UNLESS NOTED, AND ARE MEASURED TO BUILDING EXTERIOR, I.E. STUCCO, WOOD SIDING AND/OR BRICK VENEER.

- LEGEND:**
- EXISTING CONTOURS ----- 100
  - PROPOSED CONTOURS ----- (100)
  - TOP OF CURB ----- T.C.
  - FLOW LINE ----- F.L.
  - CARAGE FLOOR ----- C.F.
  - BACK OF WALL ----- B.W.
  - FINISHED SURFACE ----- F.S.
  - TOP OF GRATE ----- T.G.
  - TOP OF WALL ----- T.W.
  - CATCH BASIN ----- C.B.
  - DAYLIGHT ----- D.L.




REVISIONS		
#	DATE	SUMMARY
1	3-3-2023	updated plan
2		
3		

**Erosion Control & Landscaping Plan**  
Restoration Plan  
23333 SADDLE PEAK RD.  
MALIBU, CA 90265

OWNER: NEMATOLLAH MOSTAJER  
20225 LORENZANA DR.  
Woodland Hills, CA 91364  
CELL: (818) 599-5310

**GOLDEN PALACE CONSTRUCTION**  
CO. INC.

20225 LORENZANA DR.  
Woodland Hills, CA 91364  
PH: (818) 888-3530 CELL: (818) 599-5310  
Email: goldenpcc@aol.com; nmostajer@yahoo.com



**LEGAL DESCRIPTION.**  
LOT 1 TRACT 34964 recorded per MAP BOOK 1088 Page 89 to 96

**ACE CIVIL ENGINEERING**  
MIKE Masoodnia  
18377 Beach Blvd, Suite 211  
Huntington Beach CA 92648  
818 468 9020

**SMS Geotechnical Solutions, INC.**  
5531 Sea Lion Place, Suite # 109  
Carlsbad, CA 92010  
S.Mehdi S.Shariati 760-331-8738

DRAWN BY: C.G. DATE: 9-16-2019  
CHECKED BY: PROJECT: 14-081

**Erosion Control**  
SCALE: 1/16"=1'  
SHEET NO. E 1 of 1

**APPENDIX 2**  
**Field Observation Definitions**

## SUMMARY OF FIELD OBSERVATIONS DEFINITIONS

The following provides a reference for terms and ratings used on the survey datasheet and criteria used during the evaluation process of the oak and native tree survey.

### FORM

- Tree Number - each tree of ordinance size surveyed within the field has been assigned a number. This assigned number corresponds to a tree location on the “Tree Location and Impact Map”.
- Species - the identity of the tree being evaluated
- Tree Height - approximate height of tree
- Lean - indicates the direction the tree is leaning from vertical
- Trunk Diameter - diameter of trunk as measured from 4 ½ feet above natural grade

### PHYSICAL CONDITION

- Trunk Cavity - hollow area in a trunk
- Trunk Exudation - substance secreting or oozing from the trunk or branches
- Trunk Damage - damaged area on a trunk
- Buried Root Collar - root collar of tree is covered with soil or other material
- Exposed Roots - roots belonging to the subject tree are exposed unnaturally above the soil
- Weak Crotch - poorly formed branch attachments
- Fungal Disease - evidenced by the presence of fruiting bodies
- Insect Damage - evidenced by presence of insect frass, boring holes, chewed leaves, etc.
- Fire Damage (New/Old) - the extent of structural damage caused from fire
- Branch Cavities - hollow spaces along the branches
- Mainstem Dieback - death of the mainstem(s) from the tips towards the center
- Twig/Branch Dieback - death of twigs or branches in the tree crown from the tips towards the center
- Epicormic Growth - shoots growing from the trunk, stem, or branch of a tree
- Thin Foliage - canopy defoliation and/or twig dieback
- Drought Stressed - thin canopy, wilted and/or yellowed leaves, marginal necrosis in leaves, etc.
- Unbalanced Crown - asymmetrical canopy
- Excessive Horizontal Branching - tree exhibiting increased levels of horizontal branching not characteristic of the species
- Vigor - capacity to grow and resist stress
- Terrain - surface the tree is growing on, slope or level.

### *Health*

Tree health was determined by visually inspecting the tree for signs of disease and pests and canopy density. The following rationale for determining health grades is as follows:

- **A (Excellent)** = A healthy tree typical of species. Individual shows no visible signs of disease or pest infestation. Canopy density 90 - 100%.
- **B (Above Average)** = A healthy tree typical of species with minimal visible signs of disease or pest infestation. Canopy density 80 - 100%.
- **C (Average)** = Appears visually healthy with visible signs of disease or pest infestation typical of the species. Canopy density 60 - 79%.

- 
- **D (Poor/Declining)** = Significant signs of disease or pest infestation or structural instability. Shows extensive signs of twig and branch dieback. Canopy density 20 - 59%.
  - **F (Dead/Dying)** = Exhibits no signs of new growth or evidence of live tissue. Shows extensive signs of twig and branch dieback. Canopy density < 20%

### *Vigor*

The vigor of a tree is the capacity for growth and continued survival. Observable growth characteristics used to determine the following vigor ratings are described below.

- **Good** = Evidence of new growth, healthy leaf color, and bark is relatively free of uncharacteristic cracks and decay.
- **Moderate** = Very little evidence of new growth, minor unseasonal browning and thinning of foliage, and galls may be present.
- **Poor** = No evidence of new growth, unhealthy leaf and bark color, large amounts of deadwood, and severely unseasonal thinned canopy.

### *Aesthetics and Conformity*

The aesthetics of a tree is an overall inspection of the appearance based on type specimens of the subject species and value it adds to the surrounding landscape. The ratings and characteristics used during this process include the following:

- **A (Excellent)** Visually symmetrical and balanced, exhibits the ideal appearance and form for this species.
- **B (Average)** = Although, not symmetrical is visually appealing exhibiting very little canopy dieback and deadwood.
- **C (Below Average)** = Non-symmetrical and/or is visually unappealing exhibiting substantial canopy dieback and deadwood.
- **D (Poor)** = Displays few characteristics that are visually appealing.

**APPENDIX 3**  
**Tree Survey Data Forms**

PROJECT: 23333 Saddle Peak Rd DATE: 6/9/22

PREPARER: J. Anderson  
C. Cesa

TREE NUMBER		#1
SPECIES	Quercus agrifolia	
	Quercus lobata	
	Quercus berberidifolia	✓
	Other	
FORM	TREE HEIGHT (~ FEET)	18.
	LEAN	F
	TRUNK DIAMETER / CIRCUMFERENCE (INCHES)	6.5
		8.3
	multistem	
Total:	14.8	
PHYSICAL CONDITION	TRUNK CAVITY	
	TRUNK EXUDATION	
	TRUNK DAMAGE	
	BURIED ROOT COLLAR	
	EXPOSED ROOTS	
	WEAK CROTCH	
	FUNGAL DISEASE	
	INSECT DAMAGE	
	FIRE DAMAGE (NEW/OLD)	
	BRANCH CAVITIES	✓
	MAINSTEM DIEBACK	
	TWIG/BRANCH DIEBACK	✓
	EPICORMIC GROWTH	✓
	THIN FOLIAGE	
	DROUGHT STRESSED	
	UNBALANCED CROWN	
	EXC. HORIZONTAL BRANCH.	
	VIGOR (GOOD/MOD/POOR)	MOD
	TERRAIN (SLOPE/LEVEL)	SLOPE
TREATMENT	REMOVE DEADWOOD	
	INSECT TREATMENT	
	DISEASE TREATMENT	
	SAFETY PRUNE	
RATING	HERITAGE	
	HEALTH	B
	AESTHETICS & CONFORMITY	B
<p>NOTES: Exposure: full sun  <del>Small</del> Part of small patch of scrub-oaks. Woodpecker activity, numerous holes            Soil at base of tree excavated to show 2 main stems are part of the same tree.</p>		
NOTES:		
NOTES:		

Photos: 4430-31



PROJECT: 23333 Saddle Peak DATE: 6/9/22

PREPARER: J. Anderson  
C. Cesa

		TREE NUMBER	# 2				
SPECIES		<i>Quercus agrifolia</i>		NOTES: Tree is part of small stand of scrub oaks. Numerous woodpecker holes. Exposure - full sun			
		<i>Quercus lobata</i>					
		<i>Quercus berberidifolia</i>	✓				
		Other					
FORM		TREE HEIGHT (~ FEET)	15				
		LEAN	S				
		TRUNK DIAMETER / CIRCUMFERENCE (INCHES)	6.3				
PHYSICAL CONDITION		TRUNK CAVITY	✓				
		TRUNK EXUDATION					
		TRUNK DAMAGE	✓				
		BURIED ROOT COLLAR					
		EXPOSED ROOTS					
		WEAK CROTCH					
		FUNGAL DISEASE					
		INSECT DAMAGE					
		FIRE DAMAGE (NEW/OLD)					
		BRANCH CAVITIES	✓				
		MAINSTEM DIEBACK					
		TWIG/BRANCH DIEBACK	✓				
		EPICORMIC GROWTH	✓				
		THIN FOLIAGE					
		DROUGHT STRESSED					
		UNBALANCED CROWN	✓				
		EXC. HORIZONTAL BRANCH.					
		VIGOR (GOOD/MOD/POOR)	MOD				
	TERRAIN (SLOPE/LEVEL)	SLOPE					
TREATMENT		REMOVE DEADWOOD					
		INSECT TREATMENT					
		DISEASE TREATMENT					
		SAFETY PRUNE					
RATING		HERITAGE					
		HEALTH	A				
		AESTHETICS & CONFORMITY	B				
				NOTES:			
				NOTES:			

Photos: 4432-33

PROJECT: 23333 Saddle Peak Rd DATE: 6/9/22

PREPARER: J. Anderson  
C. Cesa

		TREE NUMBER	#3
SPECIES		<i>Quercus agrifolia</i>	
		<i>Quercus lobata</i>	
		<i>Quercus berberidifolia</i>	✓
		Other	
FORM	TREE HEIGHT (~ FEET)	18	
	LEAN	SW	
	TRUNK DIAMETER / CIRCUMFERENCE (INCHES)	6.2 2.8	
	multistem total:	9.0	
PHYSICAL CONDITION	TRUNK CAVITY		
	TRUNK EXUDATION		
	TRUNK DAMAGE	✓	
	BURIED ROOT COLLAR		
	EXPOSED ROOTS		
	WEAK CROTCH		
	FUNGAL DISEASE		
	INSECT DAMAGE	✓	
	FIRE DAMAGE (NEW/OLD)		
	BRANCH CAVITIES		
	MAINSTEM DIEBACK	✓	
	TWIG/BRANCH DIEBACK	✓	
	EPICORMIC GROWTH		
	THIN FOLIAGE		
	DROUGHT STRESSED		
	UNBALANCED CROWN		
EXC. HORIZONTAL BRANCH.			
VIGOR (GOOD/MOD/POOR)	MOD		
TERRAIN (SLOPE/LEVEL)	SLOPE		
TREATMENT	REMOVE DEADWOOD	✓	
	INSECT TREATMENT <i>Remove stem</i>	✓	
	DISEASE TREATMENT		
	SAFETY PRUNE		
RATING	HERITAGE		
	HEALTH	B	
	AESTHETICS & CONFORMITY	B	
<p>NOTES: Lower, small mainstem is heavily shaded and dying, and appears to have been cut. Woodpecker activity - numerous holes in dying stem from exposure - full sun. Tree is part of small stand of scrub oaks. Wood boring insects.</p>			
<p>NOTES:</p>			
<p>NOTES:</p>			

Photos: 4435-36

PROJECT: 2333 Saddle Peak Rd

DATE: 6/9/22

PREPARER: J. Anderson  
C. Cesa

	TREE NUMBER	#4				
SPECIES	Quercus agrifolia					
	Quercus lobata					
	Quercus berberidifolia	✓				
	Other					
FORM	TREE HEIGHT (~ FEET)	17				
	LEAN	SW				
	TRUNK DIAMETER / CIRCUMFERENCE (INCHES)	6.4				
PHYSICAL CONDITION	TRUNK CAVITY					
	TRUNK EXUDATION					
	TRUNK DAMAGE					
	BURIED ROOT COLLAR					
	EXPOSED ROOTS					
	WEAK CROTCH					
	FUNGAL DISEASE					
	INSECT DAMAGE					
	FIRE DAMAGE (NEW/OLD)					
	BRANCH CAVITIES					
	MAINSTEM DIEBACK					
	TWIG/BRANCH DIEBACK	✓				
	EPICORMIC GROWTH					
	THIN FOLIAGE					
	DROUGHT STRESSED					
	UNBALANCED CROWN					
	EXC. HORIZONTAL BRANCH.					
	TREATMENT	REMOVE DEADWOOD				
INSECT TREATMENT						
DISEASE TREATMENT						
SAFETY PRUNE						
RATING	HERITAGE					
	HEALTH	A				
	AESTHETICS & CONFORMITY	B				

NOTES: Tree is part of small stand of scrub oaks  
Exposure: Full Sun

NOTES:

NOTES:

Photo: 4434

PROJECT: 23333 Saddle Peak Rd DATE: 6/9/22

PREPARER: J. Anderson  
C. Cesa

TREE NUMBER		#6
SPECIES	Quercus agrifolia	
	Quercus lobata	
	Quercus berberidifolia	✓
	Other	
FORM	TREE HEIGHT (~ FEET)	13
	LEAN	F
	TRUNK DIAMETER / CIRCUMFERENCE (INCHES)	6.2
PHYSICAL CONDITION	TRUNK CAVITY	
	TRUNK EXUDATION	
	TRUNK DAMAGE	
	BURIED ROOT COLLAR	
	EXPOSED ROOTS	
	WEAK CROTCH	
	FUNGAL DISEASE	
	INSECT DAMAGE	
	FIRE DAMAGE (NEW/OLD)	
	BRANCH CAVITIES	
	MAINSTEM DIEBACK	
	TWIG/BRANCH DIEBACK	✓
	EPICORMIC GROWTH	✓
	THIN FOLIAGE	
	DROUGHT STRESSED	
	UNBALANCED CROWN	
	EXC. HORIZONTAL BRANCH.	
	VIGOR (GOOD/MOD/POOR)	MOD
TERRAIN (SLOPE/LEVEL)	SLOPE	
TREATMENT	REMOVE DEADWOOD	
	INSECT TREATMENT	
	DISEASE TREATMENT	
	SAFETY PRUNE	
RATING	HERITAGE	
	HEALTH	B
	AESTHETICS & CONFORMITY	B
NOTES: Another stem close to this tree treated as separate tree <del>but</del> and dbh of next tree is 6.9" so not a scrub oak woodland, exposure: full sun		
NOTES:		
NOTES:		

Photos: 4441-42

PROJECT: 23333 Saddle Reaks <sup>Pal.</sup> DATE: 6/9/22

PREPARER: J. Anderson  
C. Cesca

	TREE NUMBER	#7				
SPECIES	Quercus agrifolia					
	Quercus lobata					
	Quercus berberidifolia	✓				
	Other					
FORM	TREE HEIGHT (~ FEET)	14				
	LEAN	None				
	TRUNK DIAMETER / CIRCUMFERENCE (INCHES)	4.1				
		4.1				
	multiten Total: 8.2					
PHYSICAL CONDITION	TRUNK CAVITY					
	TRUNK EXUDATION					
	TRUNK DAMAGE					
	BURIED ROOT COLLAR <sup>due to</sup> <sub>Slope</sub>	✓				
	EXPOSED ROOTS					
	WEAK CROTCH					
	FUNGAL DISEASE					
	INSECT DAMAGE					
	FIRE DAMAGE (NEW/OLD)					
	BRANCH CAVITIES					
	MAINSTEM DIEBACK					
	TWIG/BRANCH DIEBACK	✓				
	EPICORMIC GROWTH	✓				
	THIN FOLIAGE					
	DROUGHT STRESSED					
	UNBALANCED CROWN					
	EXC. HORIZONTAL BRANCH.					
	VIGOR (GOOD/MOD/POOR)	GOOD				
TERRAIN (SLOPE/LEVEL)	SLOPE					
TREATMENT	REMOVE DEADWOOD					
	INSECT TREATMENT					
	DISEASE TREATMENT					
	SAFETY PRUNE					
RATING	HERITAGE					
	HEALTH	A				
	AESTHETICS & CONFORMITY	A				

NOTES: Exposure: Full sun.

NOTES:

NOTES:

Photos: 4443 & 4448