

Revised Draft SEIR Appendix 5.5h

Hasley Canyon Creek CLOMR





**LAND DEVELOPMENT DIVISION
STORM DRAIN & HYDROLOGY UNIT**

TO: PACE Advanced Water Engineering
ATTN: Jose Cruz
CC: Christine Huch

DATE 6/4/25

REVIEW OF HYDROLOGY STUDY

PM NO. 18108

DATE OF REPORT January 2025
PLAN CASE NO. ESTU2023000284

The FEMA Conditional Letter of Map Revision has been approved.

REVIEWED BY 
Lonnie Chung – (626) 458-7102

APPROVED BY: 
Alex Mikhailpoor

FEMA Application – Conditional Letter of Map Revision

Hasley Canyon Creek Soil Cement Bank Protection Valencia Commerce Center TPM No. 18108 ESTU No. 2023000284

January 2025
(Revised August 2024)
(Revised May 2023)

Prepared For:



FivePoint Communities, LLC
25124 Springfield Court
Valencia, CA 91335

FLOODPLAIN/WAY STUDY APPROVED

REVIEWED BY: _____ DATE 6/4/25

APPROVED BY: _____ DATE 6/4/25

COUNTY OF LOS ANGELES DEPARTMENT OF PUBLIC WORKS
LAND DEVELOPMENT DIVISION

Prepared By:



Pacific Advanced Civil Engineering, Inc.
17520 Newhope Street, Suite 200
Fountain Valley, CA 92708
714-481-7300

Contact Person:

Jose Cruz, MS, PE
Emily Randig, MS, EIT



PACE JN A535

Table of Contents

1 Introduction	1-1
1.1 Project Background and Description	1-1
2 Model Background and Development.....	2-1
2.1 Hydrology	2-1
2.2 HEC-RAS Model Development	2-1
2.2.1 FEMA Effective Model.....	2-1
2.2.2 Model Preparation	2-1
2.2.3 Model Overview.....	2-2
2.3 Summary of CLOMR HEC-RAS Models	2-4
3 Sediment Transport Considerations	3-1
3.1 Introduction.....	3-1
3.1.1 Types of Adjustment	3-1
4 Proposed Hasley Canyon Creek Modifications and Improvements	4-1
4.1 Rock Chute and Stilling Basin.....	4-1
4.2 Grade Control Structures	4-1
4.3 Franklin Parkway Bridge	4-1
4.4 Modifications to the Existing Berm	4-1
4.5 Soil Cement Bank Protection	4-2
4.5.1 Design of Soil Cement Bank Protection	4-2
4.6 Channel Freeboard Requirements.....	4-3
4.7 Bank Protection Toe-Down Design Summary	4-5
5 Hydraulic Analysis Results	5-1
5.1 Baseline Corrected Effective Hydraulic Analysis	5-1
5.2 Proposed Condition Hydraulic Analysis	5-2
5.3 Hydraulic Analysis Results and Floodplain Discussion	5-4
6 Conclusion.....	6-1
References	R-1

Tables

Table 2-1: Hasley Canyon Creek Design Hydrology	2-1
Table 4-1: “West” Bank Soil Cement Bank Protection Freeboard Summary.....	4-3
Table 4-2: “East” Bank Soil Cement Bank Protection Freeboard	4-4
Table 5-1: Flow Depth and Velocity Comparison for the Duplicate Effective and Corrected Effective ($Q_{100} = 1,640/ 820$ cfs)	5-1
Table 5-2: Flow Depth and Velocity Comparison for Corrected Effective and Proposed Condition ($Q_{100} = 1,640/820$ cfs)	5-3
Table 5-3: Tie-In Analysis for the Effective and Proposed Condition ($Q_{100} = 1,640/820$ cfs)	5-4

Figures

Figure 1-1: Project Location Map	1-2
Figure 1-2: Proposed Soil Cement Vicinity Map	1-3
Figure 6-1: Annotated FIRM.....	6-2

Exhibits

Exhibit 1: Proposed Soil Cement Configuration

Exhibit 2: Effective vs Corrected Effective and Effective vs Proposed Condition HEC-RAS Cross Section Comparison

Exhibit 3: Corrected Effective and Proposed Condition HEC-RAS Workmap

Exhibit 4: Proposed Drop Structure

Exhibit 5: Proposed Modification of Diversion Berm

Exhibit 6: “West” Bank Soil Cement Bank Protection Plan and Profile

Exhibit 7: “East” Bank Soil Cement Bank Protection Plan and Profile

Exhibit 8: Topographic Workmap

Appendices

A. MT-2 Forms

Form 1 - Overview & Concurrence Form

Form 2 - Riverine Hydrology and Hydraulics Form

Form 3 - Riverine Structures Form

B. Relevant Effective FEMA Data

a. Flood Insurance Study (FIS) Excerpts

b. FEMA Flood Insurance Rate Map Panels

c. LOMR, October 2021

C. HEC-RAS Effective Hydraulic Results

D. HEC-RAS Corrected Effective Condition Hydraulic Results

E. HEC-RAS Proposed Condition Hydraulic Results

F. As Built Drawings for Commerce Center Drive

G. As Built Drawings for the Flow Diversion Berm

H. ESA Documentation

1 Introduction

Please find enclosed an application for a Conditional Letter of Map Revision (CLOMR) for the Hasley Canyon Creek Soil Cement Bank Protection Project along Hasley Canyon Creek. The project is located within the unincorporated area of Los Angeles County, three miles west of the City of Santa Clarita, as shown on the vicinity map in **Figure 1-1**. The study reach of Hasley Canyon Creek for this project extends approximately 5,000-ft, from approximately 600 feet downstream of the Commerce Center Drive Bridge over Hasley Canyon Creek to approximately 500 feet downstream of the Hasley Canyon Creek confluence with Castaic Creek. The project involves the implementation of soil cement bank protection improvements for the Valencia Commerce Center (VCC) Industrial Park Development in Tentative Parcel Map (TPM) No. 18108. See **Figure 1-2** for a vicinity map of the project site locations and existing rip-rap and soil cement. The proposed project is located within a FEMA special flood hazard area (SFHA) Zone AE. The AE zone indicates base flood elevations have been established by a previous study.

The effective FEMA Flood Insurance Rate Map (FIRM) panels in the Hasley Canyon Creek study area are numbered 06037C0785G, 06037C0805G, and 06037C0815G and were all revised in June 2021. A subsequent Letter of Map Revision (LOMR) updated the FIRM's at the Hasley Canyon Creek and Castaic Creek confluence and downstream of Commerce Center Drive Bridge, effective October 15, 2021.

The present CLOMR application is in support of a request for the revision of FEMA Flood Insurance Rate Map (FIRM) panels 06037C0805G, as shown on the Effective FIRM panels provided in **Appendix B**. The Hasley Canyon Creek Soil Cement Bank Protection project incorporates more current 2013 topographic data to establish a new hydraulic analysis using HEC-RAS version 6.2.

1.1 Project Background and Description

The Valencia Commerce Center (VCC) Industrial Park Development in Tentative Parcel Map (TPM) No. 18108 will consist of buried soil cement bank protection, a proposed drop structure/stilling basin, two grade control structures, the Franklin Parkway Bridge over Hasley Canyon Creek, and modifications to the existing concrete/rip-rap lined berm (P.D. 2298 Unit III). A more detailed layout of the proposed soil cement bank protection and structures is shown on **Exhibit 1**. Design and analysis of these proposed improvements are described in detail in *Drainage Concept Report Volume III of V, Hasley Canyon Creek Bank Protection, EIMP No. 2019000489*, which was approved by LACPW in March 2022 (PACE, October 2021).


- (1) **Proposed Soil Cement Bank Protection** – approximately 3,000 linear feet (LF) of buried soil cement along the east and west bank of Hasley Canyon Creek. At the upstream end, the bank protection along both the east and west banks will join with the existing concrete slope lining (PD 2262). At the downstream end, the proposed Hasley Canyon Creek “East” bank protection joins the proposed Castaic Creek “West” bank protection, and the Hasley Canyon Creek “West” bank protection joins the existing concrete/ rip-rap lining (PD 2298-Unit III).
- (2) **Rock Chute and Stilling Basin** – At the upstream end of the proposed soil cement bank protection and existing concrete slope protection, a rock chute and stilling basin are required to convey flow over a ~20ft drop, to dissipate energy and provide erosion protection along the channel bottom.
- (3) **Proposed “Franklin Parkway Bridge”** – The Franklin Parkway Bridge has a span of approximately 380 LF and will have two support piers.
- (4) **Modified Flow Diversion Berm (PD 2298, Unit III, Linings B and C) at the Castaic Creek/ Hasley Canyon Creek Confluence** – An existing flow diversion berm will be modified in the proposed condition. The existing berm was designed to convey flows from Hasley Canyon Creek under Commerce Center Drive Bridge before joining with Castaic Creek flows downstream of the bridge. In the proposed condition, approximately 150 LF of the existing berm will be removed to allow flows from Hasley Canyon Creek to converge with Castaic Creek flows upstream of the Commerce Center Drive bridge.



VALENCIA COMMERCE CENTER
HASLEY CANYON CREEK CLOMR

PROJECT VICINITY MAP

P:\A535\Engineering\A535-84_Hasley Canyon Creek CLOMR\exhibits\A535-84_Figure1-2 Soil Cement Location.dwg By: erandig Date: Jul. 10, 2024 Time: 08:28 am



 17520 Newhope Street, Suite 200 Fountain Valley, CA 92708 P: (714) 481-7300 www.pacewater.com	SCALE	N.T.S.	HASLEY CREEK SOIL CEMENT BANK PROTECTION TPM # 18108	FIGURE 1-2
	DESIGNED	EMR		
	DRAWN	BDP		
	CHECKED	JC		
	DATE	MARCH, 2023	INDEX MAP	
JOB NO.	A535_84			

2 Model Background and Development

2.1 Hydrology

The project site is located within Hasley Canyon Creek watershed, which has a drainage area of approximately 7.3 square miles. Based on the Flood Insurance Study (FIS), dated June 2021, the flow rate for the 100 storm event is 1,640 cfs. **Table 2-1** below summarizes the design and FEMA flow rates for Hasley Canyon Creek within the study reach.

Table 2-1: Hasley Canyon Creek Design Hydrology

Storm Event/ Return Period	Design Flow (cfs)	Location
100 – Year	1,640 ⁽¹⁾	At Confluence with Castaic Creek
100 – Year	820 ⁽²⁾	At Flow Diversion Berm, Flow is split evenly on the North and South Sides of the Berm
Notes: (1) Source FEMA FIS for Los Angeles County and Incorporated Areas, June 2, 2021, see Appendix B . (2) Source FEMA Effective Model for Hasley Canyon Creek, dated 2022		

2.2 HEC-RAS Model Development

To fully analyze the study reach of Hasley Canyon Creek near the proposed project, a detailed hydraulic model was developed using the computer application program, HEC-RAS Version 6.2. The model extends from approximately 600 feet downstream of the Commerce Center Drive Bridge over Hasley Canyon Creek (XS 4725) to 40 feet downstream of the Commerce Center Drive Bridge over Castaic Creek, just downstream of the confluence of Hasley Canyon Creek with Castaic Creek. The total floodplain study reach is approximately 3,800 feet. PACE developed existing and proposed conditions HEC-RAS models for the study reach.

2.2.1 FEMA Effective Model

A physical map revision (PMR) was completed for the Hasley Canyon Creek project area in June 2021, which included the confluence of Hasley Canyon Creek with Castaic Creek. A request was made to FEMA for effective models for Hasley Canyon Creek and Castaic Creek based on the revision. The data received from FEMA included an effective model for Hasley Canyon Creek dated 2022, and an effective model for Castaic Creek dated 2021. The Hasley Canyon Creek effective model was used as a design basis for the existing condition and proposed condition tie-in's, discharge, and selection of manning's n roughness values.

2.2.2 Model Preparation

Hydraulic modeling was performed using HEC-RAS, a computer modeling software developed by the U.S. Army Corps of Engineers (USACE). HEC-RAS is a rigid boundary hydraulic model that assumes the channel bed does not fluctuate, and develops a one-dimensional solution of the energy equation. To do this, energy losses are evaluated by friction through Manning's equation and contraction/expansion is based on the coefficient and change in velocity head. When bridges and confluences are present, the momentum equation or pressure flow/weir equation is used to manage these situations of rapidly varying water surface profile. Per FEMA requirements, the models were run with a subcritical flow regime.

2.2.2.1 FEMA Designations

The proposed project is located within SFHA Zone AE; a detailed hydraulic analysis has been previously performed and there are base flood elevation's (BFE's) provided by FEMA.

2.2.3 *Model Overview*

The following guidelines and assumptions were used to develop the various hydraulic analyses with the HEC-RAS model:

- Cross Section Spacing Intervals
- Cross Section Geometry
- Discharge
- Flow Regime
- Boundary Conditions
- Selection of Manning roughness – ‘n’ Values
- Bank Station Definition
- Ineffective Flow Areas
- Hydraulic Structure Data

2.2.3.1 *Cross Section Spacing Intervals and Geometry*

The corrected effective cross-section geometry is based on 2013 topographic data. This topography includes existing concrete slope lining (per P.D. 2262) at the upstream end of the study reach, existing Hasley Creek Concrete/ rip-rap lining (per P.D. 2298 Unit II) upstream of Commerce Center Drive, existing Castaic Creek soil cement bank protection (per P.D. 2563) downstream of Commerce Center Drive Bridge over Castaic Creek, and the existing flow diversion berm (per P.D. 2298 Unit III) between Hasley Creek and Castaic Creek. A HEC-RAS workmap showing the HEC-RAS cross sections and 2013 topographic contours is shown in **Exhibit 3**.

The proposed conditions cross-section geometry is based on the proposed Hasley Canyon Creek finished grade contours, which tie into the existing 2013 topographic data. The proposed finished grades consist of 3:1 side slopes on each bank, which then transition to a 2 percent slope until the proposed grading daylights with the existing grades near the center of the channel. The proposed cross-sections also include the proposed drop structure and stilling basin which connects the existing channel (per P.D. 2262) upstream of the project to the proposed project bank protection improvements, and extends from HEC-RAS cross-section 4396 to cross-section 4265. Finally, the proposed cross-section geometry includes shortening the flow diversion berm at the Commerce Center Drive Bridge between Hasley Creek and Castaic Creek. Note that some of the cross-section locations differ in the existing and proposed condition geometries, as cross sections were repositioned in the proposed conditions to span the proposed channel and to be oriented perpendicular to the flow direction.

Additional cross-sections are also included at the proposed drop structure and surrounding the proposed Franklin Parkway bridge. A proposed HEC-RAS work map showing the HEC-RAS cross-sections, proposed finished grade contours, and 2013 topographic contours is included in **Exhibit 3**. Note that interpolated cross-sections were used to refine results along the proposed drop structure and within the proposed stilling basin, which experience high energy loss and abrupt changes in water surface elevations, these are not included in **Exhibit 3**.

2.2.3.2 *Discharge*

The discharges used for the Hasley Canyon Creek analysis were obtained from the FEMA FIS (June 2021). A flow rate of 1,640 cfs was used for the entire study reach upstream of the confluence of Hasley Canyon Creek with Castaic Creek, as shown in **Table 2-1**. Per the FEMA effective model, the 1,640 cfs flow is split at the flow diversion berm, with half the flow (820 cfs) going on along the north side of the berm and the other half (820 cfs) going along the south side of the berm.

2.2.3.3 *Hydraulic Flow Regime*

The hydraulic analyses were performed in a “subcritical” flow regime. A “mixed” flow regime would more closely reflect the actual conditions that would naturally occur in the hydraulic system, but the intent of the floodplain hydraulic models is strictly for defining flood hazards per FEMA standards.

2.2.3.4 Topographic Data Source

The one-foot aerial topography from 2013 (covering this project's study reach of Castaic Creek and Hasley Canyon Creek) was used for the hydraulic analysis and floodplain delineation. This topography and all elevations are in North American Vertical Datum of 1988 (NAVD88).

2.2.3.5 Boundary Conditions

The boundary condition for the downstream study limit was taken as "normal depth slope" with slope equal to 0.0187 ft/ft. This boundary condition is the same as the boundary condition for the effective model. Note, the model is run in the subcritical flow regime, which does not require an upstream boundary condition.

2.2.3.6 Selection of the Manning's Roughness Value

The FEMA FIS report specifies Manning's roughness for Hasley Canyon Creek as 0.020 - 0.040 within the channel and 0.050 - 0.1 for the overbanks. Manning's roughness values within the model were set to match those specified in the effective FEMA model for Hasley Canyon Creek.

2.2.3.7 Hydraulic Structures

The existing conditions hydraulic model includes the Commerce Center Drive Bridge over Castaic Creek (Bridge No. B3794) as well as the existing flow diversion berm (per P.D. 2298 Unit III). Geometry for the Commerce Center Drive Bridge over Castaic Creek was obtained from as-built plans provided in **Appendix F**. The FEMA effective model only includes the portion of Commerce Center Drive Bridge over the Hasley Canyon Creek side or north side of the flow diversion berm. The existing and proposed conditions models follow the same approach as the effective model for the Commerce Center Drive Bridge. The bridge modeled spans approximately 120ft from the north abutment of the bridge (Bridge Abutment 1) to the flow diversion berm (Pier 3) and includes a single pier (Pier 2), per Commerce Center Drive Bridge As-Built. The bridge is situated between cross sections 593 and 458.

The proposed condition hydraulic model includes the existing Commerce Center Drive Bridge over Castaic Creek, the proposed Franklin Parkway Bridge, the proposed bank improvements, and the modified flow diversion berm. Franklin Parkway bridge is situated between proposed HEC-RAS cross-sections 2305.5 and HEC-RAS cross-section 2190.5, and is approximately 1,000 ft upstream of the Hasley Canyon Creek and Castaic Creek confluence. Franklin Parkway bridge contains two 6-ft wide bridge piers, a bridge span of approximately 300-ft, and a bridge deck 88-ft in width.

2.2.3.8 Ineffective Flow Areas

Ineffective flow markers are incorporated in the model to establish the portion of the channel at each cross section with effective flow. Overbank areas are considered ineffective flow areas until flows reach a specific elevation, after which the effective channel widens to accommodate the higher flows. In the existing condition model, ineffective flow is designated upstream of cross sections 963, with a contraction ration of 1:1, as the natural floodplain narrows going into the north side of the flow diversion berm. This is shown in the topographic workmap, **Exhibit 8**.

2.3 Summary of CLOMR HEC-RAS Models

In summary, the Hasley Canyon Creek CLOMR includes the following condition models:

(1) Duplicate Effective Model:

This represents the effective FEMA model, truncated to the study area, and run on the newest version of HEC-RAS (6.4.1).

(2) Corrected Effective Condition Model/ Existing Condition:

Cross sections cut from 2013 topography and additional cross sections added to the effective model. This model does not include the proposed improvements.

(3) Proposed Condition Model

Cross sections cut from 2013 topography and additional cross sections added to the model with some locations changing to better suit the soil cement bank protection alignment. Cross section geometry includes proposed soil cement bank protection, Franklin Parkway bridge, and the modified flow diversion berm.

3 Sediment Transport Considerations

3.1 Introduction

Various analyses were performed to evaluate the fluvial characteristics and long-term stability of study area in the vicinity of the Lower Hasley Creek improvements as part of the *Drainage Concept Report Volume III of V, Hasley Canyon Creek Bank Protection, EIMP No. 2019000489* (Approved March 2022). The proposed soil cement bank protection, which will be installed on the east and west banks, will provide long-term erosion protection from vertical and lateral migration of the thalweg and flood protection for the adjacent proposed developments. The fluvial study evaluated the impacts from (1) fluvial modifications of the streambed from a single hypothetical storm event, or the general adjustment and (2) long-term changes in the floodplain fluvial operation, or the long term adjustment.

3.1.1 Types of Adjustment

Bed adjustment in feet quantify the fluvial modifications and long-term changes of the streambed. A positive adjustment indicates bed aggradation, while a negative adjustment indicates bed degradation. PACE considered several types of adjustment in this study including:

- *Long-Term Adjustment* which accounts for fluvial processes that occur over many rainy seasons and contribute to fluctuations in the creek's bed elevation.
- *General Adjustment* which accounts for scour that occurs during an individual storm event. Aggradation describes a situation in which the quantity of sediment that enters a given reach is higher than the quantity of sediment that exits the same reach, and degradation describes a situation in which sediment outflow exceeds inflow for a given reach.
- *Other Scour* is comprised of local scour, bend scour, low-flow incisement, and bed form height.

The total vertical adjustment (total scour) is the sum of the general adjustment, long-term adjustment, and other scour. The toe of the soil cement was designed to be at or below the maximum calculated total scour and is shown on the soil cement profiles in the "West" and "East" banks in **Exhibits 6 and 7**, respectively.

4 Proposed Hasley Canyon Creek Modifications and Improvements

The proposed improvements at Valencia Commerce Center (VCC) Industrial Park Development in Tentative Parcel Map (TPM) No. 18108 consist of soil cement bank protection along both banks of Hasley Canyon Creek, installation of a rock chute stilling basin and two grade control structures, construction of the proposed Franklin Parkway Bridge, and modifications to an existing diversion berm/ flow splitter. Below is a summary of the design of the proposed improvements.

4.1 Rock Chute and Stilling Basin

At the upstream termination/junction point of the proposed soil cement bank protection and the existing concrete slope protection, a rock chute and stilling basin are required to convey flow over the roughly 20-foot drop, to dissipate the energy and to provide erosion protection along the channel bottom. The crest of the rock chute is designed to tie in with the channel invert at the end of the existing concrete slope-lined channel (PD No. 2262). The chute and stilling basin will be rock lined along the bottom with exposed soil cement along the side slopes. The chute will be designed with a 3:1 (H:V) slope along the invert and 1.5:1 (H:V) side slopes for the exposed soil cement. The bottom width of the channel is approximately 85 feet at the crest of the chute and approximately 50 feet at the toe of the chute. The stilling basin will be level along the invert and will extend approximately 100 feet downstream. The end of the stilling basin will have a 2.5:1 (H:V) slope to tie in with the invert of the channel, and the end sill will extend roughly ten feet downstream. From this point, a sloped cut-off will be provided that will extend down to the toe of soil cement elevation at a 2:1 (H:V) slope. The proposed layout of the drop structure is shown in **Exhibit 4**.

4.2 Grade Control Structures

The proposed project also includes the construction of two grade control structures. The purpose of the grade control structures is to maintain the stability of the natural streambed by controlling head cutting and reducing long-term scour in the channel. One of the proposed grade control structures will be placed at HEC-RAS River Station 1804, approximately 675 ft upstream of the Hasley Canyon Creek and Castaic Creek confluence. The other proposed grade control structure will be placed between HEC-RAS River Stations 3190.5 and 3304, approximately 915 ft upstream of the proposed Franklin Parkway Bridge. Both grade control structures will be constructed of riprap, and the top of the structures will be set at the existing grade of the channel. The structures will be buried deep enough to prevent vertical erosion during peak flows from undermining the structure.

4.3 Franklin Parkway Bridge

The proposed project also includes the addition of the Franklin Parkway Bridge crossing over Hasley Creek. The Franklin Parkway Bridge is still in the conceptual design phase. The bridge is proposed to be located between HEC-RAS cross sections 2190.5 and 2305.5, approximately 1,000 ft upstream of the confluence of Castaic Creek and Hasley Canyon Creek. The bridge will have a proposed span of approximately 350 feet, a deck width of 88 feet, and two, six-foot support piers.

4.4 Modifications to the Existing Berm

The existing concrete and riprap lined berm (see Linings B and C on PD 2298, Unit III) is located at the confluence between Castaic Creek and Hasley Canyon Creek. The berm was designed to divert flows from Hasley Canyon Creek into Castaic Creek downstream of the Commerce Center Drive Bridge. However, a large storm in January 2005 caused flows to bifurcate the berm. This change caused the berm to become an obstruction to flows and increase chances of blockages to either flow path, into Castaic Creek, or under Commerce Center Drive.

In the proposed condition, the upstream portion of the flow diversion berm will be removed and lowered to the scour depth. This will remove the obstruction to the flow path of Hasley Canyon Creek and allow water

into Castaic Creek upstream of Commerce Center Drive Bridge. **Exhibit 5** depicts the proposed modifications to the existing flow diversion berm.

According to the as-built drawings, the existing flow diversion berm is approximately 500 feet in length and is 16-feet-wide as measured along the top of the berm. The berm consists of two linings. Lining B is a concrete lining that was installed along the Hasley Canyon Creek side of the berm. Lining C is comprised of mostly rip-rap and was placed along the side of the berm facing Castaic Creek. The as-built drawings (PD 2298, Unit III) for the flow diversion berm are provided in **Appendix G**. It should be noted that the elevations shown on PD 2298, Unit III are referenced to the NGVD 1929. A datum shift of +2.638 feet should be applied to convert NGVD 1929 elevations to NAVD 1988 elevations, as the HEC-RAS model datum is NAVD 88.

A portion of the upstream end of the existing flow diversion berm will be removed such that the modified flow diversion berm will be reduced to 150 feet in length upstream of Commerce Center Drive Bridge. Rip-rap will be placed at the upstream end of the berm. The portion of the flow diversion berm above the estimated scour elevations will be removed to eliminate the obstruction of flows from Hasley Creek entering Castaic Creek upstream of Commerce Center Drive Bridge.

4.5 Soil Cement Bank Protection

The proposed Lower Hasley Canyon Creek bank protection will consist of buried soil cement bank protection. The bank protection improvements will be located east of Commerce Center Drive, along the east and west banks of Hasley Canyon Creek. The proposed bank protection along the east and west banks of Hasley Canyon Creek will be approximately 3,000 linear feet and will protect the VCC Industrial Park Development from potential flooding and erosion. At the upstream end of Hasley Canyon Creek, the bank protection along both the east and west banks will join with the existing concrete slope lining (PD 2262). At the downstream end, the proposed Hasley Canyon Creek “East” bank protection joins the proposed Castaic Creek “West” bank protection, and the Hasley Canyon Creek “West” bank protection joins the existing concrete/ rip-rap lining (PD 2298-Unit III).

4.5.1 Design of Soil Cement Bank Protection

The “structural” segment of the proposed Lower Hasley Creek bank protection consists of LACPW standard buried soil cement to provide the appropriate level of freeboard and scour protection for all storm events up to the Capital Flood. The critical factors in determining the design of the bank protection were based on the following criteria:

1. Flood control stability and durability of bank protection.
2. Safety concerns regarding access to and from the channel in dry and wet conditions.
3. Bank protection maintenance considerations.
4. Environmental compatibility with the native area and resource enhancement concepts, and aesthetic considerations.
5. Constructability and cost of construction.

Soil cement bank protection is constructed as a monolithic and homogenous structure consisting of approximately 90% native soils and 10% cement. The typical section consists of 8-foot wide and 6 to 12-inch thick layers of soil cement. Each layer of soil cement is set back from the edge of the previous layer, at a 1.5:1 slope. The entire section varies in total height based on varying freeboard, flow depth and toe-down requirements.

The proposed soil cement bank protection addresses the above design criteria as follows:

1. Soil cement provides a stable riverbank protection material, in terms of both surface erosion and structural stability. Preliminary geotechnical analysis indicates that locally available native soils are considered acceptable for use in soil cement mix.
2. For the majority of the reach, soil cement bank protection will be completely buried with a variable backfill slope of 3:1 (H:V) or flatter. Near the upstream tie in to the existing concrete slope protection within the chute, the soil cement will be partially exposed.

4.6 Channel Freeboard Requirements

The proposed top of bank protection was designed to maintain a minimum 2.5 ft of freeboard based on LACPW design criteria. The LACPW design criteria is based on a Capital flood flow of 9,480 cfs and a manning's roughness coefficient of $n = 0.085$.

This CLOMR floodplain mapping analysis uses the 100-yr FEMA FIS flow rate of 1,640 cfs, which provides freeboard that exceeds the FEMA requirements. The freeboard height above the FEMA 100-year base flood elevation is summarized for the "West" and "East" banks in **Table 4-1** and **Table 4-2**, respectively.

Table 4-1: "West" Bank Soil Cement Bank Protection Freeboard Summary

HEC-RAS Cross Section	West Soil Cement Bank Station	Proposed Top of Bank Elevation ¹ [ft]	Proposed Condition 100-yr WSE [ft] ($Q_{100} = 1,640$ cfs)	Freeboard above 100-yr WSE [ft]
4396/End Top of Soil Cement, Join Existing Concrete Slope Lining, P.D. No. 2262	39+89.01	1071.1	1061.6	9.5
4300	39+27.91	1065.0	1042.2	22.8
4282	39+08.28	1063.0	1039.4	23.6
4276	38+65.51	1058.7	1039.5	19.3
4270	38+07.80	1053.0	1039.5	13.5
4265	37+97.72	1052.9	1039.2	13.7
4258	37+85.91	1052.8	1039.2	13.6
4157	37+09.64	1051.9	1039.3	12.7
4055.5	35+63.04	1050.3	1038.5	11.8
3940.5	34+77.22	1049.4	1036.8	12.5
3844	33+70.62	1047.5	1035.5	12.0
3747	32+79.01	1045.9	1034.0	11.9
3650	31+64.34	1043.9	1032.6	11.3
3554	30+37.39	1041.7	1030.3	11.4
3440.5	29+23.41	1039.7	1029.4	10.3
3372	28+60.84	1038.6	1028.3	10.3
3304	28+08.81	1037.7	1027.0	10.7
3190.5	27+01.61	1035.8	1025.6	10.3
3105	26+53.53	1035.0	1024.1	10.9
3020	25+83.13	1033.7	1023.8	10.0
2934	25+02.70	1032.3	1022.4	9.9
2820.5	23+87.44	1030.3	1019.1	11.2
2748	23+00.00	1028.8	1017.7	11.1
2675.5	21+95.89	1027.0	1016.5	10.5
2560.5	20+87.57	1025.1	1014.7	10.3
2476	19+64.82	1022.9	1013.9	9.0

HEC-RAS Cross Section	West Soil Cement Bank Station	Proposed Top of Bank Elevation ¹ [ft]	Proposed Condition 100-yr WSE [ft] (Q ₁₀₀ = 1,640 cfs)	Freeboard above 100-yr WSE [ft]
2391	18+61.46	1021.1	1012.4	8.7
2305.5	18+01.98	1020.1	1011.9	8.2
2190.5	16+83.64	1018.0	1008.9	9.1
2122	15+77.90	1016.1	1007.5	8.6
2054	15+24.32	1015.2	1005.9	9.2
1940.5	14+47.40	1013.8	1004.6	9.2
1872	13+93.42	1013.0	1002.9	10.1
1804	13+30.05	1012.1	1001.8	10.3
1689	12+13.58	1010.4	999.4	11.0
1584	11+45.70	1009.5	997.6	11.9
Begin West Bank Soil Cement Top, Join Existing Slope Lining (Per P.D. 2296 Unit III)	10+44.81	1008.0	-	-

Note: The proposed top of bank represents the calculated top elevation required to meet or exceed the required freeboard for the design flowrate.

Table 4-2: “East” Bank Soil Cement Bank Protection Freeboard

HEC-RAS Cross Section	East Soil Cement Bank Station	Proposed Top of Bank Elevation [ft]	Proposed Condition 100-yr WSE [ft] (Q ₁₀₀ = 1,640 cfs)	Freeboard above 100-yr WSE [ft]
End Top Soil Cement, Join Existing Concrete Slope Lining P.D. No. 2262	40+29.97	-	-	-
4396	39+91.02	1071.1	1061.6	9.4
4300	39+29.98	1065.0	1042.2	22.8
4282	39+11.65	1063.1	1039.4	23.7
4276	38+74.34	1059.4	1039.5	19.9
4270	38+43.10	1056.3	1039.5	16.8
4265	38+32.25	1055.2	1039.2	16.0
4258	38+20.42	1054.0	1039.2	14.8
4157	37+48.37	1051.5	1039.3	12.2
4055.5	36+60.38	1050.5	1038.5	12.0
3940.5	35+53.64	1049.3	1036.8	12.5
3844	34+26.58	1047.2	1035.5	11.6
3747	33+25.47	1045.5	1034.0	11.4
3650	32+40.49	1044.0	1032.6	11.5
3554	31+63.21	1042.7	1030.3	12.4
3440.5	30+45.90	1040.7	1029.4	11.3
3372	29+63.35	1039.3	1028.3	10.9
3304	28+84.58	1037.9	1027.0	10.9
3190.5	27+60.89	1035.8	1025.6	10.3
3105	26+56.85	1034.1	1024.1	9.9
3020	25+44.48	1032.1	1023.8	8.3
2934	24+53.29	1029.9	1022.4	7.5
2820.5	23+39.34	1027.1	1019.1	8.0

HEC-RAS Cross Section	East Soil Cement Bank Station	Proposed Top of Bank Elevation [ft]	Proposed Condition 100-yr WSE [ft] (Q ₁₀₀ = 1,640 cfs)	Freeboard above 100-yr WSE [ft]
2748	22+82.85	1026.2	1017.7	8.5
2675.5	22+15.00	1025.0	1016.5	8.5
2560.5	21+36.58	1023.8	1014.7	9.0
2476	20+70.49	1022.7	1013.9	8.7
2391	20+00.15	1021.5	1012.4	9.1
2305.5	19+14.24	1020.1	1011.9	8.2
2190.5	18+09.13	1018.4	1008.9	9.5
2122	17+41.40	1017.2	1007.5	9.7
2054	16+40.43	1015.6	1005.9	9.7
1940.5	15+36.82	1013.9	1004.6	9.3
1872	14+22.46	1012.0	1002.9	9.0
1804	13+50.46	1010.7	1001.8	8.9
1689	12+34.30	1008.8	999.4	9.4
1584	10+97.28	-	997.6	-
Begin Top Soil Cement, Join the proposed Castaic Creek Soil Cement Bank Protection	10+00.00	1006.8	-	-

Note: The proposed top of bank represents the calculated top elevation required to meet or exceed the required freeboard for the design flowrate.

The final top and toe of the proposed soil cement bank protection is shown in profile for the “West” and “East” banks on **Exhibit’s 6 and 7**, respectively.

4.7 Bank Protection Toe-Down Design Summary

The proposed toe of the soil cement bank protection was design based on the estimated scour depth within the Creek. Per LACPW Hydraulic Design criteria, a Manning’s roughness coefficient of $n=0.025$ was utilized to determine the maximum velocities within the study limits.

The types of scour analyzed include long-term scour, local scour, contraction scour, local scour at the bridge piers, bend scour, low-flow incisement, and bedform height.

5 Hydraulic Analysis Results

5.1 Baseline Corrected Effective Hydraulic Analysis

The main purpose of the corrected effective analysis (pre-project) is to serve as a basis of comparison for the proposed condition (post-project) analysis. A complete summary of the corrected effective hydraulic results is presented in **Appendix D**.

A comparison between the duplicate effective and corrected effective models is provided in **Table 5-1** to shown the changes in water surface elevation (WSEL) and velocity resulting from the updated topography. Note that the corrected effective model has additional sections not included in the duplicate effective model, see **Exhibit 2** for a comparison of the duplicate effective and corrected effective cross sections. See **Appendix C** for a complete summary of the duplicate effective HEC-RAS results.

Table 5-1: Flow Depth and Velocity Comparison for the Duplicate Effective and Corrected Effective ($Q_{100} = 1,640/ 820$ cfs)

Effective HEC-RAS Cross Section	Duplicate Effective		Corrected Effective HEC-RAS Cross Section	Corrected Effective		Difference [Corrected Effective - Duplicate Effective]	
	WSEL (ft)	Velocity (fps)		WSEL (ft)	Velocity (fps)	WSEL (ft)	Velocity (fps)
4295	1070.5	8.9					
4213	1069.8	8.1	4725	1070.0	7.2	0.3	-0.9
4127	1068.6	8.1	4648	1070.2	4.4	1.7	-3.7
			4622	1069.4	8.1		
			4523	1067.5	8.1		
			4396	1065.0	8.0		
3834	1062.4	7.2					
3764	1060.8	6.1	4294	1061.3	6.0	0.5	0.0
3728	1059.6	6.5	4255	1058.6	6.6	-0.9	0.1
			4207	1048.9	7.4		
			4164	1039.4	6.8		
			4133	1039.4	1.9		
			4100.5	1038.9	5.5		
			4078	1038.4	7.2		
			4055.5	1038.3	6.9		
3447	1040.1	6.5					
			3940.5	1036.5	9.4		
			3844	1035.6	7.8		
			3747	1034.5	6.9		
			3650	1032.7	8.1		
			3564	1030.8	5.9		
2997	1034.1	9.6					
			3465	1030.2	5.3		
			3369	1028.6	8.6		
2767	1029.9	5.6	3304	1027.4	7.9	-2.5	2.3
2676	1028.6	5.8					
			3190.5	1025.5	8.5		
2568	1026.9	6.8	3105	1024.0	8.1	-2.9	1.3
			3020	1023.4	6.3		
			2934	1021.8	8.5		
			2820.5	1019.2	7.9		
2253	1021.9	7.5					
			2748	1017.8	7.1		
			2675.5	1016.8	6.8		
			2560.5	1014.7	8.0		

Effective HEC-RAS Cross Section	Duplicate Effective		Corrected Effective HEC-RAS Cross Section	Corrected Effective		Difference [Corrected Effective - Duplicate Effective]	
	WSEL (ft)	Velocity (fps)		WSEL (ft)	Velocity (fps)	WSEL (ft)	Velocity (fps)
1907	1015.6	5.6	2476	1013.8	5.5	-1.8	0.0
			2391	1012.5	6.0		
1795	1013.2	6.3					
			2305	1010.7	6.3		
1715	1011.9	5.1					
			2190	1008.3	5.9		
			2122	1007.5	6.8		
1510	1008.4	7.7					
			2054	1006.3	7.8		
			1940	1004.6	5.9		
			1872	1003.4	7.0		
1269	1003.5	7.9					
			1804	1002.2	7.8		
1137	1000.8	7.1					
			1689	999.7	6.2		
North Side of Flow Diversion Berm²							
963	997.8	5.5	963	998.0	6.0	0.2	0.5
			704	994.6	5.4		
616	994.3	3.7	616	994.3	3.8	-0.1	0.1
593	994.3	3.3	593	994.2	3.4	-0.1	0.1
584	Commerce Center Drive Bridge						
458	990.5	6.6	458	990.5	6.6	0.0	0.0
358	988.6	8.2	358	988.6	8.2	0.0	0.0
290	986.6	7.6	290	986.6	7.6	0.0	0.0
South Side of Flow Diversion Berm²							
731	996.6	5.9	731	996.6	7.0	0.0	1.1
665	995.3	6.3	665	995.3	5.8	0.0	-0.6
512	992.1	5.8	512	992.6	5.7	0.4	-0.1
336	988.7	5.4	336	988.7	5.4	0.0	0.0
203	986.4	5.5	203	986.4	5.5	0.0	0.0
Note: ¹ Blank cells indicate locations where a HEC-RAS cross section is only included in one of the models, either duplicate effective or corrected effective. ² Flow is reduced from 1640 cfs to 820 cfs at the flow diversion berm (cross sections 963 and 731).							

5.2 Proposed Condition Hydraulic Analysis

The proposed condition model differs from the corrected effective model in that the proposed condition model includes:

- the soil cement bank protection and accompanied re-grading of the channel
- the proposed Franklin Parkway Bridge
- modifications to the flow diversion berm
- the drop structure

A complete summary of the proposed condition hydraulic results is presented in **Appendix E. Table 5-2** provides a comparison of the water surface elevation and velocity results between the proposed condition and corrected effective models.

Table 5-2: Flow Depth and Velocity Comparison for Corrected Effective and Proposed Condition
($Q_{100} = 1,640/820$ cfs)

Corrected Effective HEC-RAS Cross Section	Corrected Effective		Proposed HEC-RAS Cross Section	Proposed Condition		Difference [Proposed – Corrected Effective]	
	WSEL (ft)	Velocity (fps)		WSEL (ft)	Velocity (fps)	WSEL (ft)	Velocity (fps)
4725	1070.0	7.2	4725	1070.1	6.9	0.1	-0.3
4648	1070.2	4.4	4648	1070.2	4.4	0.0	0.0
4622	1069.4	8.1	4622	1069.4	8.1	0.0	0.0
4523	1067.5	8.1	4523	1067.5	8.2	0.0	0.0
4396	1065.0	8.0	4396	1061.6	8.3	-3.4	0.3
4055.5	1038.3	6.9	4055.5	1038.5	6.5	0.2	-0.4
3940.5	1036.5	9.4	3940.5	1036.8	9.4	0.3	-0.1
3844	1035.6	7.8	3844	1035.5	7.0	0.0	-0.8
3747	1034.5	6.9	3747	1034.0	4.9	-0.5	-2.0
3650	1032.7	8.1	3650	1032.6	7.3	-0.1	-0.9
3564	1030.8	5.9	3554	1030.3	7.0	-0.5	1.1
3304	1027.4	7.9	3304	1027.0	5.9	-0.4	-2.0
3190.5	1025.5	8.5	3190.5	1025.6	4.2	0.1	-4.3
3105	1024.0	8.1	3105	1024.1	8.2	0.1	0.0
3020	1023.4	6.3	3020	1023.8	4.7	0.4	-1.5
2934	1021.8	8.5	2934	1022.4	7.3	0.6	-1.2
2820.5	1019.2	7.9	2820.5	1019.1	7.1	-0.1	-0.8
2748	1017.8	7.1	2748	1017.7	6.4	-0.1	-0.7
2675.5	1016.8	6.8	2675.5	1016.5	6.5	-0.3	-0.3
2560.5	1014.7	8.0	2560.5	1014.7	8.0	0.1	0.0
2476	1013.8	5.5	2476	1013.9	4.6	0.2	-1.0
2391	1012.5	6.0	2391	1012.4	6.4	-0.1	0.3
2305	1010.7	6.3	2305.5	1011.9	3.1	1.2	-3.2
			2250	Proposed Franklin Parkway Bridge			
2190	1008.3	5.9	2190.5	1008.9	5.6	0.6	-0.3
2122	1007.5	6.8	2122	1007.5	5.9	0.0	-0.9
2054	1006.3	7.8	2054	1005.9	6.5	-0.3	-1.3
1940	1004.6	5.9	1940.5	1004.6	5.0	0.0	-0.9
1872	1003.4	7.0	1872	1002.9	7.3	-0.4	0.3
1804	1002.2	7.8	1804	1001.8	6.2	-0.4	-1.6
1689	999.7	6.2	1689	999.4	6.4	-0.3	0.2
North Side of Flow Diversion Berm ¹							
963	998.0	6.0					
704	994.6	5.4	704	994.6	5.5	0.0	0.0
616	994.3	3.8	616	994.3	3.8	0.0	0.0
593	994.2	3.4	593	994.2	3.4	0.0	0.0
584			Commerce Center Drive Bridge				
458	990.5	6.6	458	990.5	6.6	0.0	0.0
358	988.6	8.2	358	988.6	8.2	0.0	0.0
290	986.6	7.6	290	986.6	7.6	0.0	0.0
South Side of Flow Diversion Berm ¹							
731	996.6	7.0					
665	995.3	5.8					
336	988.7	5.4	336	988.7	5.4	0.0	0.0
203	986.4	5.5	203	986.4	5.5	0.0	0.0
Note: ¹ Blank cells indicate locations where a HEC-RAS cross section is only included in the corrected effective model ² Flow is reduced from 1640 cfs to 820 cfs at the flow diversion berm (cross sections 963 and 731 in the corrected effective condition and cross sections 704 and 336 in the proposed condition). ³ Tie-in Located denoted in shaded cells.							

Table 5-3 summarizes the tie-in analysis for the proposed floodplain modifications. The tie-in points, where the FIRM will be modified, are at locations where the revised floodplain is within 5% of the FEMA effective floodplain top width and the change in water surface elevation is 0.5 ft or less. See **Exhibit 2** for a comparison of the FEMA effective cross sections and the proposed condition cross sections.

Table 5-3: Tie-In Analysis for the Effective and Proposed Condition ($Q_{100} = 1,640/820$ cfs)

Effective HEC-RAS Cross Section	Effective WSEL (ft)	Effective Top-width (ft)	Proposed HEC-RAS Cross Section	Proposed WSEL (ft)	Proposed Top-width (ft)	Difference in WSEL [Proposed - Effective] (ft)	Top-width Within 5%? Yes or No
4213	1069.8	101.5	4725	1070.1	103.5	0.3	YES
4127	1068.6	101.5	4648	1070.2	106.9	1.7	NO
2767	1029.9	197.9	3304	1027.0	261.8	-2.9	NO
1907	1015.6	242.2	2476	1013.9	245.0	-1.6	YES
North Side of Flow Diversion Berm							
616	994.3	94.1	616	994.3	93.7	-0.1	YES
593	994.3	99.0	593	994.2	98.1	-0.1	YES
584	Commerce Center Drive Bridge						
458	990.5	76.9	458	990.5	76.9	0.0	YES
358	988.6	77.2	358	988.6	77.2	0.0	YES
290	986.6	84.6	290	986.6	84.6	0.0	YES
South Side of Flow Diversion Berm							
336	988.7	119.4	336	988.7	119.4	0.0	YES
203	986.4	153.0	203	986.4	153.0	0.0	YES
Notes:							
¹ Bolded Cross Section with Red Outline indicate Tie-In locations with the effective floodplain.							

5.3 Hydraulic Analysis Results and Floodplain Discussion

For the purpose of this CLOMR application, a detailed analysis of Hasley Creek from approximately 600 feet downstream of the Commerce Center Drive Bridge over Hasley Canyon Creek to approximately 40 feet downstream of the confluence of Hasley Canyon Creek with Castaic Creek is presented herein, including a hydraulic analysis of the Creek with proposed soil cement bank protection and the proposed Franklin Parkway Bridge.

According to the analysis, the proposed soil cement bank protection will cause the 100-yr floodplain to primarily widen at the location of the proposed bank protection. In addition, there are both increases and decreases in the 100-yr water surface elevations, with a maximum increase of 1.7 ft directly upstream of the Commerce Center Drive Bridge. All increases above 0.5 ft are within the limits of the proposed soil cement bank protection and do not cause impacts to any offsite properties.

The topographic work map in **Exhibit 8** shows the floodplain limits resulting from the proposed bank protection improvements. Detailed HEC-RAS results can be found in **Appendices D and E**.


6 Conclusion

The proposed addition of the “West” and “East” soil cement bank protection at Valencia Commerce Center (VCC) Industrial Park Development in Tentative Parcel Map (TPM) No. 18108 results in changes in water surface elevations between the upstream (HEC-RAS XS 4396) and downstream limits (HEC-RAS XS 1061) of study. After a detailed evaluation, which included updated topographic data from 2013 and the inclusion of the proposed improvements, the final modeled floodplain results in a primarily widened 100-yr floodplain within the limits of the study.

The corrected effective 100-year floodplain is wide at the location of the proposed project due to the natural channel being unconstrained. The project results in a floodplain that is both narrower and wider than the corrected effective along the proposed bank protection. This results in water surface elevations that both increase and decrease at locations of narrowing and widening. The maximum increase in water surface elevation is just upstream of Commerce Center Drive Bridge over Castaic Creek, with an increase of 1.2 ft. The proposed soil cement bank protection meets FEMA minimum freeboard requirements.

The comparison analysis shows that the floodplain extents for the study reach tie-in to the FEMA Zone AE floodplain for 100-yr Base Flood Elevations (BFEs) within 0.5-ft or less. The upstream and downstream tie-in locations are at HEC-RAS river stations 4396 and 1061, respectively. These abide by FEMA guidelines for flood hazard analysis.

Based on the present application and enclosed analyses, we are requesting that FEMA provide a Conditional Letter of Map Revision for the proposed Soil Cement Bank Protection Project on Hasley Canyon Creek, affecting FIRM Panel 06037C0805G. The proposed condition 100-year floodplain and base flood elevations are shown on the Annotated FIRM in **Figure 6-1**.



VALENCIA COMMERCE CENTER HASLEY CANYON CREEK CLOMR

ANNOTATED FIRM

References

FEMA, Flood Insurance Study (FIS), Number 06037CV002F. June 2, 2021.

PACE, Drainage Concept Report, Volume III or V, Hasley Canyon Creek Bank Protection EIMP No. 2019000489. October 2021. (Approved by LACPW March 2022).


PACE, FEMA Application Conditional Letter of Map Revision, Castaic Creek Bank Protection for Valencia Commerce Center (From 1-5 Freeway to Commerce Center Drive). March 2023.

PACE, Hydraulic Analysis Technical Assessment Report for Engineered Earthen-Bottom Flood Control Channels Located Within the Santa Clara River Watershed and Antelope Valley Watershed. August 2017.

R.T. Franklin and Associates, Memo – Gradation Laboratory Test Results, Parcel Map 20685, March 27, 2003



Exhibits




JOB VALENCIA COMMERCE CENTER

HASLEY CANYON CREEK
GLOMR


LOS ANGELES COUNTY

CA.




TITLE

HASLEY CANYON CREEK
PROPOSED IMPROVEMENTS



EFFECTIVE vs CORRECTED EFFECTIVE HEC-RAS SECTIONS

SCALE 1"=150'




EFFECTIVE vs PROPOSED CONDITION HEC-RAS SECTIONS

SCALE 1"=150'

LEGEND

- HEC-RAS HYDRAULIC STRUCTURE
- PROPOSED SOIL CEMENT BANK PROTECTION
- LIMITS OF EXCAVATION
- CENTERLINE
- HEC-RAS CROSS SECTIONS FROM FEMA EFFECTIVE MODEL
- HEC-RAS CROSS SECTIONS FROM PACE CLOMR

TITLE	JOB NO.	DATE	BY	DATE	REVISIONS	DATE	APP.
HASLEY CANYON CREEK	4535	03/20/23	J.C.				



SCALE 1"=150'	DESIGNED E.M.R.	DRAWN M.M.T.	CHECKED J.C.	DATE 03/20/23	JOB NO. 4535
---------------	-----------------	--------------	--------------	---------------	--------------


HASLEY CANYON CREEK	VALENCIA COMMERCE CENTER	LOS ANGELES COUNTY	CA
GLOMR	HEC-RAS CROSS SECTION COMPARISON		

HASLEY CANYON CREEK	VALENCIA COMMERCE CENTER	LOS ANGELES COUNTY	CA
GLOMR	HEC-RAS CROSS SECTION COMPARISON		


EXHIBIT	JOB NO.	A535
P:\A535\Engineering\A535-84_Hasley Canyon Creek CLOMR\Exhibit 2 HEC-RAS Workmap\FEManProposed.dwg - Tab: 24-35 - by erandig on 03/05/24 at 8:19:38 AM		



2





CORRECTED EFFECTIVE CONDITIONS
SCALE 1"=150'



PROPOSED CONDITIONS
SCALE 1"=150'

JOB NO. A535	EXHIBIT 3	 Pace Advanced Water Engineering 17520 Newhope Street, Suite 200 Fountain Valley, CA 92708 P: (714) 481-7300 www.pacewater.com	JOB HASLEY CANYON CREEK VALENCIA COMMERCE CENTER Los Angeles County CA	TITLE HASLEY CANYON CREEK CLOMR CORRECTED EFFECTIVE & PROPOSED HEC-RAS WORKMAP	SCALE 1"=150'		
					DESIGNED E.M.R.		



NO	BY	DATE	DATE	APP.




JOB	VALENCIA COMMERCE CENTER
	HASLEY CANYON CREEK
	GLOMR
	LOS ANGELES COUNTY

PACE
Advanced Water Engineering
17520 Newhope Street, Suite 200 | Fountain Valley, CA 92708
P: (714) 481-7300 | www.pacewater.com

PREPARED	JOSE CRUZ
PROJECT ENGINEER	R.C.E. NO. 72249
EXP.	06/30/2022
DRAWN	BOP
DESIGNED	JC
CHECKED	MEK
DATE	7/25/2024



TITLE	PROPOSED DROP STRUCTURE (AT UPSTREAM TERMINATION)	EXHIBIT	4	JOB NO. A535
-------	---	---------	---	--------------

[illegible]

JOB VALENCIA COMMERCE CENTER

HASLEY CANYON CREEK CLOMR

LOS ANGELES COUNTY

CA.



17520 Newhope Street, Suite 200 | Fountain Valley, CA 92708
P: (714) 481-7300 | www.pacewater.com

PREPARED <i>JOSE CRUZ</i>	
PROJECT ENGINEER	
R.C.E. NO. <i>72249</i>	
EXP. <i>06/30/2022</i>	
DRAWN <i>BDP</i>	SCALE <i>AS SHOWN</i>
DESIGNED <i>JC</i>	
CHECKED <i>EMR</i>	DATE <i>7/19/2023</i>




	TITLE
--	-------

PROPOSED MODIFICATION OF DIVERSION BERM

XHIBIT

5


OB NO. A535



PROFILE - WEST BANK

LEGEND

- PROPOSED CONDITION FLOODPLAIN ($Q_{100}=1,640$ CFS)
- FEMA 100-YEAR FLOODPLAIN (EFFECTIVE JUNE 2, 2021) FIRM PANELS 0805G, 0815G
- CORRECTED EFFECTIVE FLOODPLAIN ($Q_{100}=1,640$ CFS)



PLAN - WEST BANK

NO	BY	DATE	DATE	APP.

HASLEY CANYON CREEK CLOMR
SOIL CEMENT BANK PROTECTION
TPM. #18108 DCR VOL. III OF V

LOS ANGELES COUNTY

PACE
Advanced Water Engineering
17520 Newhope Street, Suite 200 | Fountain Valley, CA 92708
P: (714) 481-7300 | www.pacewater.com

PREPARED BY JOSE CRUZ
PROJECT ENGINEER
R.C.E. NO. 72249
EXP. 06/30/2022
DRAWN BY BDP
SCALE AS SHOWN
DESIGNED BY JC
CHECKED BY MEK
DATE 7/25/2024


STATE OF CALIFORNIA
REGISTERED PROFESSIONAL ENGINEER
JOSE CRUZ
No. 72249
CIVIL

TITLE
WEST BANK PROTECTION
PLAN AND PROFILE
EIMP. 2019000489


EXHIBIT
6
JOB NO. A535

THESE DRAWINGS ARE THE PROPERTY OF P.A.C.E. AND SHALL NOT BE REPRODUCED IN ANY MANNER NOR BE USED FOR CONSTRUCTION UNLESS STAMPED "ISSUED FOR CONSTRUCTION".

P:\A535\Engineering\A535-04_Hasley_Canyon_Creek_CLOMR\Exhibits\A535-02-Exhibit 5 - West Bank Profile (Figure-08).dwg - Tab: Layout By: erand on Jul. 25, 2024 at 10:23 am



PROFILE - EAST BANK



PLAN - EAST BANK

LEGEND

- PROPOSED CONDITION FLOODPLAIN ($Q_{100}=1,640$ CFS)
- FEMA 100-YEAR FLOODPLAIN (EFFECTIVE JUNE 2, 2021) FIRM PANELS 0805G, 0815G
- CORRECTED EFFECTIVE FLOODPLAIN ($Q_{100}=1,640$ CFS)

NO	BY	DATE	DATE	APP.

HASLEY CANYON CREEK CLOMR
SOIL CEMENT BANK PROTECTION
TPM. #18108 DGR VOL. III OF V

LOS ANGELES COUNTY

PACE
Advanced Water Engineering
17520 Newhope Street, Suite 200 | Fountain Valley, CA 92708
P: (714) 481-7300 | www.pacewater.com

PREPARED BY JOSE CRUZ
PROJECT ENGINEER
R.C.E. NO. 72249
EXP. 06/30/2022
DRAWN BY BDP
DESIGNED BY JC
CHECKED BY MEK
DATE 7/25/2024



EAST BANK PROTECTION
PLAN AND PROFILE


EIMP. 2019000489

EXHIBIT 7

JOB NO. A535

THESE DRAWINGS ARE THE PROPERTY OF P.A.C.E. AND SHALL NOT BE REPRODUCED IN ANY MANNER NOR BE USED FOR CONSTRUCTION UNLESS STAMPED "ISSUED FOR CONSTRUCTION".

P:\A535\Engineering\A535-04_Hasley_Canyon_Creek_CLOMR\A535-02-Submittal_6-East_Bank_Profile.dwg - Tab: Layout By: erandall on Jul. 25, 2024 at 10:26 am



LEGEND

PROPOSED CONDITION FLOODPLAIN
(Q₁₀₀=1,640 CFS)

CORRECTED EFFECTIVE FLOODPLAIN
(Q₁₀₀=1,640 CFS)

EFFECTIVE FEMA 100-YR
FLOODPLAIN DATED JUNE 2, 2021
(Q₁₀₀=1,640 CFS)

PROPOSED CONDITIONS HEC-RAS SECTION

INEFFECTIVE FLOW AREA

NOTE

1. CONTOURS SHOWN ON THIS MAP ARE BASED ON AERIAL TOPOGRAPHY DATED OCT. 2013

2. ALL ELEVATIONS ARE SHOWN IN FEET AND DECIMALS THEREOF BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88).

100 0 100 200

SCALE 1"=100'

SCALE 1"=150'

DESIGNED E.M.R.

DRAWN M.M.T.

CHECKED J.C.

DATE 03/2023

JOB NO. 4535

PROFESSIONAL ENGINEER
STATE OF CALIFORNIA
No. 72289
CIVIL

TITLE

HASLEY CANYON CREEK
GLOMR
TOPOGRAPHIC WORKMAP

JOB

HASLEY CANYON CREEK
VALENCIA COMMERCE
CENTER
Los Angeles County CA

EXHIBIT

8

JOB NO.

A535

DATE APP.

REVISIONS

NO.

BY

DATE

REVISIONS

DATE

APP.

THESE DRAWINGS ARE THE PROPERTY OF P.A.C.E. AND SHALL NOT BE REPRODUCED IN ANY MANNER NOR BE USED FOR CONSTRUCTION UNLESS STAMPED "ISSUED FOR CONSTRUCTION".



Appendix A – MT-2 Forms

MT-2 Form 1: Overview and Concurrence

DEPARTMENT OF HOMELAND SECURITY
Federal Emergency Management Agency
OVERVIEW & CONCURRENCE FORM

OMB Control Number: 1660-0016
Expiration: 1/31/2024

PAPERWORK BURDEN DISCLOSURE NOTICE

Public reporting burden for this form is estimated to average 1 hours per response. The burden estimate includes the time for reviewing instructions, searching existing data sources, gathering and maintaining the needed data, and completing, reviewing, and submitting the form. You are not required to respond to this collection of information unless it displays a valid OMB control number. Send comments regarding the accuracy of the burden estimate and any suggestions for reducing this burden to: Information Collections Management, Department of Homeland Security, Federal Emergency Management Agency, 500 C Street, SW, Washington, DC 20472 , Paperwork Reduction Project (1660-0016). Submission of the form is required to obtain or retain benefits under the National Flood Insurance Program. **Please do not send your completed survey to the above address.**

PRIVACY ACT STATEMENT

AUTHORITY: The National Flood Insurance Act of 1968, Public Law 90-448, as amended by the Flood Disaster Protection Act of 1973, Public Law 93-234.

PRINCIPAL PURPOSE(S): This information is being collected for the purpose of determining an applicant's eligibility to request changes to National Flood Insurance Program (NFIP) Flood Insurance Rate Maps (FIRM).

ROUTINE USE(S): The information on this form may be disclosed as generally permitted under 5 U.S.C § 552a(b) of the Privacy Act of 1974, as amended. This includes using this information as necessary and authorized by the routine uses published in DHS/FEMA/NFIP/LOMA-1 National Flood Insurance Program (NFIP); Letter of Map Amendment (LOMA) February 15, 2006, 71 FR 7990.

DISCLOSURE: The disclosure of information on this form is voluntary; however, failure to provide the information requested may delay or prevent FEMA from processing a determination regarding a requested change to a (NFIP) Flood Insurance Rate Maps (FIRM).

A. REQUESTED RESPONSE FROM DHS-FEMA

This request is for a (check one):

☐ CLOMR: A letter from DHS-FEMA commenting on whether a proposed project, if built as proposed, would justify a map revision or proposed hydrology changes (See 44 CFR Ch. 1, Parts 60, 65 & 72). All CLOMRs require documentation of compliance with the Endangered Species Act. Refer to the Instructions for details.

☐ LOMR: A letter from DHS-FEMA officially revising the current NFIP map to show the changes to floodplains, regulatory floodway or flood elevations. (See 44 CFR Ch. 1, Parts 60, 65 & 72).

B. OVERVIEW

1. The NFIP map panel(s) affected for all impacted communities is (are):

Community No.	Community Name	State	Map No.	Panel No.	Effective Date

2. a. Flooding Source:

b. Types of Flooding: ☐ Riverine ☐ Coastal ☐ Shallow Flooding (e.g., Zones AO and AH)
☐ Alluvial Fan ☐ Lakes ☐ Other (Attach Description)

3. Project Name/Identifier:

4. FEMA zone designations (choices: A, AH, AO, A1-A30, A99, AE, AR, V, V1-V30, VE, B, C, D, X)

a. Effective:

b. Revised:

5. Basis for Request and Type of Revision:

a. The basis for this revision request is (check all that apply)

- | | | | |
|---|---|---|---|
| <input type="checkbox"/> Physical Change | <input type="checkbox"/> Improved Methodology/Data | <input type="checkbox"/> Regulatory Floodway Revision | <input type="checkbox"/> Base Map Changes |
| <input type="checkbox"/> Coastal Analysis | <input type="checkbox"/> Hydraulic Analysis | <input type="checkbox"/> Hydrologic Analysis | <input type="checkbox"/> Corrections |
| <input type="checkbox"/> Weir-Dam Changes | <input type="checkbox"/> Levee Certification | <input type="checkbox"/> Alluvial Fan Analysis | <input type="checkbox"/> Natural Changes |
| <input type="checkbox"/> New Topographic Data | <input type="checkbox"/> Other (Attach Description) | | |

Note: A photograph and narrative description of the area of concern is not required, but is very helpful during review.

b. The area of revision encompasses the following structures (check all that apply)

- Structures:
- | | | |
|---|--|---|
| <input type="checkbox"/> Channelization | <input type="checkbox"/> Levee/Floodwall | <input type="checkbox"/> Bridge/Culvert |
| <input type="checkbox"/> Dam | <input type="checkbox"/> Fill | <input type="checkbox"/> Other (Attach Description) |

6. ☐ Documentation of ESA compliance is submitted (required to initiate CLOMR review). Please refer to the instructions for more information.

C. REVIEW FEE

Has the review fee for the appropriate request category been included? ☐ Yes Fee amount: \$ _____
☐ No, Attach Explanation

- Please see the DHS-FEMA Web site at <http://www.fema.gov/forms-documents-and-software/flood-map-related-fees> for Fee Amounts and Exemptions.

D. SIGNATURES

1. REQUESTOR'S SIGNATURE

All documents submitted in support of this request are correct to the best of my knowledge. I understand that any false statement may be punishable by fine or imprisonment under Title 18 of the United States Code, Section 1001.

Name:	Company:	
Mailing Address:	Daytime Telephone:	Fax No.:
	E-mail Address:	
	Date:	

Signature of Requestor (required): *Alex Herrrell*


2. COMMUNITY CONCURRENCE

As the community official responsible for floodplain management, I hereby acknowledge that we have received and reviewed this Letter of Map Revision (LOMR) or conditional LOMR request. Based upon the community's review, we find the completed or proposed project meets or is designed to meet all of the community floodplain management requirements, including the requirements for when fill is placed in the regulatory floodway, and that all necessary Federal, State, and local permits have been, or in the case of a conditional LOMR, will be obtained. For Conditional LOMR requests, the applicant has documented Endangered Species Act (ESA) compliance to FEMA prior to FEMA's review of the Conditional LOMR application. For LOMR requests, I acknowledge that compliance with Sections 9 and 10 of the ESA has been achieved independently of FEMA's process. For actions authorized, funded, or being carried out by Federal or State agencies, documentation from the agency showing its compliance with Section 7(a)(2) of the ESA will be submitted. In addition, we have determined that the land and any existing or proposed structures to be removed from the SFHA are or will be reasonably safe from flooding as defined in 44CFR 65.2(c), and that we have available upon request by FEMA, all analyses and documentation used to make this determination.

Community Official's Name and Title:		
Mailing Address:	Community Name:	
	Daytime Telephone:	Fax No.:
	E-mail Address:	
Community Official's Signature (required):		Date:

3. CERTIFICATION BY REGISTERED PROFESSIONAL ENGINEER AND/OR LAND SURVEYOR

This certification is to be signed and sealed by a licensed land surveyor, registered professional engineer, or architect authorized by law to certify elevation information data, hydrologic and hydraulic analysis, and any other supporting information as per NFIP regulations paragraph 65.2(b) and as described in the MT-2 Forms Instructions. All documents submitted in support of this request are correct to the best of my knowledge. I understand that any false statement may be punishable by fine or imprisonment under Title 18 of the United States Code, Section 1001.


Certifier's Name:		License No.:	Expiration Date: 6/30/2026
Company Name:		Mailing Address:	
Telephone No.:	Fax No.:		
E-mail Address:			
Signature: 			Date:

Ensure the forms that are appropriate to your revision request are included in your submittal.

Form Name and (Number)

Required if ...

- | | |
|--|---|
| <input type="checkbox"/> Riverine Hydrology and Hydraulics Form (Form 2) | New or revised discharges or water-surface elevations |
| <input type="checkbox"/> Riverine Structures Form (Form 3) | Channel is modified, addition/revision of bridge/culverts, addition/revision of levee/floodwall, addition/revision of dam |
| <input type="checkbox"/> Coastal Analysis Form (Form 4) | New or revised coastal elevations |
| <input type="checkbox"/> Coastal Structures Form (Form 5) | Addition/revision of coastal structure |
| <input type="checkbox"/> Alluvial Fan Flooding Form (Form 6) | Flood control measures on alluvial fans |



MT-2 Form 2: Riverine Hydrology and Hydraulics

DEPARTMENT OF HOMELAND SECURITY
Federal Emergency Management Agency
RIVERINE HYDROLOGY & HYDRAULICS FORM (FORM 2)

OMB Control Number: 1660-0016
Expiration: 1/31/2024

PAPERWORK BURDEN DISCLOSURE NOTICE

Public reporting burden for this form is estimated to average 3.5 hours per response. The burden estimate includes the time for reviewing instructions, searching existing data sources, gathering and maintaining the needed data, and completing, reviewing, and submitting the form. You are not required to respond to this collection of information unless it displays a valid OMB control number. Send comments regarding the accuracy of the burden estimate and any suggestions for reducing this burden to: Information Collections Management, Department of Homeland Security, Federal Emergency Management Agency, 500 C Street, SW, Washington, DC 20472, Paperwork Reduction Project (1660-0016). Submission of the form is required to obtain or retain benefits under the National Flood Insurance Program. **Please do not send your completed survey to the above address.**

PRIVACY ACT STATEMENT

AUTHORITY: The National Flood Insurance Act of 1968, Public Law 90-448, as amended by the Flood Disaster Protection Act of 1973, Public Law 93-234.

PRINCIPAL PURPOSE(S): This information is being collected for the purpose of determining an applicant's eligibility to request changes to National Flood Insurance Program (NFIP) Flood Insurance Rate Maps (FIRM).

ROUTINE USE(S): The information on this form may be disclosed as generally permitted under 5 U.S.C § 552a(b) of the Privacy Act of 1974, as amended. This includes using this information as necessary and authorized by the routine uses published in DHS/FEMA/NFIP/LOMA-1 National Flood Insurance Program (NFIP); Letter of Map Amendment (LOMA) February 15, 2006, 71 FR 7990.

DISCLOSURE: The disclosure of information on this form is voluntary; however, failure to provide the information requested may delay or prevent FEMA from processing a determination regarding a requested change to a (NFIP) Flood Insurance Rate Maps (FIRM).

Flooding Source: _____

Note: Fill out one form for each flooding source studied

A. HYDROLOGY

1. Reason for New Hydrologic Analysis (check all that apply):

- | | | |
|--|--|--|
| <input type="checkbox"/> Not revised (skip to section B) | <input type="checkbox"/> No existing analysis | <input type="checkbox"/> Improved data |
| <input type="checkbox"/> Alternative methodology | <input type="checkbox"/> Proposed Conditions (CLOMR) | <input type="checkbox"/> Changed physical condition of watershed |

2. Comparison of Representative 1%-Annual-Chance Discharges

Location	Drainage Area (Sq. Mi.)	Effective/FIS (cfs)	Revised (cfs)
----------	-------------------------	---------------------	---------------

3. Methodology for New Hydrologic Analysis (check all that apply)

- ☐ Precipitation/Runoff Model → Specify Model: _____ Duration: _____ Rainfall Amount: _____
- ☐ Statistical Analysis of Gage Records
- ☐ Regional Regression Equations ☐ Other (please attach description)

Please enclose all relevant models in digital format, maps, computations (including computation of parameters), and documentation to support the new analysis.

4. Review/Approval of Analysis

If your community requires a regional, state, or federal agency to review the hydrologic analysis, please attach evidence of approval/review.

4. HEC-RAS File Description**:

5. Impacts of Sediment Transport on Hydrology

Is the hydrology for the revised flooding source(s) affected by sediment transport? ☐ Yes ☐ No

If yes, then fill out Section F (Sediment Transport) of Form 3. If No, then attach your explanation.

B. HYDRAULICS

1. Reach to be Revised

Description	Cross Section	Water-Surface Elevation (ft.)	
		Effective	Proposed/Revised
Downstream Limit*			
Upstream Limit*			

*Proposed/Revised elevations must tie-into the Effective elevations within 0.5 foot at the downstream and upstream limits of revision.

2. Hydraulic Method/Model Used: _____

☐ Steady State ☐ Unsteady State ☐ One-Dimensional ☐ Two-Dimensional

3. Pre-Submittal Review of Hydraulic Models*

DHS-FEMA has developed two review programs, CHECK-2 and CHECK-RAS, to aid in the review of HEC-2 and HEC-RAS hydraulic models, respectively. We recommend that you review your HEC-2 and HEC-RAS models with CHECK-2 and CHECK-RAS.

4. HEC-RAS File Description**:

Models Submitted	Natural Run		Floodway Run		Datum
Duplicate Effective Model*	File Name:	Plan Name:	File Name:	Plan Name:	
Corrected Effective Model*	File Name:	Plan Name:	File Name:	Plan Name:	
Existing or Pre-Project Conditions Model	File Name:	Plan Name:	File Name:	Plan Name:	
Revised or Post-Project Conditions Model	File Name:	Plan Name:	File Name:	Plan Name:	
Other - (attach description)	File Name:	Plan Name:	File Name:	Plan Name:	

* For details, refer to the corresponding section of the instructions.

**See instructions for information about modeling other than HEC-RAS. ☐ Digital Models Submitted? (Required)

C. MAPPING REQUIREMENTS

A **certified topographic work map** must be submitted showing the following information (where applicable): the boundaries of the effective, existing, and proposed conditions 1%-annual-chance floodplain (for approximate Zone A revisions) or the boundaries of the 1%- and 0.2%-annual-chance floodplains and regulatory floodway (for detailed Zone AE, AO, and AH revisions); location and alignment of all cross sections with stationing control indicated; stream, road, and other alignments (e.g., dams, levees, etc.); current community easements and boundaries; boundaries of the requester's property; certification of a registered professional engineer registered in the subject State; location and description of reference marks; and the referenced vertical datum (NGVD, NAVD, etc.).

Topographic Information:

☐ Digital Mapping (GIS/CADD) Data Submitted (preferred)

Source:

Date:

Vertical Datum:

Spatial Projection:

Accuracy:

Note that the boundaries of the existing or proposed conditions floodplains and regulatory floodway to be shown on the revised FIRM and/or FBFM must tie-in with the effective floodplain and regulatory floodway boundaries. Please attach a **copy of the effective FIRM and/or FBFM**, at the same scale as the original, annotated to show the boundaries of the revised 1%-and 0.2%-annual-chance floodplains and regulatory floodway that tie-in with the boundaries of the effective 1%-and 0.2%-annual-chance floodplain and regulatory floodway at the upstream and downstream limits of the area on revision.

☐ Annotated FIRM and/or FBFM (Required)

D. COMMON REGULATORY REQUIREMENTS*

1. For LOMR/CLOMR requests, do Base Flood Elevations (BFEs) or Special Flood Hazard Areas (SFHAs) increase compared to the effective BFEs? ☐ Yes ☐ No

If Yes, please attach **proof of property owner notification**. Examples of property owner notifications can be found in the MT-2 Form 2 Instructions.

2. For CLOMR requests, if either of the following is true, please submit **evidence of compliance with Section 65.12 of the NFIP regulations**:

- The proposed project encroaches upon a regulatory floodway and would result in increases above 0.00 foot compared to pre-project conditions.
- The proposed project encroaches upon a SFHA with or without BFEs established and would result in increases above 1.00 foot compared to pre-project conditions.

3. Does the request involve the placement or proposed placement of fill? ☐ Yes ☐ No

If Yes, the community must be able to certify that the area to be removed from the special flood hazard area, to include any structures or proposed structures, meets all of the standards of the local floodplain ordinances, and is reasonably safe from flooding in accordance with the NFIP regulations set forth at 44 CFR 60.3(A)(3), 65.5(a)(4), and 65.6(a)(14). Please see the MT-2 instructions for more information.

4. Does the request involve the placement or proposed placement of fill? ☐ Yes ☐ No

If Yes, attach **evidence of regulatory floodway revision notification**. As per Paragraph 65.7(b)(1) of the NFIP Regulations, notification is required for requests involving revisions to the regulatory floodway Elements and examples of regulatory floodway revision notification can be found in the MT-2 Form 2 Instructions.

5. For CLOMR requests, please submit documentation to FEMA and the community to show that you have complied with Sections 9 and 10 of the Endangered Species Act (ESA). For actions authorized, funded, or being carried out by Federal or State agencies, please submit documentation from the agency showing its compliance with Section 7(a)(2) of the ESA. Please see the MT-2 instructions for more detail.

MT-2 Form 3: Riverine Structures

DEPARTMENT OF HOMELAND SECURITY
Federal Emergency Management Agency
RIVERINE STRUCTURES FORM (FORM 3)

OMB Control Number: 1660-0016
Expiration: 1/31/2024

PAPERWORK BURDEN DISCLOSURE NOTICE

Public reporting burden for this form is estimated to average 3.5 hours per response. The burden estimate includes the time for reviewing instructions, searching existing data sources, gathering and maintaining the needed data, and completing, reviewing, and submitting the form. You are not required to respond to this collection of information unless it displays a valid OMB control number. Send comments regarding the accuracy of the burden estimate and any suggestions for reducing this burden to: Information Collections Management, Department of Homeland Security, Federal Emergency Management Agency, 500 C Street, SW, Washington, DC 20472, Paperwork Reduction Project (1660-0016). Submission of the form is required to obtain or retain benefits under the National Flood Insurance Program. **Please do not send your completed survey to the above address.**

PRIVACY ACT STATEMENT

AUTHORITY: The National Flood Insurance Act of 1968, Public Law 90-448, as amended by the Flood Disaster Protection Act of 1973, Public Law 93-234.

PRINCIPAL PURPOSE(S): This information is being collected for the purpose of determining an applicant's eligibility to request changes to National Flood Insurance Program (NFIP) Flood Insurance Rate Maps (FIRM).

ROUTINE USE(S): The information on this form may be disclosed as generally permitted under 5 U.S.C § 552a(b) of the Privacy Act of 1974, as amended. This includes using this information as necessary and authorized by the routine uses published in DHS/FEMA/NFIP/LOMA-1 National Flood Insurance Program (NFIP); Letter of Map Amendment (LOMA) February 15, 2006, 71 FR 7990.

DISCLOSURE: The disclosure of information on this form is voluntary; however, failure to provide the information requested may delay or prevent FEMA from processing a determination regarding a requested change to a (NFIP) Flood Insurance Rate Maps (FIRM).

Flooding Source: _____

Note: Fill out one form for each flooding source studied

A. GENERAL

Complete the appropriate section(s) for each Structure listed below:

Channelization:	complete Section B
Bridge/Culvert:	complete Section C
Dam:	complete Section D
Levee/Floodwall:	complete Section E
Sediment Transport:	complete Section F (if required)

Description Of Modeled Structure

1. Name of Structure: _____

Type (check one): ☐ Channelization ☐ Bridge/Culvert ☐ Levee/Floodwall ☐ Dam

Location of Structure: _____

Downstream Limit/Cross Section: _____

Upstream Limit/Cross Section: _____

2. Name of Structure: _____

Type (check one): ☐ Channelization ☐ Bridge/Culvert ☐ Levee/Floodwall ☐ Dam

Location of Structure: _____

Downstream Limit/Cross Section: _____

Upstream Limit/Cross Section: _____

3. Name of Structure: _____

Type (check one): ☐ Channelization ☐ Bridge/Culvert ☐ Levee/Floodwall ☐ Dam

Location of Structure: _____

Downstream Limit/Cross Section: _____

Upstream Limit/Cross Section: _____

NOTE: FOR MORE STRUCTURES, ATTACH ADDITIONAL PAGES AS NEEDED.

B. CHANNELIZATION

Flooding Source: _____

Name of Structure: _____

1. Hydraulic Considerations

The channel was designated to carry _____ (cfs) and/or the _____ - year flood

The design elevation in the channel is based on (check one):

☐ Subcritical flow ☐ Critical flow ☐ Supercritical flow ☐ Energy grade line

If there is the potential for a hydraulic jump at the following locations, check all that apply and attach an explanation of how the hydraulic jump is controlled without affecting the stability of the channel.

☐ Inlet to channel ☐ Outlet to channel ☐ At Drop Structures ☐ At Transitions

☐ Other locations (specify): _____

2. Channel Design Plans

Attach the plans of the channelization certified by a registered professional engineer, as described in the instructions.

3. Accessory Structures

The channelization includes (check one):

☐ Levees [Attach Section E (Levee/Floodwall)] ☐ Drop structures ☐ Superelevated sections ☐ Energy dissipater

☐ Transitions in cross sectional geometry ☐ Debris basin/detention basin [Attach Section D (Dam/Basin)] ☐ Weir

☐ Other (Describe): _____

4. Sediment Transport Considerations

Are the hydraulics of the channel affected by sediment transport? ☐ Yes ☐ No

If yes, then fill out Section F (Sediment Transport) of Form 3. If No, then attach your explanation for why sediment transport was not considered.

C. BRIDGE/CULVERT

Flooding Source: _____

Name of Structure: _____

1. This revision reflects (check one):

- ☐ Bridge/Culvert not modeled in the FIS
☐ Modified Bridge/Culvert previously modeled in the FIS
☐ Revised analysis of Bridge/Culvert previously modeled in the FIS

2. Hydraulic model used to analyze the structure (e.g., HEC-2 with special bridge routine, WSPRO, HY8): _____

If different than hydraulic analysis for the flooding source, justify why the hydraulic analysis used for the flooding source could not analyze the structures. Attach justification.

3. Attach plans of the structures certified by a registered professional engineer. The plan detail and information should include the following (check the information that has been provided):

- | | |
|---|--|
| <input type="checkbox"/> Dimensions (height, width, span, radius, length) | <input type="checkbox"/> Distance between Cross Sections |
| <input type="checkbox"/> Shape (culverts only) | <input type="checkbox"/> Erosion Protection |
| <input type="checkbox"/> Material | <input type="checkbox"/> Low Chord Elevations - Upstream and Downstream |
| <input type="checkbox"/> Beveling and Rounding | <input type="checkbox"/> Top of Road Elevations - Upstream and Downstream |
| <input type="checkbox"/> Wink Wall Angle | <input type="checkbox"/> Structure Invert Elevations - Upstream and Downstream |
| <input type="checkbox"/> Skew Angle | <input type="checkbox"/> Stream Invert Elevations - Upstream and Downstream |
| | <input type="checkbox"/> Cross-Section Locations |

4. Sediment Transport Considerations

Are the hydraulics of the channel affected by sediment transport? ☐ Yes ☐ No

If yes, then fill out Section F (Sediment Transport) of Form 3. If No, then attach your explanation for why sediment transport was not considered.

D. DAM/BASIN

Flooding Source: _____

Name of Structure: _____

1. This request is for (check one): ☐ Existing Dam/Basin ☐ New Dam/Basin ☐ Modification of existing Dam/Basin

2. The Dam/Basin was designed by (check one): ☐ Federal Agency ☐ State Agency ☐ Private Organization

☐ Local Government Agency Name of the Agency or Organization: _____

3. The Dam was permitted as (check one): ☐ Federal Dam ☐ State Dam

Provide the permit or identification number (ID) for the dam and the appropriate permitting agency or organization

Permit or ID number _____ Permitting Agency or Organization _____

a. ☐ Local Government Dam ☐ Private Dam

Provided related drawings, specification and supporting design information.

4. Does the project involve revised hydrology? ☐ Yes ☐ No

If Yes, complete the Riverine Hydrology & Hydraulics Form (Form 2).

Was the dam/basin designed using critical duration storm? (must account for the maximum volume of runoff)

☐ Yes, provide supporting documentation with your completed Form 2.

☐ No, provide a written explanation and justification for not using the critical duration storm.

5. Does the submittal include debris/sediment yield analysis? ☐ Yes ☐ No

If Yes, then fill out Section F (Sediment Transport). If No, then attach your explanation for why debris/sediment analysis was not considered?

6. Does the Base Flood Elevation behind the dam/basin or downstream of the dam/basin change? ☐ Yes ☐ No

If Yes, complete the Riverine Hydrology & Hydraulics Form (Form 2) and complete the table below.

Stillwater Elevation Behind the Dam/Basin

FREQUENCY (% annual chance)	FIS	REVISED
-----------------------------	-----	---------

10-year (10%)		
---------------	--	--

50-year (2%)		
--------------	--	--

100-year (1%)		
---------------	--	--

500-year (0.2%)		
-----------------	--	--

Normal Pool Elevation		
-----------------------	--	--

7. Please attach a copy of the formal Operation and Maintenance Plan

E. LEVEE/FLOODWALL

1. System Elements

a. This Levee/Floodwall analysis is based on (check one):

<input type="checkbox"/> Upgrading of an existing levee/floodwall system	<input type="checkbox"/> A newly constructed levee/floodwall system	<input type="checkbox"/> Reanalysis of an existing levee/floodwall system
--	---	---

b. Levee elements and locations are (check one):

☐ Earthen embankment, dike, berm, etc

Stationed _____ to _____

☐ Structured floodwall

Stationed _____ to _____

☐ Other (describe): _____

Stationed _____ to _____

E. LEVEE/FLOODWALL (CONTINUED)

- c. Structural Type (check one): ☐ Monolithic cast-in place reinforced concrete ☐ Reinforced concrete masonry block
☐ Sheet piling ☐ Other (describe): _____

- d. Has this levee/floodwall system been certified by a Federal agency to provide protection from the base flood?
☐ Yes ☐ No

If Yes, by which agency? _____

- e. Attach certified drawings containing the following information (indicate drawing sheet numbers):

1. Plan of the levee embankment and floodwall structures. Sheet Numbers: _____
2. A profile of the levee/floodwall system showing the Base Flood Elevation (BFE), levee and/or wall crest and foundation, and closure locations for the total levee system. Sheet Numbers: _____
3. A profile of the levee/floodwall system showing the Base Flood Elevation (BFE), levee and/or wall crest and foundation, and closure locations for the total levee system. Sheet Numbers: _____
4. A layout detail for the embankment protection measures. Sheet Numbers: _____
5. Location, layout, and size and shape of the levee embankment features, foundation treatment, Floodwall structure, closure structures, and pump stations. Sheet Numbers: _____

2. Freeboard

- a. The minimum freeboard provided above the BFE is:

Riverine

- 3.0 feet or more at the downstream end and throughout ☐ Yes ☐ No
3.5 feet or more at the upstream end ☐ Yes ☐ No
4.0 feet within 100 feet upstream of all structures and/or constrictions ☐ Yes ☐ No

Coastal

- 1.0 foot above the height of the one percent wave associated with the 1%-annual-chance stillwater surge elevation or maximum wave runoff (whichever is greater). ☐ Yes ☐ No
2.0 feet above the 1%-annual-chance stillwater surge elevation ☐ Yes ☐ No

Please note, occasionally exceptions are made to the minimum freeboard requirement. If an exception is requested, attach documentation addressing Paragraph 65.10(b)(1)(ii) of the NFIP Regulations.

If No is answered to any of the above, please attach an explanation.

- b. Is there an indication from historical records that ice-jamming can affect the BFE? ☐ Yes ☐ No

3. Closures

- a. Openings through the levee system (check one): ☐ Exists ☐ Does not exist

If opening exists, list all closures:

Channel Station	Left or Right Bank	Opening Type	Highest Elevation for Opening Invert	Type of Closure Device

(Extend table on an added sheet as needed and reference)

Note: Geotechnical and geologic data

In addition to the required detailed analysis reports, data obtained during field and laboratory investigations and used in the design analysis for the following system features should be submitted in a tabulated summary form. (Reference U.S. Army Corps of Engineers [USACE] EM-1110-2-1906 Form 2086.)

E. LEVEE/FLOODWALL (CONTINUED)

4. Embarkment Protection

- a. The maximum levee slope land side is: _____
- b. The maximum levee slope flood side is: _____
- c. The range of velocities along the levee during the base flood is: _____ (min) to _____ (max)
- d. Embankment material is protected by (describe what kind): _____
- e. Riprap Design Parameters (check one): ☐ Velocity ☐ Tractive Stress
- Attach references

Reach	Sideslope	Flow Depth	Velocity	Curve or Straight	Stone Riprap			Depth of Toedown
					D ₁₀₀	D ₅₀	Thickness	
Sta _____ to _____	_____	_____	_____	_____	_____	_____	_____	_____
Sta _____ to _____	_____	_____	_____	_____	_____	_____	_____	_____
Sta _____ to _____	_____	_____	_____	_____	_____	_____	_____	_____
Sta _____ to _____	_____	_____	_____	_____	_____	_____	_____	_____
Sta _____ to _____	_____	_____	_____	_____	_____	_____	_____	_____
Sta _____ to _____	_____	_____	_____	_____	_____	_____	_____	_____

(Extend table on an added sheet as needed and reference each entry)

- f. Is a bedding/filter analysis and design attached? ☐ Yes ☐ No
- g. Describe the analysis used for other kinds of protection used (include copies of the design analysis):

Attach engineering analysis to support construction plans.

5. Embarkment and Foundation Stability

- a. Identify locations and describe the basis for selection of critical location for analysis:
- ☐ Overall height: STA: _____, height _____ ft.
- ☐ Limiting foundation soil strength:
- Strength ϕ = _____ degrees, c = _____ psf
- Slope: SS = _____ (h) to _____ (v)
- (Repeat as needed on an added sheet for additional locations)
- b. Specify the embankment stability analysis methodology used (e.g., circular arc, sliding block, infinite slope, etc.):
- c. Summary of stability analysis results: _____

E. LEVEE/FLOODWALL (CONTINUED)

5. Embankment and Foundation Stability (continued)

Case	Loading Conditions	Critical Safety Factor	Criteria (Min.)
I	End of construction		1.3
II	Sudden drawdown		1.0
III	Critical flood stage		1.4
IV	Steady seepage at flood stage		1.4
VI	Earthquake (Case I)		1.0

(Reference: USACE EM-1110-2-1913 Table 6-1)

d. Was a seepage analysis for the embankment performed? ☐ Yes ☐ No

If Yes, describe methodology used:

e. Was a seepage analysis for the embankment performed? ☐ Yes ☐ No

f. Were uplift pressures at the embankment landside toe checked? ☐ Yes ☐ No

g. Were seepage exit gradients checked for piping potential? ☐ Yes ☐ No

h. The duration of the base flood hydrograph against the embankment is _____ hours.

Attach engineering analysis to support construction plans.

6. Floodwall and Foundation Stability

a. Describe analysis submittal based on Code (check one): ☐ UBC (1988) ☐ Other (specify): _____

b. Stability analysis submitted provides for: ☐ Overturning ☐ Sliding ☐ If not, explain: _____

c. Loading included in the analyses were: ☐ Lateral earth @ $P_A =$ _____ psf; $P_p =$ _____ psf

☐ Surcharge-Slope @ _____, ☐ surface _____ psf

☐ Wind @ $P_w =$ _____ psf

☐ Seepage (Uplift); _____ ☐ Earthquake @ $P_{eq} =$ _____ %g

☐ 1%-annual-chance significant wave height: _____ ft.

☐ 1%-annual-chance significant wave period: _____ sec.

d. Summary of Stability Analysis Results: Factors of Safety.

Itemize for each range in site layout dimension and loading condition limitation for each respective reach.

Loading Condition	Criteria (Min)		Sta	To	Sta	To
	Overturn	Sliding	Overturn	Sliding	Overturn	Sliding
Dead & Wind	1.5	1.5				
Dead & Soil	1.5	1.5				
Dead, Soil, Flood, & Impact	1.5	1.5				
Dead, Soil, & Seismic	1.3	1.3				

(Ref: FEMA 114 Sept 1986; USACE EM 1110-2-2502)

Note: (Extend table on an added sheet as needed and reference)

E. LEVEE/FLOODWALL (CONTINUED)

e. Foundation bearing strength for each soil type:

Bearing Pressure	Sustained Load (psf)	Short Term Load (psf)
Computed design maximum		
Maximum allowable		

f. Foundation scour protection ☐ is, ☐ is not provided. If provided, attach explanation and supporting documentation:
Attach engineering analysis to support construction plans.

7. Settlement

- a. Has anticipated potential settlement been determined and incorporated into the specified construction elevations to maintain the established freeboard margin?
- b. The computed settlement range is _____ ft. to _____ ft.
- c. Settlement of the levee crest is determined to be primarily from : ☐ Foundation consolidation
☐ Embankment compression ☐ Other (Describe): _____
- d. Differential settlement of floodwalls ☐ has ☐ has not been accommodated in the structural design and construction
Attach engineering analysis to support construction plans.

8. Interior Drainage

- a. Specify size of each interior watershed:
Drainage to pressure conduit: _____ acres
Drainage to ponding area: _____ acres
- b. Relationship Established:
- | | | |
|------------------------------------|------------------------------|-----------------------------|
| Ponding elevation vs. storage | <input type="checkbox"/> Yes | <input type="checkbox"/> No |
| Ponding elevation vs. gravity flow | <input type="checkbox"/> Yes | <input type="checkbox"/> No |
| Differential head vs. gravity flow | <input type="checkbox"/> Yes | <input type="checkbox"/> No |
- c. The river flow duration curve is enclosed: ☐ Yes ☐ No
- d. Specify the discharge capacity of the head pressure conduit: _____ cfs
- e. Which flooding conditions were analyzed?
- | | | |
|-----------------------------------|------------------------------|-----------------------------|
| Gravity flow (Interior Watershed) | <input type="checkbox"/> Yes | <input type="checkbox"/> No |
| Common storm (River Watershed) | <input type="checkbox"/> Yes | <input type="checkbox"/> No |
| Historical ponding probability | <input type="checkbox"/> Yes | <input type="checkbox"/> No |
| Coastal wave overtopping | <input type="checkbox"/> Yes | <input type="checkbox"/> No |
- If No for any of the above, attach explanation.
- f. Interior drainage has been analyzed based on joint probability of interior and exterior flooding and the capacities of pumping and outlet facilities to provide the established level of flood protection.
☐ Yes ☐ No If No, attach explanation.
- g. The rate of seepage through the levee system for the base flood is : _____ cfs
- h. The length of levee system used to drive this seepage rate in item g: _____ ft.

E. LEVEE/FLOODWALL (CONTINUED)

8. Interior Drainage (continued)

i. Will pumping plants be used for interior drainage? ☐ Yes ☐ No

If Yes, include the number of pumping plants: _____ For each pumping plant, list:

	Plant #1	Plant #2
The number of pumps		
The ponding storage capacity		
The maximum pumping rate		
The maximum pumping head		
The pumping starting elevation		
The pumping stopping elevation		
Is the discharge facility protected?		
Is there a flood warning plan?		
How much time is available between warning and flooding?		

Will the operation be automatic? ☐ Yes ☐ No

If the pumps are electric; are there backup power sources? ☐ Yes ☐ No

(Reference: USACE EM-1110-2-3101, 3102, 3103, 3104, and 3105)

Include a copy of supporting documentation of data and analysis. Provide a map showing the flooded area and maximum ponding elevations for all interior watersheds that result in flooding.

9. Other Design Criteria

a. The following items have been addressed as stated:

Liquefaction ☐ is ☐ is not a problem

Hydrocompaction ☐ is ☐ is not a problem

Heave differential movement due to soils of high shrink/swell ☐ is ☐ is not a problem

b. For each of these problems, state the basic facts and corrective action taken:

Attach supporting documentation

c. If the levee/floodwall is new or enlarged, will the structure adversely impact flood levels and/or flow velocities floodside of the structure? ☐ Yes ☐ No

d. Sediment Transport Considerations:

Was sediment transport considered? ☐ Yes ☐ No

If Yes, then fill out Section F (Sediment Transport). If No, then attach your explanation for why sediment transport was not considered.

10. Operational Plan and Criteria

a. Are the planned/installed works in full compliance with Part 65.10 of the NFIP Regulations? ☐ Yes ☐ No

b. Does the operation plan incorporate all the provisions for closure devices as required in Paragraph 65.10(c)(1) of the NFIP regulations? ☐ Yes ☐ No

c. Does the operation plan incorporate all the provisions for interior drainage as required in Paragraph 65.10(c)(2) of the NFIP regulations? ☐ Yes ☐ No

If the answer is No to any of the above, please attach supporting documentation.

E. LEVEE/FLOODWALL (CONTINUED)11. Maintenance Plan

Please attach a copy of the formal maintenance plan for the levee/floodwall

12. Operational and Maintenance Plan

Please attach a copy of the formal Operations and Maintenance Plan for the levee/floodwall.

CERTIFICATION OF THE LEVEE DOCUMENTATION

This certification is to be signed and sealed by a licensed registered professional engineer authorized by law to certify elevation information data, hydrologic and hydraulic analysis, and any other supporting information as per NFIP regulations paragraph 65.10(e) and as described in the MT-2 Forms Instructions. All documents submitted in support of this request are correct to the best of my knowledge. I understand that any false statement may be punishable by fine or imprisonment under Title 18 of the United States Code, Section 1001.

Certifier's Name: _____ License No.: _____ Expiration Date: _____

Company Name: _____ Telephone No.: _____ Fax No.: _____

Signature: _____ Date: _____ E-mail Address: _____

CERTIFICATION OF THE LEVEE DOCUMENTATION

Flooding Source: _____

Name of Structure: _____

If there is any indication from historical records that sediment transport (including scour and deposition) can affect the Base Flood Elevation (BFE); and/or based on the stream morphology, vegetative cover, development of the watershed and bank conditions, there is a potential for debris and sediment transport (including scour and deposition) to affect the BFEs, then provide the following information along with the supporting documentation:

Sediment load associated with the base flood discharge: Volume _____ acres-feet

Debris load associated with the base flood discharge: Volume _____ acres-feet

Sediment transport rate _____ (percent concentration by volume)

Method used to estimate sediment transport: _____

Most sediment transport formulas are intended for a range of hydraulic conditions and sediment sizes; attach a detailed explanation for using the selected method.

Method used to estimate scour and/or deposition: Following LA County Hydrology and Sedimentation Manual and a Continuity Analysis using SAM

Method used to revise hydraulic or hydrologic analysis (model) to account for sediment transport: _____

Please note that bulked flows are used to evaluate the performance of a structure during the base flood; however, FEMA does not map BFEs based on bulked flows.

If a sediment analysis has not been performed, an explanation as to why sediment transport (including scour and deposition) will not affect the BFEs or structures must be provided.



Appendix B – Relevant Effective FEMA Data

FEMA FIS: Hasley Canyon Creek Flow Rates

FLOOD INSURANCE STUDY

FEDERAL EMERGENCY MANAGEMENT AGENCY

VOLUME 2 OF 9



LOS ANGELES COUNTY, CALIFORNIA AND INCORPORATED AREAS

COMMUNITY NAME	NUMBER	COMMUNITY NAME	NUMBER
AGOURA HILLS, CITY OF	065072	COMMERCE, CITY OF	060110
ALHAMBRA, CITY OF*	060095	COMPTON, CITY OF	060111
ARCADIA, CITY OF*	065014	COVINA, CITY OF*	065024
ARTESIA, CITY OF*	060097	CUDAHY, CITY OF	060657
AVALON, CITY OF	060098	CULVER CITY, CITY OF	060114
AZUSA, CITY OF	065015	DIAMOND BAR, CITY OF	060741
BALDWIN PARK, CITY OF*	060100	DOWNEY, CITY OF	060645
BELL, CITY OF*	060101	DUARTE, CITY OF*	065026
BELL GARDENS, CITY OF	060656	EL MONTE, CITY OF*	060658
BELLFLOWER, CITY OF	060102	EL SEGUNDO, CITY OF	060118
BEVERLY HILLS, CITY OF*	060655	GARDENA, CITY OF	060119
BRADBURY, CITY OF*	065017	GLENDALE, CITY OF	065030
BURBANK, CITY OF	065018	GLENDORA, CITY OF*	065031
CALABASAS, CITY OF	060749	HAWAIIAN GARDENS, CITY OF*	065032
CARSON, CITY OF	060107	HAWTHORNE, CITY OF*	060123
CERRITOS, CITY OF	060108	HERMOSA BEACH, CITY OF	060124
CLAREMONT, CITY OF*	060109	HIDDEN HILLS, CITY OF	060125

*No Special Flood Hazard Areas Identified

REVISED: June 2, 2021

FLOOD INSURANCE STUDY NUMBER

06037CV002F

Version Number 2.3.3.2



FEMA

COMMUNITY NAME	NUMBER	COMMUNITY NAME	NUMBER
HUNTINGTON PARK, CITY OF*	060126	PICO RIVERA, CITY OF	060148
INDUSTRY, CITY OF*	065035	POMONA, CITY OF*	060149
INGLEWOOD, CITY OF*	065036	RANCHO PALOS VERDES, CITY OF	060464
IRWINDALE, CITY OF*	060129	REDONDO BEACH, CITY OF	060150
LA CANADA FLINTRIDGE, CITY OF*	060669	ROLLING HILLS, CITY OF*	060151
LA HABRA HEIGHTS, CITY OF*	060701	ROLLING HILLS ESTATES, CITY OF*	065054
LA MIRADA, CITY OF	060131	ROSEMEAD, CITY OF*	060153
LA PUENTE*, CITY OF	065039	SAN DIMAS, CITY OF	060154
LA VERNE, CITY OF	060133	SAN FERNANDO, CITY OF	060628
LAKEWOOD, CITY OF	060130	SAN GABRIEL, CITY OF*	065055
LANCASTER, CITY OF	060672	SAN MARINO, CITY OF*	065057
LAWNDALE, CITY OF*	060134	SANTA CLARITA, CITY OF	060729
LOMITA, CITY OF*	060135	SANTA FE SPRINGS, CITY OF	060158
LONG BEACH, CITY OF	060136	SANTA MONICA, CITY OF	060159
LOS ANGELES, CITY OF	060137	SIERRA MADRE, CITY OF*	065059
LOS ANGELES COUNTY UNINCORPORATED AREAS	065043	SIGNAL HILL, CITY OF*	060161
LYNWOOD, CITY OF	060635	SOUTH EL MONTE, CITY OF*	060162
MALIBU, CITY OF	060745	SOUTH GATE, CITY OF	060163
MANHATTAN BEACH, CITY OF	060138	SOUTH PASADENA, CITY OF*	065061
MAYWOOD, CITY OF*	060651	TEMPLE CITY, CITY OF*	060653
MONROVIA, CITY OF*	065046	TORRANCE, CITY OF	060165
MONTEBELLO, CITY OF	060141	VERNON, CITY OF*	060166
MONTEREY PARK, CITY OF*	065047	WALNUT, CITY OF*	065069
NORWALK, CITY OF	060652	WEST COVINA, CITY OF	060666
PALMDALE, CITY OF	060144	WEST HOLLYWOOD, CITY OF*	060720
PALOS VERDES ESTATES, CITY OF	060145	WESTLAKE VILLAGE, CITY OF	060744
PARAMOUNT, CITY OF	065049	WHITTIER, CITY OF	060169
PASADENA, CITY OF*	065050		

*No Special Flood Hazard Areas Identified

REVISED: June 2, 2021

FLOOD INSURANCE STUDY NUMBER

06037CV002F

Version Number 2.3.3.2




FEMA

Table 10: Summary of Discharges, continued

Flooding Source	Location	Drainage Area (Square Miles)	Peak Discharge (cfs)					
			10% Annual Chance	4% Annual Chance	2% Annual Chance	1% Annual Chance Existing	1% Annual Chance Future	0.2% Annual Chance
Harbor District Shallow Flooding	Denker Avenue, vicinity of 204th Street	0.3	60	*	130	170	*	260
Haskell Canyon	At confluence with Bouquet Canyon Creek	9.8	730	*	2,240	3,320	*	7,360
Hasley Canyon Creek	Approximately 1,150 feet downstream of Halsey Canyon Road	7.3	*	*	*	5,544	*	10,163
Hasley Canyon Creek	Approximately 550 feet downstream of Romero Canyon Road	5.9	*	*	*	4,523	*	8,292
Hasley Canyon Creek	Approximately 600 feet downstream of Romero Canyon Road	*	220	*	680	1,006	*	2,230
Hasley Canyon Creek	Approximately 0.2 miles downstream of Hasley Canyon Road	*	330	*	1,010	1,503	*	3,330
Hasley Canyon Creek	At confluence with Castaic Creek	*	360	*	1,110	1,640	*	3,640
Hollywood Shallow Flooding	Third Street at Kenmore Avenue	3.4	800	*	1,800	2,300	*	3,500
Hollywood Shallow Flooding	South of Hollywood Freeway, vicinity of Kenmore Avenue	3.2	830	*	1,800	2,300	*	3,700
Hollywood Shallow Flooding	Santa Monica Boulevard, vicinity of Mariposa Avenue	2.8	940	*	2,100	2,700	*	4,200
Hollywood Shallow Flooding	Madison Avenue at Monroe Street	0.5	160	*	350	440	*	690
Hyde Park Shallow Flooding	South of Southwest Drive, vicinity of Van Ness Avenue	4.2	730	*	1,600	2,100	*	3,200
Hyde Park Shallow Flooding	Wilton Place, vicinity of Gage Avenue	3.3	770	*	1,600	1,900	*	3,000

FEMA Flood Insurance Rate Map Panels



FLOOD HAZARD INFORMATION

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT
THE INFORMATION DEPICTED ON THIS MAP AND SUPPORTING DOCUMENTATION ARE ALSO AVAILABLE IN DIGITAL FORMAT AT [HTTPS://MSC.FEMA.GOV](https://msc.fema.gov)

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, X, AE
		With BFE or Depth Zone AE, AD, AH, VL, AR Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
OTHER AREAS		Area with Reduced Flood Risk due to Levee See Notes Zone X
		Areas of Minimal Flood Hazard Zone X
GENERAL STRUCTURES		Area of Undetermined Flood Hazard Zone D
		Channel, Culvert or Storm Sewer
OTHER FEATURES		Levee, Dike or Floodwall
		Cross Sections with 1% Annual Chance Water Surface Elevation (BFE)
		Coastal Transect
		Coastal Transect Baseline
		Profile Baseline
		Hydrographic Feature
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary

NOTES TO USERS

For information and questions about this map, available products associated with this FIRM including historic versions of this FIRM, how to order products or the National Flood Insurance Program in general, please call the FEMA Map Information eXchange at 1-877-FEMA-MAP (1-877-336-2627) or visit the FEMA Map Service Center website at <https://msc.fema.gov>. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. Many of these products can be ordered or obtained directly from the website. Users may determine the current map date for each FIRM panel by visiting the FEMA Map Service Center website or by calling the FEMA Map Information eXchange.


Communities annexing land on adjacent FIRM panels must obtain a current copy of the adjacent panel as well as the current FIRM index. These may be ordered directly from the Map Service Center at the number listed above.

For community and countywide map dates refer to the Flood Insurance Study report for this jurisdiction.


To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

Base map information shown on this FIRM was derived from digital orthophotography collected by the U.S. Department of Agriculture Farm Service Agency. This imagery was flown in 2014 and was produced with a 1-meter ground sample distance.

SCALE



PANEL LOCATOR



National Flood Insurance Program

NATIONAL FLOOD INSURANCE PROGRAM
FLOOD INSURANCE RATE MAP
LOS ANGELES COUNTY, CALIFORNIA
and Incorporated Areas
PANEL 805 OF 2350


Panel Contains:
COMMUNITY
LOS ANGELES COUNTY
SANTA CLARITA, CITY OF

NUMBER
065043
060729

PANEL
0805
0805

SUFFIX
0
0

VERSION NUMBER
2.3.3.2
MAP NUMBER
06037C0805G
MAP REVISED
JUNE 2, 2021



FLOOD HAZARD INFORMATION

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT
THE INFORMATION DEPICTED ON THIS MAP AND SUPPORTING
DOCUMENTATION ARE ALSO AVAILABLE IN DIGITAL FORMAT AT
[HTTPS://MSC.FEMA.GOV](https://msc.fema.gov)

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, X, D
		With BFE or Depth Zone AE, AD, AH, VL, AR Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
OTHER AREAS		Area with Reduced Flood Risk due to Levee See Notes Zone X
		Areas of Minimal Flood Hazard Zone X
GENERAL STRUCTURES		Area of Undetermined Flood Hazard Zone D
		Channel, Culvert or Storm Sewer
OTHER FEATURES		Levee, Dike or Floodwall
		Cross Sections with 1% Annual Chance Water Surface Elevation (BFE)
		Coastal Transect
		Coastal Transect Baseline
		Profile Baseline
		Hydrographic Feature
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary

NOTES TO USERS

For information and questions about this map, available products associated with this FIRM including historic versions of this FIRM, how to order products or the National Flood Insurance Program in general, please call the FEMA Map Information eXchange at 1-877-FEMA-MAP (1-877-336-2627) or visit the FEMA Map Service Center website at <http://msc.fema.gov>. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. Many of these products can be ordered or obtained directly from the website. Users may determine the current map date for each FIRM panel by visiting the FEMA Map Service Center website or by calling the FEMA Map Information eXchange.


Communities annexing land on adjacent FIRM panels must obtain a current copy of the adjacent panel as well as the current FIRM index. These may be ordered directly from the Map Service Center at the number listed above.

For community and countywide map dates refer to the Flood Insurance Study report for this jurisdiction.


To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

Base map information shown on this FIRM was derived from digital orthophotography collected by the U.S. Department of Agriculture Farm Service Agency. This imagery was flown in 2014 and was produced with a 1-meter ground sample distance.

SCALE



PANEL LOCATOR



National Flood Insurance Program

NATIONAL FLOOD INSURANCE PROGRAM
FLOOD INSURANCE RATE MAP
LOS ANGELES COUNTY, CALIFORNIA
and Incorporated Areas
PANEL 815 OF 2350


Panel Contains:
COMMUNITY
LOS ANGELES COUNTY
SANTA CLARITA, CITY OF

NUMBER
065043
060729

PANEL
0815

SUFFIX
0
G

VERSION NUMBER
2.3.3.2
MAP NUMBER
06037C0815G
MAP REVISED
JUNE 2, 2021



FLOOD HAZARD INFORMATION

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT
THE INFORMATION DEPICTED ON THIS MAP AND SUPPORTING
DOCUMENTATION ARE ALSO AVAILABLE IN DIGITAL FORMAT AT
[HTTPS://MSC.FEMA.GOV](https://MSC.FEMA.GOV)

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AQ, AH, VE, AR Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee See Notes Zone X
OTHER AREAS		NO SCREEN Areas of Minimal Flood Hazard Zone X
		Area of Undetermined Flood Hazard Zone D
GENERAL STRUCTURES		Channel, Culvert or Storm Sewer
		Levee, Dike or Floodwall
OTHER FEATURES		Cross Sections with 1% Annual Chance Water Surface Elevation (BFE)
		Coastal Transect
		Coastal Transect Baseline
		Profile Baseline
		Hydrographic Feature
		Base Flood Elevation Line (BFE)
		Limit of Study
OTHER FEATURES		Jurisdiction Boundary

NOTES TO USERS

For information and questions about this map, available products associated with this FIRM including historic versions of this FIRM, how to order products or the National Flood Insurance Program in general, please call the FEMA Map Information eXchange at 1-877-FEMA-MAP (1-877-336-2627) or visit the FEMA Map Service Center website at <http://msc.fema.gov>. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. Many of these products can be ordered or obtained directly from the website. Users may determine the current map date for each FIRM panel by visiting the FEMA Map Service Center website or by calling the FEMA Map Information eXchange.


Communities annexing land on adjacent FIRM panels must obtain a current copy of the adjacent panel as well as the current FIRM index. These may be ordered directly from the Map Service Center at the number listed above.

For community and countywide map dates refer to the Flood Insurance Study report for this jurisdiction.

To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-636-6620.

Base map information shown on this FIRM was derived from digital orthophotography collected by the U.S. Department of Agriculture Farm Service Agency. This imagery was flown in 2014 and was produced with a 1-meter ground sample distance.

SCALE



PANEL LOCATOR



National Flood Insurance Program

NATIONAL FLOOD INSURANCE PROGRAM
FLOOD INSURANCE RATE MAP
LOS ANGELES COUNTY, CALIFORNIA
and Incorporated Areas
PANEL 785 OF 2350

Panel Containing:
COMMUNITY
LOS ANGELES COUNTY

NUMBER PANEL SUFFIX
065043 0785 G

VERSION NUMBER
2.3.3.2
MAP NUMBER
06037C0785G
MAP REVISED
JUNE 2, 2021

***FEMA LOMR: Castaic Creek Soil Cement Bank Protection
October 2021***



Federal Emergency Management Agency

Washington, D.C. 20472

LETTER OF MAP REVISION DETERMINATION DOCUMENT

COMMUNITY AND REVISION INFORMATION		PROJECT DESCRIPTION	BASIS OF REQUEST
COMMUNITY	Los Angeles County California (Unincorporated Areas)	NO PROJECT	1D HYDRAULIC ANALYSIS UPDATED TOPOGRAPHIC DATA
	COMMUNITY NO.: 065043		
IDENTIFIER	Castaic Creek Soil Cement Bank Protection PM 26363	APPROXIMATE LATITUDE & LONGITUDE: 34.434, -118.626 SOURCE: USGS QUADRANGLE DATUM: NAD 83	
ANNOTATED MAPPING ENCLOSURES		ANNOTATED STUDY ENCLOSURES	
TYPE: FIRM* NO.: 06037C0792G DATE: June 2, 2021 TYPE: FIRM NO.: 06037C0805G DATE: June 2, 2021 TYPE: FIRM NO.: 06037C0815G DATE: June 2, 2021		DATE OF EFFECTIVE FLOOD INSURANCE STUDY: June 02, 2021 PROFILE(S): 53P, 54P, 96P AND 102P	

Enclosures reflect changes to flooding sources affected by this revision.

* FIRM - Flood Insurance Rate Map

FLOODING SOURCE(S) & REVISED REACH(ES)

See Page 2 for Additional Flooding Sources

Castaic Creek - from just upstream of Highway 126 to just downstream of Commerce Centre Drive.

SUMMARY OF REVISIONS

Flooding Source	Effective Flooding	Revised Flooding	Increases	Decreases
Castaic Creek	BFEs*	BFEs	YES	YES
	Zone AE	Zone AE	YES	YES
	Zone AE	Zone X(shaded)	YES	YES

* BFEs - Base Flood Elevations

DETERMINATION

This document provides the determination from the Department of Homeland Security's Federal Emergency Management Agency (FEMA) regarding a request for a Letter of Map Revision (LOMR) for the area described above. Using the information submitted, we have determined that a revision to the flood hazards depicted in the Flood Insurance Study (FIS) report and/or National Flood Insurance Program (NFIP) map is warranted. This document revises the effective NFIP map, as indicated in the attached documentation. Please use the enclosed annotated map panels revised by this LOMR for floodplain management purposes and for all flood insurance policies and renewals in your community.

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Mapping and Insurance eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMC Clearinghouse, 3601 Eisenhower Avenue, Suite 500, Alexandria, VA 22304-6426. Additional Information about the NFIP is available on our website at <https://www.fema.gov/flood-insurance>.

Patrick "Rick" F. Sacbitt, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration

21-09-1266P

102-I-A-C



Federal Emergency Management Agency

Washington, D.C. 20472

LETTER OF MAP REVISION DETERMINATION DOCUMENT (CONTINUED)

OTHER FLOODING SOURCES AFFECTED BY THIS REVISION

FLOODING SOURCE(S) & REVISED REACH(ES)

Hasley Canyon Creek - from its confluence to approximately 400 feet upstream of the confluence with Castaic Creek.
Hasley Canyon Creek Split - From its convergence to approximately 360 upstream of convergence with Hasley Canyon Creek.

SUMMARY OF REVISIONS

Flooding Source	Effective Flooding	Revised Flooding	Increases	Decreases
Hasley Canyon Creek	BFEs*	BFEs	YES	YES
	Zone AE	Zone AE	YES	YES
Hasley Canyon Creek Split	BFEs*	BFEs	YES	YES
	Zone AE	Zone AE	YES	YES

* BFEs - Base Flood Elevations

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Mapping and Insurance eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMC Clearinghouse, 3601 Eisenhower Avenue, Suite 500, Alexandria, VA 22304-6426. Additional Information about the NFIP is available on our website at <https://www.fema.gov/flood-insurance>.

Patrick "Rick" F. Sacibit, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration



Federal Emergency Management Agency
Washington, D.C. 20472

**LETTER OF MAP REVISION
DETERMINATION DOCUMENT (CONTINUED)**

COMMUNITY INFORMATION

APPLICABLE NFIP REGULATIONS/COMMUNITY OBLIGATION

We have made this determination pursuant to Section 206 of the Flood Disaster Protection Act of 1973 (P.L. 93-234) and in accordance with the National Flood Insurance Act of 1968, as amended (Title XIII of the Housing and Urban Development Act of 1968, P.L. 90-448), 42 U.S.C. 4001-4128, and 44 CFR Part 65. Pursuant to Section 1361 of the National Flood Insurance Act of 1968, as amended, communities participating in the NFIP are required to adopt and enforce floodplain management regulations that meet or exceed NFIP criteria. These criteria, including adoption of the FIS report and FIRM, and the modifications made by this LOMR, are the minimum requirements for continued NFIP participation and do not supersede more stringent State/Commonwealth or local requirements to which the regulations apply.

COMMUNITY REMINDERS

We based this determination on the 1-percent-annual-chance flood discharges computed in the FIS for your community without considering subsequent changes in watershed characteristics that could increase flood discharges. Future development of projects upstream could cause increased flood discharges, which could cause increased flood hazards. A comprehensive restudy of your community's flood hazards would consider the cumulative effects of development on flood discharges subsequent to the publication of the FIS report for your community and could, therefore, establish greater flood hazards in this area.

Your community must regulate all proposed floodplain development and ensure that permits required by Federal and/or State/Commonwealth law have been obtained. State/Commonwealth or community officials, based on knowledge of local conditions and in the interest of safety, may set higher standards for construction or may limit development in floodplain areas. If your State/Commonwealth or community has adopted more restrictive or comprehensive floodplain management criteria, those criteria take precedence over the minimum NFIP requirements.

We will not print and distribute this LOMR to primary users, such as local insurance agents or mortgage lenders; instead, the community will serve as a repository for the new data. We encourage you to disseminate the information in this LOMR by preparing a news release for publication in your community's newspaper that describes the revision and explains how your community will provide the data and help interpret the NFIP maps. In that way, interested persons, such as property owners, insurance agents, and mortgage lenders, can benefit from the information.

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Mapping and Insurance eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMC Clearinghouse, 3601 Eisenhower Avenue, Suite 500, Alexandria, VA 22304-6426. Additional Information about the NFIP is available on our website at <https://www.fema.gov/flood-insurance>.

Patrick "Rick" F. Sacbibit, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration



Federal Emergency Management Agency

Washington, D.C. 20472

LETTER OF MAP REVISION DETERMINATION DOCUMENT (CONTINUED)

We have designated a Consultation Coordination Officer (CCO) to assist your community. The CCO will be the primary liaison between your community and FEMA. For information regarding your CCO, please contact:

Ms. Kathryn Lipiecki
Director, Mitigation Division
Federal Emergency Management Agency, Region IX
1111 Broadway, Suite 1200
Oakland, CA 94607-4052
(510) 627-7211

STATUS OF THE COMMUNITY NFIP MAPS

We will not physically revise and republish the FIRM and FIS report for your community to reflect the modifications made by this LOMR at this time. When changes to the previously cited FIRM panel(s) and FIS report warrant physical revision and republication in the future, we will incorporate the modifications made by this LOMR at that time.

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Mapping and Insurance eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMC Clearinghouse, 3601 Eisenhower Avenue, Suite 500, Alexandria, VA 22304-6426. Additional Information about the NFIP is available on our website at <https://www.fema.gov/flood-insurance>.

A handwritten signature in black ink, appearing to read "Rick F. Sacibit".

Patrick "Rick" F. Sacibit, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration



Federal Emergency Management Agency

Washington, D.C. 20472

LETTER OF MAP REVISION DETERMINATION DOCUMENT (CONTINUED)

PUBLIC NOTIFICATION OF REVISION

A notice of changes will be published in the *Federal Register*. This information also will be published in your local newspaper on or about the dates listed below, and through FEMA's Flood Hazard Mapping website at https://www.floodmaps.fema.gov/fhm/bfe_status/bfe_main.asp

LOCAL NEWSPAPER


Name: *Los Angeles Daily News*
Dates: June 10, 2021 and June 17, 2021


Within 90 days of the second publication in the local newspaper, any interested party may request that we reconsider this determination. Any request for reconsideration must be based on scientific or technical data. Therefore, this letter will be effective only after the 90-day appeal period has elapsed and we have resolved any appeals that we receive during this appeal period. Until this LOMR is effective, the revised flood hazard determination presented in this LOMR may be changed.


This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Mapping and Insurance eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMC Clearinghouse, 3601 Eisenhower Avenue, Suite 500, Alexandria, VA 22304-6426. Additional Information about the NFIP is available on our website at <https://www.fema.gov/flood-insurance>.

A handwritten signature in black ink, appearing to read "Rick F. Sacibit".

Patrick "Rick" F. Sacibit, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration







NOTE: MAP AREA SHOWN ON THIS PANEL IS LOCATED
WITHIN TOWNSHIP 4 NORTH, RANGE 17 WEST.

JOINS PANEL 0785

118° 37' 30"

34° 26' 15"

Los Angeles County
Unincorporated Areas
065043

REVISED
AREA

ZONE AE

JOINS PANEL 0815

Castaic Creek

Profile Baseline








FRANKLIN PKWY

Bridge


HENRY MAYO DR
RAILROAD

3811000mN

126

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
OTHER AREAS OF FLOOD HAZARD OTHER AREAS		Regulatory Floodway
		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee See Notes. Zone X
		Area of Undetermined Flood Hazard Zone D

SCALE



National Flood Insurance Program

NATIONAL FLOOD INSURANCE PROGRAM
FLOOD INSURANCE RATE MAP

LOS ANGELES COUNTY, CALIFORNIA
and Incorporated Areas

PANEL 792 OF 1075

Panel Contains:

COMMUNITY LOS ANGELES COUNTY NUMBER 065043 PANEL 0792 SUFFIX G




REVISED TO
REFLECT LOMR
EFFECTIVE: October 15, 2021


VERSION NUMBER
2.3.3.0

MAP NUMBER
06037C0792G


MAP REVISED
JUNE 2, 2021



REVIS



SCALE



FEMA

National Flood Insurance Program

NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP

LOS ANGELES COUNTY, CALIFORNIA
and Incorporated Areas

805 OF 1075

Panel Contains:

COMMUNITY	NUMBER	PANEL	SUFFIX
LOS ANGELES COUNTY	065043	0805	G
SANTA CLARITA, CITY OF	060729	0805	G

**REVISED TO
REFLECT LOMR
EFFECTIVE: October 15, 2021**



NOTE: MAP AREA SHOWN ON THIS PANEL IS LOCATED WITHIN TOWNSHIP 5 NORTH, RANGE 17 WEST AND TOWNSHIP 5 NORTH, RANGE 16 WEST AND TOWNSHIP 4 NORTH, RANGE 17 WEST AND TOWNSHIP 4 NORTH, RANGE 16 WEST.

VERSION NUMBER
2.3.3.0


MAP NUMBER
06037C0805G

MAP REVISED
JUNE 2, 2021

NOTE: MAP AREA SHOWN ON THIS PANEL IS LOCATED
WITHIN TOWNSHIP 3 NORTH, RANGE 16 WEST AND
TOWNSHIP 3 NORTH, RANGE 17 WEST.



SCALE



National Flood Insurance Program

NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP

LOS ANGELES COUNTY, CALIFORNIA
and Incorporated Areas

PANEL **815** OF **1075**

Panel Contains:

COMMUNITY	NUMBER	PANEL	SUFFIX
LOS ANGELES COUNTY	065043	0815	G
SANTA CLARITA, CITY OF	060729	0815	G



**REVISED TO
REFLECT LOMR
EFFECTIVE: October 15, 2021**

VERSION NUMBER
2.3.3.0

MAP NUMBER
06037C0815G

MAP REVISED
JUNE 2, 2021




Appendix C – HEC-RAS Effective Results

Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 4295 Hasley 3911.677



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 4295 Hasley 3911.677



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 4213 Hasley 3829.697



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 4127 Hasley 3743.888



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 3834 Hasley 3450.237



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 3764 Hasley 3380.608



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 3728 Hasley 3344.197



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 3447 Hasley 3063.212



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 2997 Hasley 2613.671



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 2767 Hasley 2383.369



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 2676 Hasley 2292.714



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 2568 Hasley 2184.677



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 2253 Hasley 1869.959



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 1907 Hasley 1524.013



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 1795 Hasley 1411.347



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 1715 Hasley 1331.576



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 1510 Hasley 1127.001



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 1269 Hasley 885.489



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 1 RS = 1137 Hasley 753.443



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 0 RS = 963 Hasley 579.379



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 0 RS = 616 Hasley 232.324



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 0 RS = 593 Hasley 209.534



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 0 RS = 584 BR Commerce Dr. (#1)



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 0 RS = 458 Hasley 74.608



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 0 RS = 358 Hasley 2.0



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = Hasley Reach = 0 RS = 290 Hasley 1.0



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = H Overflow Reach = Reach-1 RS = 731 Hasley O 5.0



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = H Overflow Reach = Reach-1 RS = 665 Hasley O 4.0



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = H Overflow Reach = Reach-1 RS = 512 Hasley O 3.0



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective


River = H Overflow Reach = Reach-1 RS = 336 Hasley O 2.0



Hasley Canyon Plan: Duplicate Effective 6/12/2024

Geom: Duplicate Effective

River = H Overflow Reach = Reach-1 RS = 203 Hasley O 1.0



HEC-RAS Plan: Duplicate Effective Profile: 100-yr

River	Reach		River Sta	Profile	Q Total	Min Ch El	W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chnl	Flow Area	Top Width	Froude # Chl
					(cfs)	(ft)	(ft)	(ft)	(ft)	(ft/ft)	(ft/s)	(sq ft)	(ft)	
Hasley	1	4295	Hasley 3911.677	100-yr	1640.00	1065.95	1070.49	1070.49	1071.71	0.006639	8.86	185.17	73.31	0.98
Hasley	1	4213	Hasley 3829.697	100-yr	1640.00	1065.89	1069.77	1069.77	1070.78	0.007498	8.09	202.80	101.54	1.01
Hasley	1	4127	Hasley 3743.888	100-yr	1640.00	1065.13	1068.55	1068.55	1069.56	0.007425	8.06	203.55	101.48	1.00
Hasley	1	3834	Hasley 3450.237	100-yr	1640.00	1060.14	1062.40	1062.40	1063.20	0.008047	7.18	228.55	146.07	1.01
Hasley	1	3764	Hasley 3380.608	100-yr	1640.00	1058.71	1060.84	1060.84	1061.42	0.009241	6.09	269.47	244.63	1.02
Hasley	1	3728	Hasley 3344.197	100-yr	1640.00	1056.98	1059.56	1059.56	1060.21	0.008407	6.48	253.24	262.78	1.00
Hasley	1	3447	Hasley 3063.212	100-yr	1640.00	1036.71	1040.11	1039.49	1040.77	0.008347	6.53	251.28	92.85	0.70
Hasley	1	2997	Hasley 2613.671	100-yr	1640.00	1030.56	1034.09	1034.09	1035.52	0.016828	9.60	170.77	59.60	1.00
Hasley	1	2767	Hasley 2383.369	100-yr	1640.00	1027.50	1029.94	1029.73	1030.42	0.013579	5.61	292.56	197.93	0.81
Hasley	1	2676	Hasley 2292.714	100-yr	1640.00	1026.13	1028.60	1028.46	1029.12	0.015143	5.77	287.79	210.16	0.85
Hasley	1	2568	Hasley 2184.677	100-yr	1640.00	1024.26	1026.90	1026.63	1027.62	0.012419	6.80	241.05	113.52	0.82
Hasley	1	2253	Hasley 1869.959	100-yr	1640.00	1019.57	1021.85	1021.85	1022.73	0.019870	7.50	218.76	128.59	1.01
Hasley	1	1907	Hasley 1524.013	100-yr	1640.00	1013.79	1015.56	1015.44	1016.04	0.017371	5.57	294.41	242.13	0.89
Hasley	1	1795	Hasley 1411.347	100-yr	1640.00	1011.38	1013.22	1013.22	1013.82	0.022626	6.24	262.77	222.53	1.01
Hasley	1	1715	Hasley 1331.576	100-yr	1640.00	1010.03	1011.89	1011.60	1012.30	0.010915	5.08	322.55	214.61	0.73
Hasley	1	1510	Hasley 1127.001	100-yr	1640.00	1006.10	1008.42	1008.42	1009.35	0.019085	7.73	212.31	114.76	1.00
Hasley	1	1269	Hasley 885.489	100-yr	1640.00	1001.15	1003.50	1003.50	1004.46	0.018522	7.90	211.82	114.25	1.00
Hasley	1	1137	Hasley 753.443	100-yr	1640.00	998.19	1000.78	1000.78	1001.56	0.020292	7.08	231.70	196.31	1.00
Hasley	0	963		100-yr	820.00	994.52	997.85	997.85	998.31	0.025279	5.41	151.59	170.72	1.01
Hasley	0	616	Hasley 232.324	100-yr	820.00	990.79	994.33	993.22	994.54	0.003128	3.67	223.52	94.10	0.42
Hasley	0	593	Hasley 209.534	100-yr	820.00	990.66	994.29	992.92	994.46	0.002194	3.30	249.54	98.95	0.36
Hasley	0	584		Bridge										
Hasley	0	458	Hasley 74.608	100-yr	820.00	988.13	990.47	990.34	991.13	0.015566	6.55	125.86	76.91	0.89
Hasley	0	358		100-yr	820.00	985.09	988.58	988.58	989.53	0.015103	8.21	112.87	77.24	0.92
Hasley	0	290		100-yr	820.00	984.24	986.55	986.55	987.35	0.016727	7.60	121.90	84.64	0.94
H Overflow	Reach-1	731		100-yr	820.00	994.52	996.57	996.42	997.10	0.015516	5.87	139.80	97.24	0.86
H Overflow	Reach-1	665		100-yr	820.00	993.53	995.33	995.28	995.95	0.019330	6.32	129.70	95.05	0.95
H Overflow	Reach-1	512		100-yr	820.00	990.31	992.11	992.11	992.63	0.024241	5.76	142.34	142.09	1.01
H Overflow	Reach-1	336		100-yr	820.00	986.72	988.65	988.49	989.09	0.015087	5.35	153.16	119.42	0.83
H Overflow	Reach-1	203		100-yr	820.00	984.52	986.41	986.35	986.87	0.018710	5.47	153.58	152.99	0.91




Appendix D – HEC-RAS Corrected Effective Condition Hydraulic Results

HEC-RAS Plan: Corr. Eff. Profile: 100-yr

River	Reach	River Sta	Profile	Q Total	Min Ch El	W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chnl	Flow Area	Top Width	Froude # Chl
				(cfs)	(ft)	(ft)	(ft)	(ft)	(ft/ft)	(ft/s)	(sq ft)	(ft)	
Hasley US	Hasley US	4725	100-yr	1640.00	1065.89	1070.02		1070.82	0.005162	7.18	228.47	103.20	0.85
Hasley US	Hasley US	4648	100-yr	1640.00	1065.13	1070.20		1070.50	0.001062	4.39	373.43	106.76	0.41
Hasley US	Hasley US	4622	100-yr	1640.00	1067.00	1069.35	1069.35	1070.36	0.007406	8.07	203.28	101.98	1.01
Hasley US	Hasley US	4523	100-yr	1640.00	1064.22	1067.45	1067.45	1068.48	0.007245	8.14	201.43	97.88	1.00
Hasley US	Hasley US	4396	100-yr	1640.00	1062.35	1065.02	1065.02	1066.01	0.007534	7.98	205.62	106.04	1.01
Hasley US	Hasley US	4294	100-yr	1640.00	1059.14	1061.29	1061.29	1061.86	0.009262	6.04	271.67	250.04	1.02
Hasley US	Hasley US	4255	100-yr	1640.00	1055.65	1058.64	1058.64	1059.32	0.008562	6.60	248.42	188.45	1.01
Hasley US	Hasley US	4207	100-yr	1640.00	1045.43	1048.86	1048.86	1049.71	0.007728	7.36	222.88	132.83	1.00
Hasley US	Hasley US	4164	100-yr	1640.00	1036.62	1039.41	1039.41	1040.13	0.022254	6.81	240.73	173.07	1.02
Hasley US	Hasley US	4133	100-yr	1640.00	1034.00	1039.40		1039.46	0.000391	1.86	881.56	214.67	0.16
Hasley US	Hasley US	4100.5	100-yr	1640.00	1033.00	1038.92		1039.38	0.003506	5.46	300.24	73.59	0.48
Hasley US	Hasley US	4078	100-yr	1640.00	1033.00	1038.43		1039.24	0.007559	7.20	227.83	65.22	0.68
Hasley US	Hasley US	4055.5	100-yr	1640.00	1033.00	1038.30		1039.04	0.007637	6.88	238.36	74.91	0.68
Hasley US	Hasley US	3940.5	100-yr	1640.00	1031.00	1036.50	1035.86	1037.88	0.012159	9.42	174.01	46.15	0.86
Hasley US	Hasley US	3844	100-yr	1640.00	1030.01	1035.58		1036.51	0.013287	7.78	210.93	84.18	0.87
Hasley US	Hasley US	3747	100-yr	1640.00	1029.10	1034.48	1034.18	1035.21	0.012247	6.86	236.03	108.64	0.82
Hasley US	Hasley US	3650	100-yr	1640.00	1028.00	1032.65	1032.65	1033.68	0.019078	8.12	201.91	99.55	1.01
Hasley US	Hasley US	3564	100-yr	1640.00	1027.00	1030.79		1031.33	0.010628	5.88	278.83	143.89	0.74
Hasley US	Hasley US	3465	100-yr	1640.00	1026.00	1030.20		1030.64	0.004249	5.32	308.10	91.54	0.51
Hasley US	Hasley US	3369	100-yr	1640.00	1025.00	1028.59	1028.59	1029.73	0.018436	8.55	191.86	84.83	1.00
Hasley US	Hasley US	3304	100-yr	1640.00	1023.50	1027.42		1028.39	0.013337	7.88	208.22	81.17	0.87
Hasley US	Hasley US	3190.5	100-yr	1640.00	1022.00	1025.49	1025.49	1026.61	0.018055	8.49	193.23	85.86	1.00
Hasley US	Hasley US	3105	100-yr	1640.00	1021.00	1024.02	1023.87	1025.05	0.014957	8.11	202.27	83.42	0.92
Hasley US	Hasley US	3020	100-yr	1640.00	1019.56	1023.36		1023.96	0.008436	6.25	262.41	103.74	0.69
Hasley US	Hasley US	2934	100-yr	1640.00	1018.19	1021.77	1021.77	1022.91	0.018379	8.54	192.09	85.34	1.00
Hasley US	Hasley US	2820.5	100-yr	1640.00	1016.37	1019.21	1019.21	1020.17	0.019661	7.85	208.97	111.85	1.01
Hasley US	Hasley US	2748	100-yr	1640.00	1015.00	1017.79	1017.67	1018.58	0.015886	7.11	230.75	122.28	0.91
Hasley US	Hasley US	2675.5	100-yr	1640.00	1014.00	1016.79		1017.51	0.013051	6.79	241.68	118.11	0.84
Hasley US	Hasley US	2560.5	100-yr	1640.00	1012.00	1014.67	1014.67	1015.66	0.019303	7.99	205.18	105.26	1.01
Hasley US	Hasley US	2476	100-yr	1640.00	1010.49	1013.75		1014.23	0.008894	5.54	295.94	147.92	0.69
Hasley US	Hasley US	2391	100-yr	1640.00	1009.70	1012.52	1012.50	1013.08	0.020590	6.02	272.26	225.84	0.97
Hasley US	Hasley US	2305	100-yr	1640.00	1007.27	1010.70	1010.70	1011.30	0.020625	6.30	271.58	235.14	0.98
Hasley US	Hasley US	2190	100-yr	1640.00	1004.73	1008.30		1008.85	0.009484	5.93	276.66	130.73	0.72
Hasley US	Hasley US	2122	100-yr	1640.00	1004.00	1007.47		1008.18	0.009809	6.75	243.06	96.53	0.75
Hasley US	Hasley US	2054	100-yr	1640.00	1003.17	1006.27	1006.27	1007.21	0.019662	7.77	211.12	115.44	1.01
Hasley US	Hasley US	1940	100-yr	1640.00	1001.59	1004.56		1005.10	0.009940	5.90	277.98	137.49	0.73
Hasley US	Hasley US	1872	100-yr	1640.00	1000.99	1003.39	1003.21	1004.15	0.013452	6.99	240.38	138.08	0.85
Hasley US	Hasley US	1804	100-yr	1640.00	999.61	1002.18	1002.18	1003.11	0.016728	7.76	217.79	149.19	0.95
Hasley US	Hasley US	1689	100-yr	1640.00	997.48	999.73	999.73	1000.29	0.018660	6.20	292.81	278.00	0.94
Hasley	0	963	100-yr	820.00	996.00	998.03	998.03	998.60	0.023410	6.04	135.73	261.70	1.01
Hasley	0	704	100-yr	820.00	991.00	994.57		995.02	0.009485	5.43	150.88	80.89	0.70
Hasley	0	616	100-yr	820.00	990.79	994.25		994.48	0.003483	3.80	216.06	93.73	0.44
Hasley	0	593	100-yr	820.00	990.66	994.21	992.91	994.39	0.002441	3.41	241.20	98.06	0.38
Hasley	0	584	Bridge										
Hasley	0	458	100-yr	820.00	988.13	990.47	990.33	991.13	0.015566	6.55	125.86	76.91	0.89
Hasley	0	358	100-yr	820.00	985.09	988.58	988.58	989.53	0.015103	8.21	112.87	77.24	0.92
Hasley	0	290	100-yr	820.00	984.24	986.55	986.55	987.35	0.016727	7.60	121.90	84.64	0.94
H Overflow	Reach-1	731	100-yr	820.00	994.52	996.57	996.57	997.32	0.020897	6.96	117.90	79.27	1.01
H Overflow	Reach-1	665	100-yr	820.00	993.00	995.29		995.80	0.013771	5.76	142.46	93.29	0.82
H Overflow	Reach-1	512	100-yr	820.00	991.00	992.56	992.56	993.06	0.024288	5.68	144.35	148.14	1.01
H Overflow	Reach-1	336	100-yr	820.00	986.72	988.65		989.09	0.015087	5.35	153.16	119.42	0.83
H Overflow	Reach-1	203	100-yr	820.00	984.52	986.41	986.35	986.87	0.018710	5.47	153.58	152.99	0.91


Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 4725




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 4648




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025


RS = 4622



Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025


RS = 4523






Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 4164




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 4133




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 4100.5




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 4078




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 4055.5




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 3940.5




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025





RS = 3844



Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025


RS = 3747






Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 3304




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 3190.5




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 3105




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 3020




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 2934




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 2820.5




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025


RS = 2748





Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 2675.5











Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 704




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 616 Hasley 232.324




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025

RS = 593 Hasley 209.534




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025


RS = 584 BR Commerce Dr. (#1)




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025
RS = 458 Hasley 74.608




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025
RS = 358 Hasley 2.0




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025
RS = 290 Hasley 1.0




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025
RS = 731 Hasley O 5.0




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025
RS = 665 Hasley O 4.0




Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025
RS = 512 Hasley O 3.0



Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025
RS = 336 Hasley O 2.0



Hasley Canyon Plan: Hasley Creek_Corrected Effective 1/31/2025
RS = 203 Hasley O 1.0






Appendix E – HEC-RAS Proposed Condition Hydraulic Results

HEC-RAS Plan: Proposed Profile: 100-yr

River	Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Hasley US	Hasley US	4725	100-yr	1640.00	1065.89	1070.11		1070.85	0.004514	6.89	238.17	103.49	0.80
Hasley US	Hasley US	4648	100-yr	1640.00	1065.13	1070.23		1070.52	0.001034	4.36	376.55	106.86	0.41
Hasley US	Hasley US	4622	100-yr	1640.00	1066.97	1069.38	1069.38	1070.39	0.007371	8.07	203.21	101.65	1.01
Hasley US	Hasley US	4523	100-yr	1640.00	1064.28	1067.46	1067.46	1068.50	0.007243	8.16	201.01	97.40	1.00
Hasley US	Hasley US	4396	100-yr	1640.00	1059.45	1061.62	1061.62	1062.68	0.023770	8.27	198.33	94.42	1.01
Hasley US	Hasley US	4380.00*	100-yr	1640.00	1056.12	1058.37	1058.37	1059.46	0.023551	8.39	195.47	90.37	1.01
Hasley US	Hasley US	4364.00*	100-yr	1640.00	1052.78	1055.11	1055.11	1056.23	0.023299	8.52	192.56	86.26	1.00
Hasley US	Hasley US	4348.00*	100-yr	1640.00	1049.45	1051.87	1051.87	1053.03	0.023091	8.66	189.43	82.14	1.01
Hasley US	Hasley US	4332.00*	100-yr	1640.00	1046.12	1048.64	1048.64	1049.84	0.022809	8.80	186.37	78.04	1.00
Hasley US	Hasley US	4316.00*	100-yr	1640.00	1042.78	1045.40	1045.40	1046.65	0.022655	8.97	182.88	73.93	1.01
Hasley US	Hasley US	4300	100-yr	1640.00	1039.45	1042.19	1042.19	1043.49	0.022386	9.13	179.57	69.86	1.00
Hasley US	Hasley US	4291.00*	100-yr	1640.00	1036.45	1039.23	1039.23	1040.55	0.022398	9.21	178.16	68.49	1.01
Hasley US	Hasley US	4282	100-yr	1640.00	1033.45	1039.38		1039.64	0.001812	4.09	400.57	77.21	0.32
Hasley US	Hasley US	4280.50*	100-yr	1640.00	1033.45	1039.41		1039.61	0.001314	3.54	462.66	87.45	0.27
Hasley US	Hasley US	4279.00*	100-yr	1640.00	1033.45	1039.43		1039.58	0.000998	3.13	524.23	97.66	0.24
Hasley US	Hasley US	4277.50*	100-yr	1640.00	1033.45	1039.44		1039.57	0.000785	2.80	585.46	107.86	0.21
Hasley US	Hasley US	4276	100-yr	1640.00	1033.45	1039.45		1039.55	0.000634	2.54	646.58	118.06	0.19
Hasley US	Hasley US	4274.50*	100-yr	1640.00	1033.45	1039.46		1039.54	0.000498	2.27	723.60	130.93	0.17
Hasley US	Hasley US	4273.00*	100-yr	1640.00	1033.45	1039.47		1039.53	0.000402	2.05	800.43	143.79	0.15
Hasley US	Hasley US	4271.50*	100-yr	1640.00	1033.45	1039.47		1039.52	0.000331	1.87	877.24	156.67	0.14
Hasley US	Hasley US	4270	100-yr	1640.00	1033.45	1039.47		1039.52	0.000277	1.72	954.01	169.56	0.13
Hasley US	Hasley US	4265	100-yr	1640.00	1037.00	1039.22		1039.49	0.005671	4.15	394.92	181.86	0.50
Hasley US	Hasley US	4258	100-yr	1640.00	1037.00	1039.19		1039.43	0.005114	3.91	419.34	195.64	0.47
Hasley US	Hasley US	4157	100-yr	1640.00	1035.56	1039.27		1039.31	0.000360	1.66	990.54	273.21	0.15
Hasley US	Hasley US	4055.5	100-yr	1640.00	1033.00	1038.49		1039.14	0.007619	6.48	252.97	87.45	0.87
Hasley US	Hasley US	3940.5	100-yr	1640.00	1031.00	1036.83		1038.19	0.011054	9.36	175.29	42.48	0.81
Hasley US	Hasley US	3844	100-yr	1640.00	1030.00	1035.53	1035.53	1036.29	0.021016	6.95	235.82	159.32	1.01
Hasley US	Hasley US	3747	100-yr	1640.00	1029.17	1034.02		1034.39	0.005860	4.91	333.68	145.65	0.57
Hasley US	Hasley US	3650	100-yr	1640.00	1028.00	1032.55	1032.55	1033.37	0.020522	7.25	226.27	141.19	1.01
Hasley US	Hasley US	3554	100-yr	1640.00	1027.00	1030.26	1030.25	1031.01	0.020744	6.97	235.22	157.01	1.00
Hasley US	Hasley US	3440.5	100-yr	1640.00	1025.32	1029.39		1029.73	0.005940	4.66	352.24	169.07	0.57
Hasley US	Hasley US	3372	100-yr	1640.00	1025.00	1028.34	1028.32	1028.98	0.020491	6.43	255.19	191.22	0.98
Hasley US	Hasley US	3304	100-yr	1640.00	1023.53	1027.03	1027.03	1027.57	0.023561	5.92	277.16	261.79	1.01
Hasley US	Hasley US	3190.5	100-yr	1640.00	1022.00	1025.56		1025.83	0.005156	4.21	389.43	195.25	0.53
Hasley US	Hasley US	3105	100-yr	1640.00	1021.00	1024.12	1023.93	1025.15	0.014483	8.15	201.20	80.16	0.91
Hasley US	Hasley US	3020	100-yr	1640.00	1019.68	1023.79		1024.14	0.006180	4.74	346.21	165.22	0.58
Hasley US	Hasley US	2934	100-yr	1640.00	1018.19	1022.40	1022.40	1023.24	0.019606	7.33	223.78	132.34	0.99
Hasley US	Hasley US	2820.5	100-yr	1640.00	1016.37	1019.11	1019.11	1019.89	0.020266	7.09	231.16	147.94	1.00
Hasley US	Hasley US	2748	100-yr	1640.00	1015.00	1017.70	1017.60	1018.34	0.016624	6.43	254.93	162.82	0.91
Hasley US	Hasley US	2675.5	100-yr	1640.00	1014.00	1016.49		1017.15	0.011770	6.49	252.57	122.09	0.80
Hasley US	Hasley US	2560.5	100-yr	1640.00	1012.00	1014.74	1014.74	1015.73	0.019272	8.00	204.89	104.79	1.01
Hasley US	Hasley US	2476	100-yr	1640.00	1010.48	1013.92	1013.17	1014.24	0.009211	4.58	357.81	245.01	0.67
Hasley US	Hasley US	2391	100-yr	1640.00	1009.71	1012.42	1012.42	1013.05	0.022218	6.35	258.28	209.82	1.01
Hasley US	Hasley US	2305.5	100-yr	1640.00	1007.88	1011.91	1010.64	1012.07	0.002249	3.12	525.47	222.15	0.36
Hasley US	Hasley US	2250											
Hasley US	Hasley US	2190.5	100-yr	1640.00	1006.00	1008.85	1008.62	1009.34	0.014069	5.62	291.75	202.13	0.82
Hasley US	Hasley US	2122	100-yr	1640.00	1004.00	1007.52	1007.28	1008.05	0.015936	5.88	279.05	198.17	0.87
Hasley US	Hasley US	2054	100-yr	1640.00	1003.00	1005.93	1005.93	1006.59	0.022765	6.48	253.12	203.35	1.02
Hasley US	Hasley US	1940.5	100-yr	1640.00	1001.77	1004.55		1004.94	0.009570	4.98	329.60	205.43	0.69
Hasley US	Hasley US	1872	100-yr	1640.00	1000.95	1002.94	1002.93	1003.76	0.019755	7.27	225.72	137.13	1.00
Hasley US	Hasley US	1804	100-yr	1640.00	999.70	1001.80	1001.73	1002.39	0.018689	6.18	265.30	197.25	0.94
Hasley US	Hasley US	1689	100-yr	1640.00	997.49	999.39	999.39	1000.02	0.022415	6.36	257.95	210.80	1.01
Hasley US	Hasley US	1584	100-yr	1640.00	995.00	997.59		998.00	0.013743	5.17	317.51	245.35	0.80
Hasley US	Hasley US	1406	100-yr	1640.00	992.72	995.18		995.48	0.014239	4.41	371.72	373.86	0.78
Hasley US	Hasley US	1354	100-yr	1640.00	991.22	995.22		995.29	0.000910	2.14	765.62	287.39	0.23
Hasley	0	704	100-yr	820.00	991.00	994.56		995.03	0.009654	5.47	150.02	80.98	0.71
Hasley	0	616	Hasley 232.324	100-yr	820.00	990.79	994.25	994.48	0.003483	3.80	216.06	93.73	0.44
Hasley	0	593	Hasley 209.534	100-yr	820.00	990.66	994.21	992.92	0.002441	3.41	241.20	98.06	0.38
Hasley	0	584											
Hasley	0	458	Hasley 74.608	100-yr	820.00	988.13	990.47	990.34	0.015566	6.55	125.86	76.91	0.89
Hasley	0	358		100-yr	820.00	985.09	988.58	988.58	0.015103	8.21	112.87	77.24	0.92
Hasley	0	290		100-yr	820.00	984.24	986.55	986.55	0.016727	7.60	121.90	84.64	0.94
H Overflow	Reach-1	336	100-yr	820.00	986.72	988.65		989.09	0.015087	5.35	153.16	119.42	0.83
H Overflow	Reach-1	203	100-yr	820.00	984.52	986.41	986.35	986.87	0.018710	5.47	153.58	152.99	0.91


Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4725




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4648




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4622




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4523




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4396




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4380.00*




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025





RS = 4364.00*







Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4348.00*









Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4276




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4274.50*




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025





RS = 4273.00*




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 4271.50*







Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 4055.5




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 3940.5



Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 3844




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 3747




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 3650




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 3554




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 3440.5




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025


RS = 3372




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 3304




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 3190.5




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 3105




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 3020




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 2934




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 2820.5



Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 2748




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 2675.5




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 2560.5




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 2476




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 2391




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 2305.5




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 2250 BR




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 2190.5




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 2122




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 2054




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 1940.5




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 1872




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025

RS = 1804




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025


RS = 1689




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 1584




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 1406




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 1354




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 704




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 616 Hasley 232.324




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 593 Hasley 209.534




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 584 BR Commerce Dr. (#1)




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 458 Hasley 74.608




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 358 Hasley 2.0




Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 290 Hasley 1.0



Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 336 Hasley O 2.0



Hasley Canyon Plan: Hasley Creek_Proposed 1/31/2025
RS = 203 Hasley O 1.0





**Appendix F – As-Built Drawings-Commerce Center
Drive**

LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS



PLANS FOR BRIDGE

ON

COMMERCE CENTER DRIVE



OVER

CASTAIC CREEK



AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes



INDEX	
SHEET	TITLE
1	TITLE SHEET
2	TOPOGRAPHY
3	PILE LAYOUT & WINGWALL DETAILS
4	ABUTMENTS
5	PIERS
6-8	PRESTRESSED GIRDER DETAILS
9	GIRDER DIAPHRAGMS
10-11	DECK DETAIL SHEETS
12	MISCELLANEOUS DETAILS
13-15	LOG OF TEST BORINGS

SPECIFICATIONS

DESIGN: Load Factor Design
Bridge Design Specifications (1989 A.A.S.H.T.O. with Interims and Caltrans Supplements)
Design Loading:
Dead Load: Includes 35 psf for future wearing surface
Live Load: HS20-44 and P13 overload
Seismic Load: Peak Rock Acceleration 0.60g, Depth to Alluvium 80'-150 ft.
Design Stresses: Reinforced Concrete: $f_y = 60,000$ psi
 $f'_c = 3,250$ psi
 $n = 9$
Transverse deck slab
 $f_s = 20,000$ psi
 $f_c = 1,200$ psi
 $n = 10$
Prestressed Concrete: See "Prestressing Notes"
Structural Steel (A36): $f_y = 36,000$ psi
Design Soil Pressure (net): 3,000 psf
Pile Design Load: Abutts 45 ton, Piers 70 ton
CONSTRUCTION:
Standard Specifications for Public Works
Construction (1994) w/Current Supplements
DATUM:
NEWHALL 1983, ROOM TAG IN CB 4 FT N BCR 70 FT N & 32 FT E CL INT
OLD ROAD & HASLEY CANYON ROAD OFF RAMP EL. 1065.685 CL 3976


INDEX TO STANDARD PLANS

The Following State of California Department of Transportation Standard Plans, Dated July 1992, Are a Part of These Contract Drawings.

A62-C Limits of Payment for Excavation and Backfill-Bridge
A77-D Guard Rail Flares
A77-F Miscellaneous Guard Rail Details
B2-5 Pile Details-Class 45 and Class 70
B6-21 Joint Seals
B7-5 Deck Drains
B11-54 Concrete Barrier Type 26
B0-5 Deck Construction Joint
The Following Los Angeles County Department of Public Works Standard Plans, Latest Edition, are Part of These Contract Drawings.
6102 Picket Railing

AMERICAN PUBLIC WORKS ASSOCIATION (APWA)
STANDARD PLANS FOR PUBLIC WORKS CONSTRUCTION,
1994 EDITION


460-0 Pull Boxes
465-0 Conduit Expansion Details



NOTE: The contractor shall verify all controlling field dimensions before ordering or fabricating any material or starting construction.





SISKAND ENGINEERING ASSOCIATES CONSULTING ENGINEERS 15220 WILSHIRE BLVD., VAN NUYS, CALIFORNIA 91411 (818) 707-8550		LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS DESIGN DIVISION STRUCTURES SECTION	
DESIGNED BY: JORA SARKISSIAN		COMMERCE CENTER DRIVE OVER CASTAIC CREEK TITLE SHEET	
DRAWN BY: ALBERT GEVORKIAN		SUBMITTED: J. Sarkissian 11/24/97 APPROVED: J. Sarkissian 11/25/97 BY: J. Sarkissian	
PROJECT ENGINEER: JORA SARKISSIAN		BRIDGE NO.: 3794 PROJECT NO.: SHT.: 1 OF: 15 DWG. NO.: 614612	



SCALE: 1" = 60'

- NOTE: UNLESS OTHERWISE INDICATED:**
- EXISTING TOPOGRAPHY SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR.
 - FOR RELOCATION OR REMOVAL OF EXISTING UTILITIES, SEE SPECS.
 - INDICATES BOTTOM OF FOOTING ELEVATION.
 - SLOPE PAVING MAY BE PORTLAND CEMENT CONCRETE OR AIR-BLOWN MORTAR. SEE SPECS.
 - FOR GUARD RAIL DETAILS, SEE CALTRANS STD. PLAN ATT-D, TYPE I FLARE AND ATT-F, ATT-E. FOR ANCHORAGE TO BRIDGE SIDEWALK, SEE STD. B11-54, TYP.
 - FOR SITE AND EMBANKMENT PREPARATION, SEE SPECS.
 - FOR TYPICAL SLOPE PAVING DETAILS SEE "MISCELLANEOUS DETAILS" ON SHEET NO. 12.
 - LINING AND BIKE PATH TO BE CONSTRUCTED PER P.D. NO. 2298 (UNIT III)


NOTE:
CONTRACTOR'S ATTENTION IS DIRECTED TO THE PRESENCE OF GROUND WATER AT ELEVATION OF 2 TO 4 FEET BELOW THE RIVER BED GRADE. CONTRACTOR WILL BE REQUIRED TO PROVIDE ALL NECESSARY DEWATERING FACILITIES TO ADEQUATELY DEWATER BELOW THE SOFFIT OF PIER FOOTING OR BOTTOM OF THE FOOTING OF THE SLOPE PAVING PRIOR TO THE PLACEMENT OF ANY REINFORCEMENT AND STRUCTURAL OR AIR BLOWN CONCRETE. DEWATERING SHALL CONTINUE UNTIL THE STRENGTH OF STRUCTURAL OR AIR BLOWN CONCRETE BELOW THE WATER TABLE HAS REACHED THE STRENGTH OF 2000 P.S.I.



AS BUILT
Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes



SIKAND ENGINEERING ASSOCIATES CONSULTING ENGINEERS 3229 BURNING BLDG., TOLSON, CALIFORNIA (916) 787-8554 91611		LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS DESIGN DIVISION STRUCTURES SECTION	
DESIGNED BY: JORA SARKISSIAN		COMMERCE CENTER DRIVE OVER CASTAIC CREEK	
DRAWN BY: ALBERT GEVORKIAN		TOPOGRAPHY	
PROJECT ENGINEER: 		REVIEWED Steve M. Hennessey	BRIDGE NO.: 3794 PROJECT NO.: SHT.: 2 OF: 15
JORA SARKISSIAN		DATE 11/24/97	DWG. NO.: 614611



Note: Pile layout for all Piers are identical to that shown for Pier 4 or Pier 2

PLAN


SCALE: $\frac{1}{8}'' = 1'-0''$

LOCATION	MINIMUM	ESTIMATED
ABUT 1	960.00	960.00
ABUT 8	950.00	950.00
PIER 2 & 3	926.00	926.00
PIERS 4, 5, 6, 7	922.00	922.00


NOTE - Unless otherwise indicated:

- Dimensions shown for pile layout are measured at bottom of footings.
- Vertical piles are indicated by H.
- Battered piles are 3:12 at abutments, direction of batter is indicated thus H→.
- Lugs for steel pile shall be $\frac{3}{8}'' \times 5''$ plates cut to fit. Welded to each side of web and shall be placed as directed by the Engineer. See Specs.
- Estimated pile tip elevations as shown on this sheet shall be used for bidding purposes.
- For pile driving, See Specs.
- For pile details See Caltrans Std. Plan B2-5.
- All piles are HP 12x53, with
 - Abuts. 40 ton capacity
 - Piers 70 ton capacity


Note: Pile layout for Abut. 8 is identical but opposite hand to that shown for Abut. 1



TYPICAL WINGWALL DETAILS
NO SCALE



Design H	6'	8'	10'	12'
W	4'-2"	5'-2"	6'-2"	7'-2"
C	1'-4"	1'-8"	2'-0"	2'-4"
B	2'-10"	3'-6"	4'-2"	4'-10"
F	1'-2"	1'-2"	1'-2"	1'-2"
(b)	—	—	—	#4 @ 18"
(c)	#5 @ 18"	#5 @ 16"	#5 @ 9"	#6 @ 9"
(d)	#5 @ 18"	#4 @ 16"	#4 @ 9"	#5 @ 9"









STEEL PILE ANCHOR
NO SCALE

AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes



SIRAND ENGINEERING ASSOCIATES CONSULTING ENGINEERS 15220 BROADWAY BLVD., VAN NUYS, CALIFORNIA 91411 (818) 787-8550		LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS DESIGN DIVISION STRUCTURES SECTION	
DESIGNED BY: JORA SARKISSIAN		COMMERCE CENTER DRIVE OVER CATAIC CREEK	
DRAWN BY: ALBERT GEVORKIAN		PILE LAYOUT & WINGWALL DETAILS	
PROJECT ENGINEER: JORA SARKISSIAN		REVIEWED Steve M. Hennessy 11/24/97 STRUCTURAL SECTION DATE	BRIDGE NO.: 3794 PROJECT NO.: SHEET: 3 OF: 15 DWG. NO.: 614610



BEARING	SEAT	ELEVATION
GIRDER	ABUTMENT 1	ABUTMENT 8
E-1	1002.56	1002.56
E-2	1002.39	1002.39
E-3	1002.22	1002.21
E-4	1002.04	1002.04
E-5	1001.87	1001.87
E-6	1001.70	1001.70
W-1	1002.56	1002.56
W-2	1002.39	1002.39
W-3	1002.22	1002.23
W-4	1002.06	1002.06
W-5	1001.89	1001.89
W-6	1001.72	1001.72

- NOTE - Unless otherwise indicated:
- Elevation shown is for back face of abutments and wing walls.
 - Bearing seat elevations are top of concrete and are located at the intersection of E bearing and E girder.
 - Reinforcing steel shall have 2" cover in walls and 3" cover in footings.
 - Premolded joint filler should be fastened with 8 d galvanized nails @ 12" o.c. staggered.
 - Reinforcing steel shall be continuous through construction joints.
 - Bearing seats shall be parallel to roadway grade and level perpendicular to E girder.

JOINT TYPE SEALS CHANGED TO TYPE "B" SEAL
AS BUILT
 Date 1-26-01 Corrections by: G. Pereda
 Resident Engineer: Zaven Abrahamian

LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
DESIGN DIVISION
 STRUCTURES SECTION

COMMERCE CENTER DRIVE
 OVER
 CASTAIC CREEK
ABUTMENTS




REVIEWED: *Steve M. Hennessey* 11/24/97
 PROJECT ENGINEER: *JORA SARKISSIAN*

BRIDGE NO.: 3794
 PROJECT NO.:
 SHT.: 4
 OF: 15
 DWG. NO.: 614609

SIKAND ENGINEERING ASSOC.
 CONSULTING ENGINEERS
 19230 BURBANK BLVD. VAN NUYS, CALIF. 91411
 (818) 787-8550


DRAWN BY: *ALBERT GEORAKIAN*
 PROJECT ENGINEER: *JORA SARKISSIAN*

ADDED ABUTMENT UTILITY OPENING & REVISED SHEAR KEY LOCATIONS.
 CHECKED
 DRAWN




BEARING SEAT ELEVATION						
GIRDER	PIER 2	PIER 3	PIER 4	PIER 5	PIER 6	PIER 7
E-1	1002.81	1003.07	1003.37	1003.42	1003.23	1002.90
E-2	1002.64	1002.89	1003.20	1003.25	1003.07	1002.73
E-3	1002.47	1002.73	1003.03	1003.08	1002.90	1002.55
E-4	1002.29	1002.55	1002.86	1002.91	1002.72	1002.38
E-5	1002.12	1002.38	1002.69	1002.74	1002.55	1002.21
E-6	1001.95	1002.21	1002.52	1002.57	1002.38	1002.04
W-1	1002.81	1003.07	1003.36	1003.42	1003.24	1002.90
W-2	1002.64	1002.90	1003.19	1003.25	1003.07	1002.73
W-3	1002.47	1002.73	1003.02	1003.08	1002.91	1002.57
W-4	1002.31	1002.56	1002.85	1002.91	1002.74	1002.40
W-5	1002.14	1002.40	1002.68	1002.74	1002.57	1002.23
W-6	1001.97	1002.23	1002.51	1002.57	1002.40	1002.06


- NOTE: Unless otherwise indicated:
- Elevations shown in table are at E of pier. See Sect. B-B.
 - Reinforcing steel shall have 2" cover in cap and 3" cover in walls and footing.
 - Finish bearing seats parallel to roadway grade and level transverse to girders.
 - See Sheet 3 for pile layout.



PIERS 3 & 6



SECTION B-B



DETAIL 'C'

AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes

SECTION P-P

Scale: 1/4" = 1'-0"

ELEVATION

Scale: 1/4" = 1'-0"

NOTE: Reinforcement Shown is Typ. for both faces of Pier.



SIKAND ENGINEERING ASSOC.
CONSULTING ENGINEERS

15230 BURBANK BLVD. VAN NUYS, CALIF.
(818) 787-8550 91411

DESIGNED BY:
JORA SARKISSIAN

DRAWN BY:

ALBERT GEVORKIAN


PROJECT ENGINEER:
JORA SARKISSIAN

LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
STRUCTURES DIVISION
SECTIONS

COMMERCE CENTER DRIVE
OVER
CASTAIC CREEK
PIERS

REVIEWED

BRIDGE NO.: 3794
PROJECT NO.:
SHT.: 5
OF: 15
DATE: 4/24/97
DWG. NO.: 614608




GIRDER ELEVATION FOR PIER 4 TO ABUT. 8
No Scale


AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes


- NOTE:**
- Girder length shown is for finished girder. Allowance shall be made for elastic shortening.
 - For dowels cast in girder, see Sht.
 - Extend #4 & #6 longitudinal reinforcing 8" past end of girder at Pier
 - Omit keys on exterior face of girder
 - Ends of girder shall be marked for span location.
 - Contractor shall submit shop drawings indicating location and size of holes for dowel through girders.



SECTION C-C
No Scale




SECTION D-D
No Scale




ALTERNATE INSERT ASSEMBLY
No Scale


* 6 dowel 6'-0" long. Place through 1" holes formed in girder. Holes need not be grouted




ALTERNATE DOWEL ASSEMBLY
No Scale



ELEVATION
No Scale



SECTION E-E
No Scale




RESTRAINER UNIT DETAIL
No Scale

CLEARANCES FOR POST TENSIONED UNITS

- Units may be bundled vertically in groups of 3 max.
- Horizontal clearance between units equal to 2 1/2" min.
- Vertical clearance between bundled units equal to 3" min.
- Any deviation shall be approved by the Engineer.

CLEARANCES FOR PRETENSIONED STRANDS



- Strands may be bundled in groups consisting of 3 vertically and 2 horizontally, and separated at the ends.
- The minimum distance "S" between groups or individual strands is 1 1/2" for 3/8" strands, 1 3/4" for 1/2" strands and 2" for 5/8" strands.
- "S" is measured between centers of adjacent strands.
- Any deviation shall be approved by the Engineer.

GIRDER PRESTRESSING NOTES FOR PIER 4 TO ABUT. 8

X	DESIGN STRESSES	Post tension	Pretension
4"	P = Working force, lbs	615,000	675,000
8"	Concrete strength, psi	f _c = 5,000 f _{ci} = 4,900	f _c = 5,000 f _{ci} = 4,900

CONCRETE STRENGTH:

f_{ci} is at time of initial stressing. (force transfer to conc)
f_c is at 28 days.

WORKING FORCE:

The force remaining per girder after all losses.

CABLE PATH:

Where impractical to obtain cable path shown with a proposed prestressing system, it may vary within limits from 4" to 8" at E girder and from 22" to 26" at the end of the girder subject to the approval of the Engineer. See Specs.


LOSSES:

The stress loss in prestressing steel due to shrinkage, creep, and sequence stressing shall be assumed to be:
pretension steel: 42,000 psi.
post tension steel: 32,000 psi.
Provision shall be made for any other losses peculiar to the system of prestressing used.

GIRDER DEFLECTIONS: (PRE-TENSION) FOR "X"=4"

Time	Condition	Deflection
Initial	Prestress + D.L. Girder	- 1 3/4"
	Prestress + D.L. Girder	- 2 1/4"
3 months	D.L. Slab	1/2 pt. + 1 1/2"
	D.L. Slab	1/4 pt. + 1 1/8"
	Prestress + D.L. Girder + D.L. Slab	- 5/8"
Final	Prestress + D.L. Girder + D.L. Slab	- 3/4"


A minus(-) sign indicates upward deflection. Deflections measured at E Span and are based on the assumption that the deck will not be placed on precast girders until 3 months after prestressing. Final deflection is assumed to occur 4 years after initial prestressing.
* Includes other dead loads.



TYPICAL GIRDER FRAMING PLAN
No Scale




SIKAND ENGINEERING ASSOC. CONSULTING ENGINEERS 15230 BURBANK BLVD. VAN NUYS, CALIF. (818) 787-8550 91411	LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS DESIGN DIVISION STRUCTURES SECTION COMMERCE CENTER DRIVE OVER CASTAIC CREEK PRESTRESSED GIRDER DETAILS NO. 1
DESIGNED BY: JORA SARKISSIAN DRAWN BY: ALBERT GEVORKIAN PROJECT ENGINEER: JORA SARKISSIAN	BRIDGE NO. 3794 JOB NO. SHT. 6 OF 15 DWG. NO. 614607 DATE 11/24/97



AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes

NOTE - Unless otherwise indicated:
1. Reinforcing steel shall have 2" cover.
2. Deck steel not shown.




PRESTRESSING FORCES FOR SPAN 3-4

GIRDERS E-2, E-3, E-4, E-5 & E-6			
"X"	DESIGN STRESSES	POST TENSION	PRETENSION
4"	P=WORKING FORCE, lbs	670,000	750,000
8"		765,000	850,000
	CONCRETE STRENGTH, psi	f'ci = 5,500	f'ci = 5,500
		f'ci = 5,100	f'ci = 4,900


GIRDERS E-1, W-1, W-2, W-3, W-4, W-5 & W-6			
"X"	DESIGN STRESSES	POST TENSION	PRETENSION
4"	P=WORKING FORCE, lbs	615,000	675,000
8"		700,000	765,000
	CONCRETE STRENGTH, psi	f'ci = 5,000	f'ci = 5,000
		f'ci = 4,900	f'ci = 4,900

LOC.	A	B	C	D
W-6	79'-10 1/2"	78'-8 1/2"	13'-1 1/4"	22'-2 3/4"
W-5	80'-10 7/8"	79'-8 7/8"	13'-3 1/2"	22'-7"
W-4	81'-11 1/4"	80'-9 3/4"	13'-5 1/2"	22'-11 5/8"
W-3	82'-11 1/2"	81'-9 1/2"	13'-7 5/8"	23'-3 1/8"
W-2	83'-11 7/8"	82'-9 7/8"	13'-9 5/8"	23'-7 1/4"
W-1	85'-0 1/4"	83'-10 1/4"	13'-11 3/4"	23'-11 3/8"
E-1	86'-0 1/2"	84'-10 1/2"	14'-1 3/4"	24'-3 1/2"
E-2	87'-0 7/8"	85'-10 7/8"	14'-3 7/8"	24'-7 5/8"
E-3	88'-1 1/4"	86'-11 1/4"	14'-5 7/8"	24'-11 3/4"
E-4	89'-1 5/8"	87'-11 5/8"	14'-7 7/8"	25'-3 7/8"
E-5	90'-2"	89'-0"	14'-10"	25'-8"
E-6	91'-2 1/4"	90'-0 1/4"	15'-0"	26'-0 1/8"

GIRDER DIMENSIONS FOR SPAN 3-4



CLEARANCES FOR PRETENSIONED STRANDS



- Strands may be bundled in groups consisting of 3 vertically and 2 horizontally, and separated at the ends.
- The minimum distance "S" between groups or individual strands is 1 1/2" for 3/4" strands, 1 3/4" for 7/8" strands and 2" for 1" strands.
- "S" is measured between centers of adjacent strands.
- Any deviation shall be approved by the Engineer.

PRESTRESSING NOTES FOR SPAN 3-4

"X"	DESIGN STRESSES	Post tension	Pretension
P = Working force, lbs			
Concrete strength, psi	f'ci =	f'ci =	f'ci =

CONCRETE STRENGTH:

f'ci is at time of initial stressing. (Force transfer to conc.)
f'ci is at 28 days.

WORKING FORCE:

The force remaining per girder after all losses.

CABLE PATH:

Where impractical to obtain cable path shown with a proposed prestressing system, it may vary within limits from 4" to 8" at E girder and from 22" to 26" at the end of the girder subject to the approval of the Engineer. See Specs.

LOSSES:

The stress loss in prestressing steel due to shrinkage, creep, and sequence stressing shall be assumed to be:

pretension steel: 42,000 psi.
post tension steel: 32,000 psi.
Provision shall be made for any other losses peculiar to the system of prestressing used.

GIRDER DEFLECTIONS: (PRE-TENSION) FOR "X" = 4"

Time	Condition	Deflection
Initial	Prestress + D.L. Girder	-1 3/4"
	Prestress + D.L. Girder	-2 1/4"
3 months	D.L. Slab	1/2 pt. + 1 1/2"
	D.L. Slab	1/4 pt. + 1 1/8"
	Prestress + D.L. Girder + D.L. Slab	-3/4"
Final	Prestress + D.L. Girder + D.L. Slab	-7/8"

A minus(-) sign indicates upward deflection. Deflections measured at E Span and are based on the assumption that the deck will not be placed on precast girders until 3 months after prestressing. Final deflection is assumed to occur 4 years after initial prestressing.
* Includes other dead loads.

SIKAND ENGINEERING ASSOC.
CONSULTING ENGINEERS
15230 BURBANK BLVD. VAN NUYS, CALIF. 91411
(818) 787-8550

DESIGNED BY:

JORA SARKISSIAN

DRAWN BY:

ALBERT GEVORKIAN

PROJECT ENGINEER:

JORA SARKISSIAN

LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
DESIGN DIVISION
STRUCTURES SECTION

COMMERCE CENTER DRIVE
OVER
CASTAIC CREEK

PRESTRESSED GIRDER DETAILS NO. 2



BRIDGE NO. 3794

JOB NO.


SHT. 7 OF 15

DWG. NO. 614606







GIRDER ELEVATION FOR ABUT 1 TO PIER 3
No Scale




SECTION G-G
Scale: 3/8" = 1'-0"




SECTION K-K
Scale: 3/8" = 1'-0"




SECTION L-L
Scale: 3/8" = 1'-0"




SECTION M-M
Scale: 3/8" = 1'-0"



SECTION J-J
Scale: 3/8" = 1'-0"




DETAIL "E"
CONTINUITY SPLICE
No Scale




SECTION N-N
No Scale



TYPE A SEAL
Full Scale



SECTION F-F
Scale: 3/8" = 1'-0"



SECTION I-I
Scale: 3/8" = 1'-0"

AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes

CLEARANCES FOR PRETENSIONED STRANDS

1. Strands may be bundled in groups consisting of 3 vertically and 2 horizontally, and separated at the ends.
2. The minimum distance "S" between groups or individual strands is 1 1/2" for 3/4" strands, 1 3/4" for 7/8" strands and 2" for 1" strands.
3. "S" is measured between centers of adjacent strands.
4. Any deviation shall be approved by the Engineer.

GIRDER PRESTRESSING NOTES FOR ABUT 1 TO PIER 3

"X"	DESIGN STRESSES	Post tension	Pretension
4"	P = Working force, lbs	370,000	390,000
6"		420,000	445,000
	Concrete strength, psi	f _{ci} = 5,000	f _{ci} = 5,000
		f _{ci} = 4,000	f _{ci} = 4,000

CONCRETE STRENGTH:

f_{ci} is at time of initial stressing. (Force transfer to conc)
f_c is at 28 days.

WORKING FORCE:

The force remaining per girder after all losses.

CABLE PATH:

Where impractical to obtain cable path shown with a proposed prestressing system, it may vary within limits from 4" to 8" at girder and from 22" to 26" at the end of the girder subject to the approval of the Engineer See Specs.

LOSSES:

The stress loss in prestressing steel due to shrinkage, creep, and sequence stressing shall be assumed to be:
pretension steel: 42,000 psi.
post tension steel: 32,000 psi.
Provision shall be made for any other losses peculiar to the system of prestressing used.

GIRDER DEFLECTIONS: (PRE-TENSION) FOR "X"=4"

Time	Condition	Deflection
Initial	Prestress + D.L. Girder	- 5/8"
	Prestress + D.L. Girder	- 3/4"
3 months	D.L. Slab	1/2 pt. + 1/2"
	Prestress + D.L. Girder + D.L. Slab	1/4 pt. + 3/8"
Final	Prestress + D.L. Girder + D.L. Slab	- 1/4"

A minus(-) sign indicates upward deflection. Deflections measured at & Span and are based on the assumption that the deck will not be placed on precast girders until 3 months after prestressing. Final deflection is assumed to occur 4 years after initial prestressing.
* Includes other dead loads.




SIKAND ENGINEERING ASSOC.
CONSULTING ENGINEERS
18230 BURBANK BLVD. VAN NUYS, CALIF.
(818) 787-8550 91411
DESIGNED BY:
JORA SARKISSIAN
DRAWN BY:
ALBERT GEVORKIAN
PROJECT ENGINEER
JORA SARKISSIAN

LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
DESIGN DIVISION
STRUCTURES SECTION
COMMERCE CENTER DRIVE
OVER
CASTAIC CREEK
PRESTRESSED GIRDER DETAILS NO. 3
BRIDGE NO. 3794
JOB NO.
SHT. 8 OF 15
DWG. NO. 614605
REVIEWED
Steve M. Hennessy 11/24/97
STRUCTURAL SECTION DATE

NOTE: Contractor may propose alternative continuity splice assembly, subject to approval by the Engineer.


Pipes and rods to be securely wedged and braced in place to prevent displacement during girder concrete pour.

All threads to be oriented correctly.



NORMAL SECTION - END DIAPHRAGM AT ABUT. 1 & 8


Scale: 1/4" = 1'-0"



NORMAL SECTION - INTERMEDIATE DIAPHRAGM


Scale: 1/4" = 1'-0"

Note: For Joint Seal on Sidewalk at Abut. 1, Pier 3, Pier 6 and Abut. 8, See Caltrans Std. Plan 86-21.



NORMAL SECTION - END DIAPHRAGM AT PIER

Scale: 1/4" = 1'-0"



INSERT ASSEMBLY DETAIL

No Scale

NOTES :



- #6 x 6'-0" dowels placed through 1 1/2" dia. hole formed in girder, when diaphragms are continuous. Hole need not be grouted.
- 1" dia. bolts x 1'-4" with insert assemblies when diaphragms are discontinuous. Bolts required for exterior girder.
- Intermediate and end diaphragms are to be placed 5 days before placing deck.
- This note certifies forming so as to prevent spalling problems of thin unreinforced concrete under girders.

AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes



SIKAND ENGINEERING ASSOCIATES CONSULTING ENGINEERS 15224 BUREAU BLVD., VAN NUYS, CALIFORNIA 91411 (818) 777-0559	LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS DESIGN DIVISION STRUCTURES SECTION	
DESIGNED BY: JORA SARKISSIAN	COMMERCE CENTER DRIVE OVER CASTAIC CREEK GIRDER DIAPHRAGMS	
DRAWN BY: ALBERT GEYORKIAN	REVIEWED Steve M. Hennessy 11/24/97	
PROJECT ENGINEER: JORA SARKISSIAN	BRIDGE NO.: 3794 SHT.: 9 OF: 15 DWG. NO.: 614604	



AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes

4-#5 Bars 8'-0" Lg. Between Girders at end Diaphragms at Piers 3 & 6 and at Abuts. at Top of Deck. Place as Shown. Typical.

NOTE - Unless otherwise indicated:

- Grade 60 reinforcing steel shall be spliced as follows:
 - Only one-half of the bars may be spliced within the required lap length.
 - Minimum lap splices for No. 6 and smaller bars shall be 32 d. No. 7, 8 and bars shall be 45 d and No. 10 and 11 bars shall be 60 d.
 - Splice lengths shall be determined by the diameter, d of the smaller bar joined.
- Type "A", "B" and "C" bar splices shall be staggered and identical splices of the same type bar shall be spaced at least 3'-0" apart.
- Reinforcing steel shall have 2" cover.
- Deck truss bends shall be 45°.
- Premolded joint filler shall be fastened with 8d galvanized nails at 12" o.c. staggered.
- For additional notes and details, see sheet No. 9.
- All bars #10. Unless otherwise noted.

BOTTOM SLAB STEEL #5, S=10" **TOP SLAB STEEL**

Note: Splices for #10 cont. bars shall be located 25' min. from E piers.







Note: Numbers at ends of #10 bars indicate distance from E pier.

DECK PLAN

Scale: 3/16" = 1'-0"



SIKAND ENGINEERING ASSOC. CONSULTING ENGINEERS 19230 BURBANK BLVD. VAN NUYS, CALIF. (818) 787-8550 91411		LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS DESIGN DIVISION STRUCTURES SECTION	
DESIGNED BY: JURA SARKISSIAN		COMMERCE CENTER DRIVE CASTAIC CREEK DECK DETAIL SHEET 1	
DRAWN BY: ALBERT GEVORKIAN		REVIEWED Steve M. Hennessey 11/24/97 STRUCTURAL SECTION DATE	
PROJECT ENGINEER: JURA SARKISSIAN		BRIDGE NO.: 3794 PROJECT NO.: SHT.: 10 OF: 15	DWG. NO.: 614603



- NOTE - Unless otherwise indicated:
- For Concrete Barrier Type 26, See Caltrans Std. Plan B11-54
 - For 4' picket railing, see L.A.C.D.P.W. Std. Plan 6102-0.
 - Where standard barrier railing expansion joints interfere with picket railing post spacing, joints may be relocated 9" from @ post.
 - Utility hangers shall consist of 1" dia. x 9'lg. bolts in pairs @ 10'±. Embed 5" in concrete. Bolt 1"-BUNC-2, thread 6". Furnish 2 nuts per bolt. All parts to be galvanized. See specs.
 - Provide 1 1/2" dia. rigid galvanized steel conduit with pull wire as shown on this plan. Provide expansion fittings at sidewalk joints and abutment per A.P.W.A. Std. Plan 465-0 in Specs.
 - For #5 pull box, see A.P.W.A. Std. Plan 460-0.
 - For deck constr. jt. see CALTRANS std. plan B 0-5, bridge detail 5-2.


AS BUILT

Date: 1-26-01 Corrections by: G. Pereda

Resident Engineer: Zaven Abrahamian

No Changes

SIKAND ENGINEERING ASSOCIATES CONSULTING ENGINEERS 15250 BURNBANK BLVD., VAN NUYS, CALIFORNIA 91411 (818) 707-4554		LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS DESIGN DIVISION STRUCTURES SECTION	
DESIGNED BY: JORA SARKISSIAN		COMMERCE CENTER DRIVE OVER CASTAIC CREEK DECK DETAIL SHEET 2	
DRAWN BY: ALBERT GEVORKIAN		REVIEWED Steve M. Hennessy 11/24/97	
PROJECT ENGINEER: JORA SARKISSIAN		BRIDGE NO.: 3794 PROJECT NO.: SHT.: 11 OF: 15 DWG. NO.: 614602	DATE:







ADDED UTILITY HANGER AND OPENING LOCATIONS.

REVISIONS

CHECKED


DRAWN




- WALL CONSTRUCTION SEQUENCE**
- REMOVE 5' OF EXISTING SOIL.
CONSTRUCT AND COMPACT EMBANKMENT TO BOTTOM OF WALL FOOTING.
CONSTRUCT WALL.
CONSTRUCT AND COMPACT EMBANKMENT TO 6" ABOVE BOTTOM OF ABUTMENT FOOTING.
EXCAVATE TO BOTTOM OF ABUTMENT FOOTING 1 WEEK AFTER
COMPLETION OF COMPACTED FILL PLACEMENT.
PRE-DRILL FOR PILES TO ORIGINAL GROUND LEVELS AND DRIVE PILES.
FILL VOID WITH PER-GRAVEL AND CONSTRUCT ABUTMENT FOOTING.
CONTRACTOR MAY SUBMIT ALTERNATE CONSTRUCTION SEQUENCE FOR APPROVAL
BY ENGINEER.

AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes




SIKM ENGINEERING ASSOCIATES CONSULTING ENGINEERS 15226 BROADWAY BLVD., VAN NUT, CALIFORNIA (818) 787-8550 9141	LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS DESIGN DIVISION STRUCTURES SECTION		
DESIGNED BY: <u>JORA SARKISSIAN</u>	COMMERCE CENTER DRIVE OVER CASTAIC CREEK		
DRAWN BY: <u>ALBERT GEVORKIAN</u>	MISCELLANEOUS DETAILS		
PROJECT ENGINEER:  <u>JORA SARKISSIAN</u>	<table border="1"> <tr> <td data-bbox="2439 1870 2747 1947"> REVIEWED <u>Step M. Hennessey</u> 11/24/97 STRUCTURAL SECTION DATE </td> <td data-bbox="2756 1870 2915 1947"> BRIDGE NO.: <u>3794</u> PROJECT NO.: _____ SHT.: <u>12</u> DWG. NO.: _____ OF: <u>15</u> <u>614601</u> </td> </tr> </table>	REVIEWED <u>Step M. Hennessey</u> 11/24/97 STRUCTURAL SECTION DATE	BRIDGE NO.: <u>3794</u> PROJECT NO.: _____ SHT.: <u>12</u> DWG. NO.: _____ OF: <u>15</u> <u>614601</u>
REVIEWED <u>Step M. Hennessey</u> 11/24/97 STRUCTURAL SECTION DATE	BRIDGE NO.: <u>3794</u> PROJECT NO.: _____ SHT.: <u>12</u> DWG. NO.: _____ OF: <u>15</u> <u>614601</u>		

LOG OF BORING 89-025-F6	BORING NO. WB-F5	LOG OF BORING 89-025-F6	BORING NO. WB-F5
DESCRIPTION SURFACE CONDITION: Located in center of road ELEVATION: 980		DESCRIPTION	
0 FILL: Road surfaced with 3/4 inch gravel, base is locally derived sand and gravel		40 Grades to gravelly	
SP SAND: Tan, gravelly, fine to very coarse, graded layers 1 to 4 feet thick		45 ML SILT: Medium brown, fine to very coarse, weakly graded layers to 4 feet	
5		SP SAND: Tan, gravelly, fine to very coarse, weakly graded layers to 4 feet	
10		50	
15		55	
20		60 End of boring at 60 feet Water at 12 feet - no caving	

LOG OF BORING 89-025-F6	BORING NO. WB-F5 (Cont'd)
DESCRIPTION	
20 ML SILT: Reddish brown, clayey silt	
SP SAND: Tan, gravelly to very gravelly, fine to very coarse in graded 1 to 5 foot layers	
30	
35	
40 SP GRAVEL/ SAND: Change to cobbles, fine to medium	
40 SP SAND: Change to minor gravel	

* Percent
** Pounds per cubic foot
+ SPT



APPROXIMATE LOCATION OF BORINGS


SCALE: 1"=50'

GEOTECHNICAL INVESTIGATION CONDUCTED BY

R.T. FRANKIAN AND ASSOCIATES
234 SOUTH BUENA VISTA STREET
P.O. BOX 7762
BURBANK, CALIFORNIA 91510-7762

AS BUILT

Date: 1-26-01 Corrections by: G. Pereda
Resident Engineer: Zaven Abrahamian
No Changes



SIKAND ENGINEERING ASSOCIATES CONSULTING ENGINEERS 1522N BURNBANK BLVD., TAYLOR, CALIFORNIA 91791 (916) 767-8550		LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS DESIGN DIVISION STRUCTURES SECTION	
DESIGNED BY: JORA SARKISSIAN		COMMERCE CENTER DRIVE OVER CASTAIC CREEK	
DRAWN BY: ALBERT GEVORKIAN		LOG OF TEST BORINGS SHT. 3	
PROJECT ENGINEER: JORA SARKISSIAN		REVIEWED Steve M. Hennessey 11/24/97 STRUCTURAL SECTION DATE	BRIDGE NO.: 3794 PROJECT NO.: SHT.: 15 OF: 15
		DWG. NO.: 614598	





Appendix G – As-Built Drawings Flow Diversion Berm

NPDES NOTES

- ATTACHMENT A
- BEST MANAGEMENT PRACTICES FOR CONSTRUCTION ACTIVITIES
- The following is intended as an attachment for construction and grading plans and represent the minimum standards of good housekeeping which must be implemented on all construction sites regardless of size.
- ☐ Eroded sediments and other pollutants must be retained on site and may not be transported from the site via sheetflow, swales, area drains, natural drainage courses or wind.
 - ☐ Stockpiles of earth and other construction related materials must be protected from being transported from the site by the forces of wind or water.
 - ☐ Fuels, oils, solvents and other toxic materials must be stored in accordance with their listing and are not to contaminate the soil and surface waters. All approved storage containers are to be protected from the weather. Spills must be cleaned up immediately and disposed of in a proper manner. Spills may not be washed into the drainage system.
 - ☐ Excess or waste concrete may not be washed into the public way or any other drainage system. Provisions shall be made to retain concrete wastes on site until they can be disposed of as solid waste.
 - ☐ Trash and construction related solid wastes must be deposited into a covered receptacle to prevent contamination of rainwater and dispersal by wind.
 - ☐ Sediments and other materials may not be tracked from the site by vehicle traffic. The construction entrance roadways must be stabilized so as to inhibit sediments from being deposited into the public way. Accidental depositions must be swept up immediately and may not be washed down by rain or other means.
 - ☐ Any slopes with disturbed soils or denuded of vegetation must be stabilized so as to inhibit erosion by wind and water.
 - ☐ Other _____

- B. The following BMPs as outlined in, but not limited to, the Best Management Practice Handbook, California Stormwater Quality Task Force, Sacramento, California, 1993, or the latest revised edition, may apply during construction (additional measures may be required if deemed appropriate by County).
- CA001 - DEMATERING OPERATIONS
 - CA002 - PAVING OPERATIONS
 - CA003 - STRUCTURE CONSTRUCTION AND PAINTING
 - CA010 - MATERIAL DELIVERY AND STORAGE
 - CA012 - SPILL PREVENTION AND CONTROL
 - CA020 - SOLID WASTE MANAGEMENT
 - CA021 - HAZARDOUS WASTE MANAGEMENT
 - CA023 - CONCRETE WASTE MANAGEMENT
 - CA030 - VEHICLE AND EQUIPMENT CLEANING
 - CA031 - VEHICLE AND EQUIPMENT FUELING
 - CA032 - VEHICLE AND EQUIPMENT MAINTENANCE
 - CA040 - EMPLOYEE/SUBCONTRACTOR TRAINING
 - ESC01 - SCHEDULING
 - ESC02 - PRESERVATION OF EXISTING VEGETATION
 - ESC10 - SEEDING AND PLANTING
 - ESC11 - MULCHING
 - ESC20 - GEOTEXTILES AND MATS
 - ESC21 - DUST CONTROLS
 - ESC22 - TEMPORARY STREAM CROSSING
 - ESC23 - CONSTRUCTION ROAD STABILIZATION
 - ESC24 - STABILIZED CONSTRUCTION ENTRANCE
 - ESC30 - EARTH DIME
 - ESC31 - TEMPORARY DRAINS AND SHALES
 - ESC32 - SLOPE DRAIN
 - ESC40 - OUTLET PROTECTION
 - ESC41 - CHECK DAMS
 - ESC50 - SILT FENCE
 - ESC51 - STRAW BALE BARRIERS
 - ESC52 - SAND BAG BARRIER
 - ESC53 - BRUSH OR ROCK FILTER
 - ESC54 - STORM DRAIN INLET PROTECTION



HYDRAULIC ELEMENTS						
LINE	STATION	Q ₅₀ IN CFS	SECTION	S.F.	VELOCITY IN FT./SEC.	DEPTH IN FEET
LINE "L"	5+14.00 TO 5+35.00	12.0	24" R.C.P.	0.3225	19.7	0.61
	5+35.00 TO 5+50.00	6.0	24" R.C.P.	0.3225	16.8	0.70
	5+50.00 TO 6+37.00	6.0	24" R.C.P.	0.0100	5.9	0.89
LINE "M"	1+02.00 TO 1+35.60	6.0	18" R.C.P.	0.1601	15.5	0.95
	4+198.50 TO 5+137.08	10.0	24" R.C.P.	0.0020	3.18	9.00'
	5+137.08 TO 9+133.42	10.0	24" R.C.P.	0.0020	3.18	7.17'
LINE "N"	1+02.00 TO 2+01.91	5.0	18" R.C.P.	0.0023	2.83	4.51
	1+01.41 TO 1+34.59	NGL.	18" R.C.P.			
	1+01.00 TO 1+22.75	NGL.	18" R.C.P.			
LINE "O"	BEGINNING TO END OF LININGS C, D, F & G	50.700	NATURAL CHANNEL WITH 1:1 SIDE SLOPES	0.0188	10.81	14.9
	BEGINNING TO END OF LINING E	50.700	NATURAL CHANNEL WITH 1:1 SIDE SLOPES	0.0188	10.81	14.9
	LININGS A & B	9.700	NATURAL CHANNEL WITH 1:1 SIDE SLOPES	0.0272	6.69	4.4

BENCH MARK CL 3976
LACRD BM
RDBM TAG IN C.B. 4 FT. N.B.C.R TO FT. N.
AND 32 FT. E. CL INT. OLD ROAD AND
HASLEY CYN. ROAD OFF-RAMP
NEWHALL GUARD (1983) ELEV. 1065.685

GENERAL NOTES (Cont'd)

- ALL BACKFILL AND FILLS OUTSIDE OF STREET RIGHT OF WAY SHALL BE COMPACTED TO 90% OF MAXIMUM DENSITY AS DETERMINED BY A.S.T.M. SOIL COMPACTION TEST D1557-78 METHOD "D" UNLESS OTHERWISE SPECIFIED. THIS SHALL BE CERTIFIED BY A GEOTECHNICAL ENGINEER. THE CERTIFICATION SHALL BE SUBMITTED TO THE DIRECTOR OF PUBLIC WORKS PRIOR TO ACCEPTANCE OF WORK BY THE COUNTY.
- ALL BACKFILL AND FILLS WITHIN STREET RIGHT OF WAY SHALL BE COMPACTED IN ACCORDANCE WITH SECTION 306-1.3.4 OF THE STANDARD SPECIFICATIONS UNLESS OTHERWISE NOTED AND INSPECTED BY THE DEPARTMENT. CONTRACTOR SHALL NOTIFY THE INSPECTOR AT LEAST 24 HOURS IN ADVANCE FOR SOIL TESTING AS REQUIRED BY THE INSPECTOR.
- PIPE BEDDING SHALL BE IN ACCORDANCE WITH LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS STANDARD DRAWING NO. 3092 UNLESS OTHERWISE NOTED. THE BEDDING MATERIAL PLACED FROM THE BOTTOM OF THE PIPE TO 1 FOOT OVER THE TOP OF THE PIPE SHALL BE SAND, CRUSHED AGGREGATE, OR NATIVE FREE-DRAINING GRANULAR MATERIAL AND SHALL HAVE A SAND EQUIVALENT OF 20 OR GREATER.
- PIPE SHALL BE EMBEDDED 5 INCHES INTO ALL STRUCTURES INCLUDING INLET AND OUTLET HEADWALLS, UNLESS OTHERWISE SPECIFIED.
- UNLESS OTHERWISE SPECIFIED IN THE PROFILE ON THESE PLANS, THE PIPE SHALL BE MANUFACTURED WITH A MINIMUM CONCRETE COVER OVER THE STEEL IN THE INVERT OF 0.75 INCHES FOR R.C.P. UP TO 56 INCHES IN DIAMETER AND 1.25 INCHES FOR PIPE GREATER THAN 56 INCHES IN DIAMETER.
- ALL CATCH BASINS WITHIN THE DEDICATED STREET RIGHTS-OF-WAY SHALL BE CONSTRUCTED PER THE STREET PLANS.
- THE CONTRACTOR SHALL PROVIDE TO THE SATISFACTION OF THE DIRECTOR OF PUBLIC WORKS A SYSTEM FOR CONTRIBUTORY DRAINAGE TO BE OPERABLE AT ALL TIMES UNTIL THIS STORM DRAIN SYSTEM IS ACCEPTED FOR MAINTENANCE. THIS MAY HAVE TO BE DESIGNED BY A CIVIL ENGINEER.
- ALL REFERENCES ON THIS PLAN TO THE COUNTY ENGINEER, ROAD DEPARTMENT, OR FLOOD CONTROL DISTRICT SHALL APPLY TO THE APPROPRIATE ELEMENTS OF THE DEPARTMENT OF PUBLIC WORKS.
- EXISTING UTILITIES SHALL BE MAINTAINED IN PLACE BY THE CONTRACTOR, UNLESS OTHERWISE NOTED.
- WHERE THE UTILITIES ARE INDICATED ON THE DRAWINGS TO BE SUPPORTED, SAID SUPPORTS SHALL BE IN ACCORDANCE WITH STANDARD PLANS FOR CONSTRUCTION NO. 224, UNLESS OTHERWISE INDICATED.
- ALL OPENINGS RESULTING FROM THE CUTTING OR PARTIAL REMOVAL OF EXISTING CULVERTS, PIPES OR SIMILAR STRUCTURES SHALL BE SEALED WITH 8 INCHES OF BRICK AND MORTAR OR 6 INCHES OF CONCRETE, UNLESS OTHERWISE SHOWN.
- MANHOLES NO. 1, 2, 3, AND 4, SHALL USE THE STANDARD PLANS FOR PUBLIC WORKS CONSTRUCTION NO. 630 FOR THE "FRAME AND COVER" AND NO. 635 FOR THE "STANDARD DROP STEP".
- THIS STORM DRAIN WILL NOT BE ACCEPTED FOR MAINTENANCE UNTIL THE STREETS HAVE BEEN PAVED, MANHOLES BROUGHT TO GRADE AND THE SYSTEM CLEANED TO SATISFACTION OF THE DIRECTOR OF PUBLIC WORKS.
- THE LATEST REVISED STANDARD PLAN OR DRAWING SHALL BE USED UNLESS OTHERWISE SPECIFICALLY NOTED.
- A NPDES PERMIT FROM THE REGIONAL WATER QUALITY CONTROL BOARD IS REQUIRED BEFORE ANY DISCHARGE OF NON-STORM WATER INTO THE STORM DRAIN IS ALLOWED.

LIST OF STANDARDS

	L.A.C.D.P.W.	A.P.N.A.
1. M.H. NO. 1	PER	(321-0)
2. CURB OPENING CATCH BASIN	PER	300-0
3. STANDARD M.H. SHAFT	PER	(324-0)
4. M.H. FRAME AND COVER	PER	630-0
5. STEEL STEP	PER	635-0
6. C.B. MANHOLE FRAME AND COVER	PER	312-0
7. C.B. REINFORCEMENT	PER	309-0
8. MONOLITHIC C.B. CONNECTION	PER	308-0
9. C.B. FACE PLATE ASSEMBLY	PER	310-0
10. AND PROTECTION BAR	PER	311-0
11. FRAME AND GRATING FOR C.B.	PER	313-0
12. LOCAL DEPRESSION AT C.B.	PER	(331-0)
13. J.S. NO. 2	PER	600-0
14. CHAIN LINK FENCE AND GATES	PER	3092-0
15. PIPE BEDDING	PER	6008-0
16. SAFETY REQUIREMENTS	PER	380-1
17. CONCRETE COLLAR	PER	

GENERAL NOTES:

- A PERMIT SHALL BE OBTAINED AND A DEPOSIT PAID TO THE DEPARTMENT OF PUBLIC WORKS AT THE PERMIT COUNTER, 900 SOUTH FREMONT AVENUE 8-TH FLOOR, ALHAMBRA, AT LEAST 72 HOURS PRIOR TO STARTING WORK UNDER THIS CONTRACT. COPIES OF ALL OTHER REQUIRED PERMITS, SUCH AS FLOOD CONTROL DISTRICT AND ROAD EXCAVATION, MUST BE FILED WITH THE PERMIT APPLICATION.
- WHEN WORK IS WITHIN A CONTRACT CITY, THE CONTRACTOR MUST CONTACT THE DIRECTOR OF PUBLIC WORKS OF THAT CITY TO DETERMINE THE LOCATION TO PAY THE INSPECTION DEPOSIT.
- THE CONTRACTOR SHALL CONTACT THE DISTRICT OFFICE LISTED AT THE "APPLICATION FOR STORM DRAIN CONSTRUCTION INSPECTION FORM 1" TO ARRANGE FOR AN ACCEPTABLE CONSTRUCTION START DATE.
- APPROVAL OF THIS PLAN BY THE COUNTY OF LOS ANGELES DOES NOT CONSTITUTE A REPRESENTATION TO THE ACCURACY OF THE LOCATION, OR THE EXISTENCE OR NON-EXISTENCE OF ANY UNDERGROUND UTILITY, PIPE OR STRUCTURE WITHIN THE LIMITS OF THIS PROJECT. THIS NOTE APPLIES TO ALL SHEETS.
- ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST ADOPTED EDITION OF THE "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION", INCLUDING SUPPLEMENTS AND SHALL BE PROSECUTED ONLY IN THE PRESENCE OF THE DIRECTOR OF PUBLIC WORKS.
- THE CONTRACTOR'S ATTENTION IS DIRECTED TO SECTION 7-10.4.1 OF THE "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION" IN REGARD TO SAFETY ORDERS AND SHALL CONFORM TO THE "MINIMUM PUBLIC SAFETY REQUIREMENTS" AS SHOWN IN LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS STD. 6008-0.
- ELEVATIONS ARE IN FEET ABOVE U.S.C. & G.S. MEAN SEA LEVEL DATUM OF 1929, UNLESS OTHERWISE INDICATED.
- NO CONCRETE SHALL BE PLACED UNTIL THE FORMS AND REINFORCING STEEL HAVE BEEN PLACED, INSPECTED AND APPROVED.
- ALL STRUCTURAL CONCRETE SHALL BE PORTLAND CEMENT CONCRETE WITH AN ULTIMATE 28 DAY COMPRESSIVE STRENGTH OF 4000 P.S.I. UNLESS OTHERWISE NOTED.
- TRANSVERSE REINFORCEMENT AND TRANSVERSE JOINTS SHALL BE PLACED AT RIGHT ANGLES (OR RADIAL) TO THE CONDUIT CENTER LINE EXCEPT AS OTHERWISE SHOWN ON THE DRAWINGS.
- ALL STEEL ADJACENT TO FACE OF CONCRETE SHALL HAVE 2" CLEARANCE UNLESS OTHERWISE SPECIFIED.
- REINFORCEMENT SHALL BE DEFORMED BARS OF INTERMEDIATE GRADE STEEL, PER A.S.T.M. A-615-GRADE 60.
- ALL BAR BENDS AND HOOKS SHALL CONFORM TO THE AMERICAN CONCRETE INSTITUTE "MANUAL OF STANDARD PRACTICE".
- DIMENSIONS FROM FACE OF CONCRETE TO STEEL ARE TO CENTER LINE OF STEEL UNLESS OTHERWISE NOTED.
- ALL STEEL THAT IS TO BE CONTINUOUS SHALL HAVE A MINIMUM LAP OF 30 BAR DIAMETERS OR 18" WHICHEVER IS GREATER.
- ALL CONSTRUCTION JOINTS IN THE FOOTING OF SLABS AND WALLS SHALL BE IN THE SAME PLANE. NO STAGGERING OF JOINTS WILL BE PERMITTED.
- ALL EXPOSED EDGES SHALL BE FINISHED WITH A 3/4" CHAMFER.
- UNLESS OTHERWISE SHOWN, CONCRETE DIMENSIONS SHALL BE MEASURED VERTICALLY OR HORIZONTALLY AND PARALLEL OR AT RIGHT ANGLES (OR RADIAL) TO THE CENTER LINE OF CONSTRUCTION.
- CONCRETE BACKFILL IS REQUIRED WHEN THE PIPE HAS LESS THAN ONE FOOT OF COVER. THE CONCRETE BACKFILL SHALL CONSIST OF 1:3:5 MIX, PORTLAND CEMENT CONCRETE POURED FROM WALL TO WALL OF TRENCH AND FROM BOTTOM OF TRENCH TO A MINIMUM OF 4 INCHES OVER THE TOP OF THE PIPE.
- ALL PIPES SHALL BE PLACED IN TRENCH IN NATURAL GROUND AND/OR COMPACTED FILL. THE GROUND LEVEL BEFORE THE TRENCHING SHALL BE AT LEAST 3 FEET ABOVE THE TOP OF THE PIPE ELEVATION, OR AT FINISH SURFACE ELEVATION, WHICHEVER IS LESS. ALL BACKFILLS IN EASEMENTS SHALL BE COMPACTED TO THE DENSITY REQUIRED BY THE GRADING PLAN.

RIPRAP NOTES

- ROCKS FOR GROUTED RIPRAP SHALL BE GOOD QUALITY RIVER RUN ROCK. THE SMALLEST DIMENSIONS SHALL EXCEED 6 INCHES AND THE LARGEST DIMENSION SHALL NOT EXCEED 24 INCHES. THE LARGEST DIMENSION SHALL NOT EXCEED 4 TIMES THE SMALLEST DIMENSION.
- THERE SHALL BE A GROUT BED OF AT LEAST 2 INCHES BENEATH THE FIRST LAYER OF ROCK. ALL THE VOIDS BETWEEN THE ROCKS SHALL BE FILLED WITH GROUT. MAXIMUM SPACING BETWEEN ROCKS SHALL BE 2 INCHES.
- SURFACE ROCKS SHALL BE IMBEDDED FROM 1/2 TO 2/3 OF THEIR MAXIMUM DIMENSION.

NOTE: CONCRETE MAY BE SUBSTITUTED FOR THE GROUT.

PRIVATE ENGINEERS NOTICE TO CONTRACTORS

THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITY PIPES OR STRUCTURES SHOWN ON THESE PLANS ARE OBTAINED BY A SEARCH OF THE AVAILABLE RECORDS. TO THE BEST OF OUR KNOWLEDGE THERE ARE NO EXISTING UTILITIES EXCEPT AS SHOWN ON THIS MAP.

THE CONTRACTOR IS REQUIRED TO TAKE DUE PRECAUTIONARY MEASURES TO PROTECT THE UTILITY LINES SHOWN AND ANY OTHER LINES NOT OF RECORD OR NOT SHOWN ON THIS DRAWING.

REGISTERED CIVIL ENGINEER No. 42890 DATE

COUNTY OF LOS ANGELES, CALIFORNIA
HARRY W. STONE DIRECTOR OF PUBLIC WORKS

LAND DEVELOPMENT DIVISION
APPROVED BY: *Ronald D. Dinklage* DATE: 4-13-98
FOR ASSISTANT DEPUTY DIRECTOR
CHECKED BY: *R.D. Dinklage* R.C.E. No. 45641 DATE: 4-13-98
OFFICE OF THE DIRECTOR OF PUBLIC WORKS




PREPARED BY:
SIKAND ENGINEERING ASSOCIATES
15230 BURBANK BLVD.
VAN NUYS, CA. 91411
(818) 787-8550
SIGNATURE: *[Signature]* R.C.E. No. 42890


NO.	REVISION	REVISED BY	APPROVED BY	DATE

SEE SHEET NO. 9 FOR
GRADING & EASEMENT DATA

COUNTY OF LOS ANGELES, CALIFORNIA
HARRY W. STONE DIRECTOR OF PUBLIC WORKS
PLANNING AND DEVELOPMENT DIVISION
CHECKED BY: *[Signature]* R.C.E. NO. *45391* DATE: *4-18-98*
OFFICE OF THE DIRECTOR OF PUBLIC WORKS



NO.	Δ	R	L	T
C1	29°26'34"	504.00'	258.99'	132.42'
C2	06°01'22"	698.00'	73.37'	36.72'



NO.	REVISION	REVISED BY	APPROVED BY	DATE
△	REVISED LATERAL "L-2" PROFILE	<i>[Signature]</i> RGS 5/1/13	<i>[Signature]</i>	11/1/13




ALLIANCE ENGINEERING
2248 PARADAY AVE.
CARLSBAD, CA 92008
760-431-9896

For Δ ONLY




SIKAND ENGINEERING ASSOCIATES
15230 BURBANK BLVD.
VAN NUYS, CA. 91411
(818) 787-8550
JORA SARKISSIAN

SIGNATURE: [Signature] R.C.E. NO. 42890




COUNTY OF LOS ANGELES, CALIFORNIA
HARRY W. STONE DIRECTOR OF PUBLIC WORKS

CHECKED BY: P. J. [Signature] LAND DEVELOPMENT DIVISION R.C.E. NO. 45641 DATE: 4-13-98
OFFICE OF THE DIRECTOR OF PUBLIC WORKS



NO.	Δ	R	L	T
C1	29°26'34"	520.00'	267.21'	136.63'
C2	06°01'22"	714.00'	75.05'	37.56'
C3	180°00'00"	8.00'	25.13'	—



NO.	REVISION	REVISED BY	APPROVED BY	DATE
⚠	VOIDED LAT. "M-2" PROFILE.	<i>[Signature]</i> 42890	<i>[Signature]</i>	7/1/99

SEE SHEET NO. 9 FOR
GRADING & EASEMENT DATA



SIKAND ENGINEERING ASSOCIATES
15230 BURBANK BLVD.
VAN NUYS, CA. 91411
(818) 787-8550
JORA SARKISSIAN


SIGNATURE: [Signature] R.C.E. NO. 42890

COUNTY OF LOS ANGELES, CALIFORNIA

HARRY W. STONE DIRECTOR OF PUBLIC WORKS

CHECKED BY: Ph.D. Dwyer LAND DEVELOPMENT DIVISION
R.C.E. NO. 456A1 DATE: 4-13-98
OFFICE OF THE DIRECTOR OF PUBLIC WORKS

SHT 4 OF 9 SHTS




PROFILE OF LINING "D"

SCALE: HORIZ. 1"=40'
VERT. 1"=8'

134.52' ROCK RIP-RAP LINING PER DETAIL ON SHEET NO. 8


SEE SHEET NO. 9 FOR
GRADING & EASEMENT DATA



PLAN OF LINING "D"

SCALE: 1"=40'


NO.	REVISION	REVISED BY	APPROVED BY	DATE




SIKAND ENGINEERING ASSOCIATES
15230 BURBANK BLVD.
VAN NUYS, CA. 91411
(818) 787-8550
JORA SARKISSIAN
SIGNATURE: *J. Sarkissian* R.C.E. NO. 42890




COUNTY OF LOS ANGELES, CALIFORNIA
HARRY W. STONE DIRECTOR OF PUBLIC WORKS
CHECKED BY: *Paul K. Dolan* LAND DEVELOPMENT DIVISION R.C.E. NO. 45641 DATE: 4-13-98
OFFICE OF THE DIRECTOR OF PUBLIC WORKS




PROFILE OF LINING "E"
SCALE: HORIZ. 1"=40'
VERT. 1"=8'




PROFILE OF LINING "F"
SCALE: HORIZ. 1"=40'
VERT. 1"=8'




PROFILE OF LINING "G"
SCALE: HORIZ. 1"=40'
VERT. 1"=8'



PLAN OF LINING "E"
SCALE: 1"=40'



PLAN OF LINING "F"
SCALE: 1"=40'



PLAN OF LINING "G"
SCALE: 1"=40'

NO.	REVISION	REVISED BY	APPROVED BY	DATE

* CUT-OFF DEPTH TRANSITION FROM 10' TO 6'
SLOPE OF LINING TRANSITION FROM 1 1/2:1 TO 2:1
CONCRETE LINING.





10+96.00 END RIP-RAP LINING
BEGIN CONCRETE LINING
(SEE JOIN DETAIL ON SHT. 8)

11+06.00 END CONCRETE LINING
BEGIN RIP-RAP LINING
(SEE JOIN DETAIL ON SHT. 8)



SIKAND ENGINEERING ASSOCIATES
15230 BURBANK BLVD
VAN NUYS, CA. 91411
(818) 787-8550
JURA SARKISSIAN
SIGNATURE: *J. Sarkissian* R.C.E. NO. 42890

COUNTY OF LOS ANGELES, CALIFORNIA
HARRY W. STONE DIRECTOR OF PUBLIC WORKS
CHECKED BY: *P. Stone* LAND DEVELOPMENT DIVISION
R.C.E. NO. 45641 DATE: 4-13-98
OFFICE OF THE DIRECTOR OF PUBLIC WORKS



STATION	Δ	R	L	T
1	23° 34' 49"	45.00'	18.52'	9.39'
2	67° 18' 32"	45.00'	52.86'	29.96'
3	19° 46' 50"	45.00'	15.54'	7.85'
4	26° 55' 36"	45.00'	21.15'	10.77'
5	34° 48' 32"	45.00'	27.34'	14.11'
6	60° 00' 00"	22.50'	23.56'	12.99'
7	11° 54' 13"	45.00'	9.34'	4.69'
8	51° 02' 11"	22.50'	20.04'	10.14'

PLAN OF LINE "M"
SCALE: 1"=40'

NO.	REVISION	REVISED BY	APPROVED BY	DATE
1	REVISED LINE "M" PLAN & PROFILE, ELIMINATED LATERAL "M-2"	J. KHALIL	S. KHALIL	7/1/99
2	REVISED LINE "M" PLAN & PROFILE	J. KHALIL	S. KHALIL	11/1/99
3	REVISED LINE "L" PROFILE AND ADDED PROPOSED (2)-18" SEWER CROSSING	J. KHALIL	S. KHALIL	11/1/99

PLANS PREPARED BY:
SIKAND ENGINEERING ASSOCIATES
15230 BURBANK BLVD., VAN NUYS,
CALIF. 91411, TEL. (818) 787-8550
JOHN SARKISSIAN
SIGNATURE: *John Sarkissian* R.C.E. NO. 42890

COUNTY OF LOS ANGELES, CALIFORNIA
THOMAS A. TIDEMANSON DIRECTOR OF PUBLIC WORKS
CHECKED BY: *John Sarkissian* R.C.E. NO. 45601 DATE: 4-13-98
OFFICE OF THE DIRECTOR OF PUBLIC WORKS

STRUCTURAL NOTES

- DIMENSIONS FROM FACE OF CONCRETE TO STEEL ARE TO CENTER OF BAR AND SHALL BE TWO INCHES UNLESS OTHERWISE SHOWN.
- CONCRETE DIMENSIONS SHALL BE MEASURED HORIZONTALLY OR VERTICALLY ON THE PROFILE, AND PARALLEL TO OR AT RIGHT ANGLES (OR RADIALLY) TO CENTERLINE OF CONDUIT ON THE PLAN EXCEPT AS OTHERWISE SHOWN.
- ALL BAR BENDS AND HOOKS SHALL CONFORM TO THE AMERICAN CONCRETE INSTITUTE'S "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE", 1971 EDITION, SECTION 7.1.
- PLACING OF REINFORCEMENT SHALL CONFORM TO THE AMERICAN CONCRETE INSTITUTE'S "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE", 1971 EDITION, SECTION 7.3.
- TRANSVERSE CONSTRUCTION JOINTS SHALL NOT BE PLACED WITHIN 30 INCHES OF MANHOLE OR JUNCTION STRUCTURE OPENING.
- TRANSVERSE CONSTRUCTION JOINTS IN WALLS AND SLABS SHALL BE IN THE SAME PLANE. NO STAGGERING OF JOINTS WILL BE PERMITTED. TRANSVERSE CONSTRUCTION JOINTS SHALL BE NORMAL OR RADIAL TO THE CENTERLINE OF CONSTRUCTION.
- THE TRANSVERSE REINFORCING STEEL SHALL TERMINATE ONE AND ONE-HALF INCHES FROM THE CONCRETE SURFACES UNLESS OTHERWISE SHOWN ON THE STRUCTURAL DETAILS.
- EXPOSED EDGES OF CONCRETE MEMBERS SHALL BE ROUNDED OR BEVELLED.
- NO SPLICES IN TRANSVERSE STEEL REINFORCEMENT WILL BE PERMITTED OTHER THAN SHOWN ON THE DRAWING WITHOUT APPROVAL OF THE ENGINEER. NO MORE THAN TWO SPLICES WILL BE PERMITTED IN ANY LONGITUDINAL BAR BETWEEN TRANSVERSE JOINTS. SPLICES SHALL BE STAGGERED.
- LONGITUDINAL STEEL SHALL BE LAPPED 20 BAR DIAMETERS AT SPLICES. TRANSVERSE STEEL SHALL BE LAPPED 30 BAR DIAMETERS AT SPLICES.
- LONGITUDINAL STEEL SHALL BE CONTINUOUS AND EXTEND THROUGH ALL CONSTRUCTION JOINTS.
- UNLESS OTHERWISE SHOWN ON THE DRAWINGS, TRANSVERSE JOINT KEYWAYS (IN SLABS AND WALLS), AS DETAIL FOR LONGITUDINAL KEYWAYS AT THE BASE OF THE WALLS, SHALL BE PLACED AT THE END OF EACH FOUR, BUT THE SPACING THEREOF SHALL NOT EXCEED 50 FEET OR BE LESS THAN 10 FEET. ALL CONSTRUCTION JOINTS IN BOTTOM SLAB, TOP SLAB, AND SIDE WALLS SHALL BE IN THE SAME PLANE. NO STAGGERING OF JOINTS WILL BE PERMITTED.
- UNLESS OTHERWISE SHOWN ON THE DETAILS, IN CURVED SECTIONS, TRANSVERSE BARS SHALL BE PLACED RADIALLY. STRAIGHT TRANSVERSE BARS IN TOP AND BOTTOM SLABS SHALL BE SPACED AS SHOWN ON THE TYPICAL SECTIONS. SPACING SHALL BE AT THE CENTERLINE OF THE BARREL ON THE OUTSIDE OF THE CURVE FOR DOUBLE BARREL BOXES. STRAIGHT BARS AND L-BARS IN WALLS SHALL BE SPACED AS SHOWN FOR THE TYPICAL SECTIONS. WITH THE SPACING MEASURED BETWEEN THE VERTICAL LEGS OF BARS.
- AT THE BEGINNING AND ENDING OF ALL POURS, A CURTAIN OF REINFORCEMENT COMPOSED OF B, C, C2, D, CW, F, G, AND H BARS SHALL BE PLACED THREE INCHES FROM THE TRANSVERSE CONSTRUCTION JOINT.
- THE VERTICAL WALL STEEL IN INTERIOR WALLS AND IN THE INTERIOR FACE OF EXTERIOR WALLS MAY BE SPLICED AT THE CONSTRUCTION JOINT AT THE BASE OF THE WALL. THE SPLICES SHALL BE 20 BAR DIAMETERS IN LENGTH.
- IN ALL SECTIONS LAP C AND C2 BARS. THE VERTICAL LENGTH OF C AND C2 BARS HAS BEEN CALCULATED FOR A FOUR INCH STARTER WALL. IF THE HEIGHT OF THE STARTER WALL IS VARIED, THE VERTICAL LENGTH OF THE C AND C2 BARS SHALL BE VARIED CORRESPONDINGLY SO AS TO MAINTAIN A 30 DIAMETER LAP BETWEEN THE TWO BARS. THE LAPS SHALL BE BASED ON THE SMALLER BARS.
- CONCRETE QUANTITIES ARE BASED ON A SIX-BY-SIX INCH FILLET AND THE STEEL QUANTITIES DO NOT INCLUDE ANY OPTIONAL SPLICES.
- IF WALL THICKNESS IS SIX INCHES PLACE REINFORCEMENT AT THE CENTERLINE OF THE WALL.
- THE DESIGN OF BOX SECTIONS IDENTIFIED BY A NUMERICAL VALUE IS BASED ON A WIDTH OF TRENCH EQUAL TO THE OUTSIDE WIDTH OF THE CONDUIT PLUS THREE FEET. WHEN THE COVER IS EQUAL TO 10 FEET OR LESS THE TRENCH WIDTH IS UNRESTRICTED. WHEN THE COVER IS GREATER THAN 10 FEET AND THE TRENCH WIDTH IS GREATER THAN THE OUTSIDE WIDTH OF THE CONDUIT PLUS 3 FEET FOR A DISTANCE IN EXCESS OF 10 FEET AN ALTERNATE SECTION SHALL BE USED AS INDICATED BELOW.
- WHEN THE DEPTH OF COVER IS LESS THAN 18 FEET, SECTIONS WITH THE SUFFIX "B" SHALL BE USED.
- WHEN THE DEPTH OF COVER IS GREATER THAN 18 FEET AND:
 - THE TRENCH WIDTH IS LESS THAN THE OUTSIDE WIDTH OF THE CONDUIT PLUS 6 FEET, SECTIONS WITH SUFFIX "A" SHALL BE USED.
 - THE TRENCH WIDTH IS GREATER THAN THE OUTSIDE WIDTH OF CONDUIT PLUS 6 FEET, SECTIONS WITH THE SUFFIX "R" SHALL BE USED.

R. C. RECTANGULAR CHANNEL

- TRANSVERSE CONSTRUCTION JOINTS SHALL NOT BE PLACED WITHIN 30 INCHES OF INLETS.
- TRANSVERSE JOINTS SHALL BE PLACED AT THE JUNCTION OF RECTANGULAR OPEN CHANNEL SECTIONS WITH CLOSED CONDUIT SECTIONS. THE JOINT SHALL NOT BE KEYED AND SHALL HAVE A THREE-EIGHTS-INCH LAYER OF EXPANSION JOINT MATERIAL IN WALLS AND INVERT.
- ALL RECTANGULAR OPEN CHANNEL WALLS SHALL BE FENCED IN ACCORDANCE WITH APWA STANDARD DRAWING 600-0 EXCEPT AS OTHERWISE SHOWN ON THE DRAWINGS.
- UNLESS OTHERWISE SHOWN ON THE DRAWINGS, IN CURVED SECTIONS, THE MAXIMUM SPACING OF BARS SHALL NOT EXCEED THAT SHOWN ON THE TYPICAL SECTIONS. STEEL SHALL BE PLACED RADIALLY FROM THE MAXIMUM SPACING.
- AT THE BEGINNING AND ENDING OF ALL POURS, A COMPLETE CURTAIN OF REINFORCEMENT COMPOSED OF B1, B4, AND BY BARS SHALL BE PLACED THREE INCHES FROM THE TRANSVERSE CONSTRUCTION JOINT.
- LONGITUDINAL STEEL SHALL TERMINATE TWO INCHES FROM TRANSVERSE CONSTRUCTION JOINTS.



STRUCTURAL DESIGN CRITERIA

LIVE LOAD
H₂O - S16-44 unless otherwise noted

DEAD LOAD
Earth load per Marston's formula: w = 110 p.c.f.
K_u = K_u' = 0.150
Bd = Outside width of box plus 3 feet
Side earth 37 p.s.f. per foot of depth
Internal water pressure: 62.4 p.s.f. per foot of depth
Weight of concrete: 150 p.c.f.

ALLOWABLE STRESSES
f_c = 4000 p.s.i. at 28 days
f_c = 1800 p.s.i.
f_s = 24000
n = 8
shear and bond stresses per A.C.I. 318-63






NO	REVISION	REVISED BY	APPROVED BY	DATE





WALL REINFORCING BEYOND BRIDGE

DESIGN H	2'	4'	6'	8'
"C" BARS	#4 @ 12"	#4 @ 12"	#4 @ 12"	#5 @ 9"
"C" KEY	0"	6"	15"	24"
"d" BARS	—	—	#4 @ 18"	#4 @ 12"








UNDER BRIDGE: #4 @ 12"



CONCRETE LINING DETAIL "B"



NOTE: EXPANSION JOINT SHALL BE SPACED @ 40' INTERVALS



SIKAND ENGINEERING ASSOCIATES
15230 BURBANK BLVD.
VAN NUYS, CA 91411
(818) 787-8550
JORA SARKISSIAN
SIGNATURE: *J. S. Sarkissian* R.C.E. NO. 42890

COUNTY OF LOS ANGELES, CALIFORNIA
HARRY W. STONE DIRECTOR OF PUBLIC WORKS
CHECKED BY: *[Signature]* R.C.E. NO. 15641 DATE: 4-13-98
OFFICE OF THE DIRECTOR OF PUBLIC WORKS

EASEMENT TO L.A.C.F.C.D. FOR FLOOD CONTROL PURPOSES.

STORM DRAIN PLANS IN
D.S. NO. 485 P.D. No. 2298 (UNIT 10)


EASEMENT DATA

T NO.	DIRECTION	DISTANCE
1.	S. 40°42'51" W	85.81'
2.	N. 73°57'48" W	40.24'
3.	N. 16°02'12" E	40.00'
4.	N. 45°25'14" E	8.43'
5.	N. 45°25'14" E	20.00'
6.	N. 79°06'38" E	54.08'
7.	N. 74°00'15" E	52.83'
8.	N. 48°25'14" E	10.30'
9.	S. 23°27'24" E	23.43'
10.	S. 16°20'56" W	40.00'
11.	S. 49°51'40" W	11.28'
12.	N. 72°53'09" W	19.00'
13.	S. 45°25'14" W	19.65'
14.	S. 41°34'46" E	14.01'
15.	S. 16°20'56" W	26.00'
16.	S. 73°39'04" E	44.00'
17.	S. 16°20'56" W	26.00'
18.	S. 73°39'04" E	70.00'
19.	S. 35°49'21" E	33.35'
20.	S. 60°44'13" W	56.74'
21.	S. 40°39'43" E	7.19'
22.	N. 16°20'56" E	34.56'
23.	N. 16°20'56" E	34.56'
24.	S. 48°25'14" W	109.31'
25.	S. 48°25'14" W	109.31'
26.	S. 48°25'14" W	109.31'
27.	S. 48°25'14" W	109.31'
28.	S. 48°25'14" W	109.31'
29.	S. 44°10'19" E	16.02'

EASEMENT CURVE DATA

C NO.	DELTA	RADIUS	LENGTH	TANGENT
1.	100°14'12"	111.00'	194.19'	132.84'
2.	005°37'02"	847.00'	83.04'	41.55'
3.	026°27'15"	273.91'	126.47'	64.38'
4.	048°07'38"	250.00'	209.99'	111.64'
5.	044°29'23"	87.00'	67.55'	35.58'
6.	003°44'54"	564.00'	36.90'	18.46'
7.	069°39'23"	90.00'	109.42'	62.62'
8.	044°09'28"	73.00'	56.26'	29.61'
9.	034°50'53"	104.00'	63.25'	32.64'
10.	000°55'03"	992.00'	15.89'	7.94'

SCALE: 1" = 60'



13 L.F. - 12" P.V.C. AND C.S.P. INLET
PER A.R.W.A. STD. PLAN NO. 351-1,
CASE 1, INLET ELEV. = 999.00
(NOT TO BE MAINTAINED BY THE LACPCD)

EASEMENT CURVE DATA (CONT.)

C NO.	DELTA	RADIUS	LENGTH	TANGENT
11.	59°15'34"	42.00'	43.44'	23.89'
12.	59°15'34"	58.00'	59.99'	32.99'
13.	27°11'16"	58.00'	27.62'	14.03'
14.	27°11'16"	42.00'	19.93'	10.16'

SECTION "A-A"

SCALE: 1/4" = 1'-0"

SECTION "B-B"

SCALE: 1/4" = 1'-0"

NO.	REVISION	REVISED BY	APPROVED BY	DATE
1	REVISED EASEMENT DATA, REVISED N.Y. CURB LOC. @ C.C.D. @ HWY 126 GRADING.	42890	7/9/99	



SIKAND ENGINEERING ASSOCIATES
15230 BURBANK BLVD.
VAN NUYS, CA 91411
(818) 787-8550
JORA SARKISSIAN
SIGNATURE: [Signature] R.C.E. No. 42890

COUNTY OF LOS ANGELES, CALIFORNIA
HARRY W. STONE, DIRECTOR OF PUBLIC WORKS
CHECKED BY: [Signature] R.C.E. NO. 45641 DATE: 4-13-98
OFFICE OF THE DIRECTOR OF PUBLIC WORKS



Appendix H – ESA Documentation

Documentation of ESA Compliance

The VCC Project for which a CLOMR is sought involves federal permitting by the U.S. Army Corps of Engineers under Section 404 of the Clean Water Act. The VCC Project, including the area subject to the requested CLOMR, lies within the Valencia Commerce Center development area covered by Corps Permit No. 89-00419-AOA (“Corps Permit”). The Corps Permit, as amended by letter dated March 3, 2003, authorized the discharge of fill material to waters of the United States for the construction and maintenance of flood control, bank stabilization, site drainage facilities and bridges associated with the Valencia Commerce Center development.

In compliance with Section 7 of the ESA, the Corps initiated formal consultation with the U.S. Fish and Wildlife Service regarding the effects of issuing the Corps Permit. The Service issued Biological Opinion No. 1-8-02-F-43 (“Biological Opinion,” **attached**), analyzing the effects of the proposed activities on the federally listed arroyo toad and unarmored threespine stickleback. The Biological Opinion concluded that the activities authorized by the Corps Permit would not jeopardize the continued existence of the arroyo toad or unarmored stickleback, and it authorized incidental take of those species associated with the Valencia Commerce Center development. The Biological Opinion also concurred with the Corps’ determination that the activities were not likely to adversely affect the federally listed least Bell’s vireo.

The Corps Permit expired before all authorized activities were completed. In order to complete the current portion of the Valencia Commerce Center development, Newhall expects to seek additional authorization from the Corps. The Corps will comply with the ESA in connection with any new permit action, including conducting any additional consultation required by ESA Section 7.


Attachment: Biological Opinion No. 1-8-02-F-43



United States Department of the Interior

FISH AND WILDLIFE SERVICE

Ventura Fish and Wildlife Office
2493 Portola Road, Suite B
Ventura, California 93003



In Reply, refer to: 2002-6.3

December 17, 2002

David J. Castanon, Chief
North Coast Section, Regulatory Branch
Ventura Field Office, Army Corps of Engineers
2151 Alessandro Drive, Suite 110
Ventura, California 93001

Subject: Biological Opinion for the Castaic Creek Bank Protection, Valencia Commerce Center, Los Angeles County, California (No. 89-00419-AOA)(1-8-02-F-43)

Dear Mr. Castanon:

This document transmits the U.S. Fish and Wildlife Service's (Service) biological opinion based on our review of the U.S. Army Corps of Engineers (Corps) authorization of the Valencia Company to construct flood control and site drainage facilities associated with the Valencia Commerce Center and its effects on the federally endangered arroyo toad (*Bufo californicus*), and the federally endangered unarmored threespine stickleback (*Gasterosteus aculeatus williamsoni*) in accordance with section 7 of the Endangered Species Act of 1973, as amended (Act) (16 U.S.C. 1531 et seq.). You also requested formal consultation on the effects of the action on critical habitat for the arroyo toad. Because of the recent vacature of this critical habitat (see Status of the Species section below), our consultation does not address the effects of the action on critical habitat. Unarmored threespine stickleback are known to occur downstream at the Castaic Creek and Santa Clara River confluence. Your January 7, 2002, request for the initiation of formal consultation was received on January 9, 2002.

The Corps has determined that the project is not likely to adversely affect the federally endangered least Bell's vireo (*Vireo bellii pusillus*), and has not included the species in its request for formal consultation. The Corps reached this conclusion because focused surveys for breeding least Bell's vireos would be conducted immediately prior to construction and each year during the breeding season for the duration of the project, and if nests are found, construction would be set back a minimum of 500 feet from nest sites (Aaron Allen, Corps, pers. comm. 2002). The Service concurs with the Corps' determination that this species is not likely to be adversely affected by the authorization of the 404 permit. Consequently, the least Bell's vireo will not be discussed further in this biological opinion.

David J. Castanon (1-8-02-F-43)

2

This biological opinion is based on information provided in the biological evaluation prepared by URS Corporation (URS 2002) for the Corps; other project information provided by the Corps, including the results of a focused survey for arroyo toads in Castaic Creek (Impact Sciences 2001a); a letter to the Corps from Valencia Company (Mark Subbotin *in litt.* 2002a); and information in our files. A complete administrative record of this consultation is on file at the Ventura Fish and Wildlife Office.

CONSULTATION HISTORY

Your original request for formal consultation included only the arroyo toad. The unarmored threespine stickleback was not included at the time because we believed the species was not present in Castaic or Hasley creeks. Since the original request for formal consultation was sent, new information has been made available to us. Specifically, installation of bank protection may require dewatering operations in which groundwater is collected and discharged downstream of the work area. The amount of discharged water may create sufficient flow during dewatering operations to form continuous flowing channel from the work site to Castaic Creek or the Santa Clara River. The unarmored threespine stickleback is known to occur in the Santa Clara River and may move upstream into Castaic Creek when flows are present.

Because of this new information, the Corps determined that the proposed construction activities and dewatering operations may affect the unarmored threespine stickleback and amended its request for formal consultation to include the species on May 10, 2002. In a telephone conversation with the Corps on May 15, 2002, we requested a 30-day extension on the consultation period in light of this new information, staffing shortages, workload, and high priority projects. The Corps agreed to the extension via telephone on May 15, 2002.

We provided your office a draft of this biological opinion on August 2, 2002. We received your comments by facsimile on August 15, 2002. This final biological opinion incorporates and addresses those comments, where applicable.

BIOLOGICAL OPINION

DESCRIPTION OF THE PROPOSED ACTION

In January 2002, the Corps initiated formal consultation with the Service on the Corps' authorization of the Valencia Company to complete one project of three separate proposed actions. The Corps has authorized, through a general permit under section 404 of the Clean Water Act, three actions by the Valencia Company intended to provide comprehensive flood protection for upland development along Castaic Creek, which are listed below:

1. Discharge of fill into 4.0 acres of an ephemeral streambed to construct an underground stormdrain for a regional mail facility of the U.S. Postal Service. The drainage was filled and the post office was completed in 1991. Because this component of the 404 permit has been completed, it will not be addressed again in this biological opinion.

David J. Castanon (1-8-02-F-43)

3

2. Construction of a flood control channel within Hasley Canyon with concrete sides and an 80-foot-wide earthen bottom. The middle section of Hasley Creek was lined with concrete in 1991 by the Valencia Company. Because this component of the 404 permit has been completed, it will not be addressed again in this biological opinion. The lower portion of Hasley Creek will be completed in 2002 through 2005 and will be addressed in this biological opinion.
3. Installation of bank protection along both sides of Castaic Creek from Highway 5 to Route 126. Two types of bank protection are proposed: (1) soil cement, and (2) gunite or concrete lining. Most of the proposed 19,400 feet of channel lining would be soil cement. This component of the of the 404 permit will be addressed in this biological opinion.

Valencia Company has proposed a form of bank protection method which is being used in the Natural River Management Plan (NRMP) on the Santa Clara River under a separate 404 permit issued in 1998. This bank protection method consists of soil cement including a mixture of situ soils, Portland cement, and water that are compacted to form hardened material. The soil cement is placed in stacks and buried along the banks of a creek or river. Valencia Company anticipates that bank protection installation would be completed from 2002 through 2005. Maps and aerial photographs depicting the location, aerial extent, and various components of the proposed action may be found in the biological evaluation (URS 2002).

The proposed flood protection was to be in addition to approximately 2,000 linear feet of existing ungrouted riprap bank protection located at the north end of the project site and at the Commerce Center Bridge. The Valencia Company proposes to install approximately 19,400 feet of bank protection along Castaic and Hasley creeks over a period of four years. In addition to construction activities, the Valencia Company also proposed methods and criteria for maintenance activities in the project area.

The Valencia Company proposes construction of five temporary road crossings over Castaic and Hasley creeks in order to accomplish the installation of bank protection. Earth-moving equipment would cross the streambed as soils are moved for the project. An elevated crossing fitted with culverts would be installed in order to avoid contact between equipment and surface flows. The creek bed within the roadway corridor would be lined with plastic sheeting to prevent mixing of upland soils with streambed alluvium. The footprint of the roads would be approximately 90 feet wide and 400 feet long. Reinforced concrete pipe or steel culvert would be installed within the existing scour channels to permit any surface flows to continue downstream unimpeded. The top of the roadway would be approximately 75 to 80 feet wide and elevated to 6 to 8 feet above the streambed. K-rail would be installed along the upstream boundary of the roadway to prevent any high flows from eroding the roadway. The roadway would connect to existing dirt access roads on each side of the creek.

David J. Castanon (1-8-02-F-43)

4

Hasley Creek

The Valencia Company proposes to relocate a portion of Hasley Creek to an upland area west of the existing natural channel to best fit development plans for the commerce center (A. Allen, pers. comm. 2002). The Hasley Creek work site parallels Commerce Center Drive and extends in a southern direction. The channel lining would consist of 2,700 feet of double-sided soil cement that would connect to the existing downstream structure that now drains to Castaic Creek. Relocating lower Hasley Creek would eliminate approximately a 2,700 linear foot reach of existing creek bed, approximately 2.10 acres. This area would be filled with soils excavated from the proposed drainage channel. The new lower drainage channel would contain approximately 6.80 acres of alluvial soft-bottom channel and 14 drop basins located approximately 225 feet apart constructed of riprap grouted with cement. The new drainage channel would tie in with the existing alluvial soft-bottom channel lining and the northern abutment of the Commerce Center Bridge.

Bank Protection

The Valencia Company proposes to employ two forms of bank protection over most of the project area: 1) soil cement or riprap for the length of Hasley Creek and Castaic Creek, consisting of a single row of soil cement; and 2) a single row of ungrouted riprap, with concrete tie-ins at structures. The portions of the bank protection above the Castaic Creek which are covered with soil will be revegetated with native plantings and irrigated.

Bank protection installation would occur in a 1.7 mile stretch of Castaic Creek from the Old Road bridge downstream to Route 126 and the downstream portion of Hasley Creek near its confluence with Castaic Creek. In general, for Castaic Creek, the alignment of buried bank protection would follow the existing banks with some encroachment into the creek in certain locations. In other areas the bank stabilization would be installed in upland areas, as described in the letter report from Valencia Company to the Corps (Subbotin, *in litt.* 2002a). Parameters used in designing flood protection for this action are governed by the Capital Flood event as defined by the County of Los Angeles Department of Public Works.

Approximately 19,400 linear feet of bank would be modified through placement of the buried bank protection. Installation of soil cement bank protection requires excavation of a flat-bottom trench to an engineered scour depth for a Capital Flood event. The width of the trench bottom is designed to fit construction equipment. The sides of the trench would slope outward at an approximate 1 to 1 ratio. Once soil cement installation is completed, the trench is then backfilled and graded to match existing creek bed contours at locations where creek bed intrusion has occurred. A 16-foot-wide maintenance road at the outer limit of upland impacts would parallel the open space above the buried bank protection. To install the bank protection, the trenches are excavated below the creek bottom where ground water may be encountered. In this situation, the ground water must be removed during construction. Ground water in the construction area

David J. Castanon (1-8-02-F-43)

5

would be drawn down through a series of shallow dewatering wells strategically placed in close proximity to the excavated trenches. The collected water would be discharged downstream of the work area.

The area to be affected by installation of bank protection consists of 135.0 acres of wetland habitat. In a letter to the Corps, Valencia Company asserts that placement of bank protection in upland areas construes a net gain of 16.4 acres in creek bed acreage resulting in a total wetland habitat area of 151.4 acres; however, the Service disagrees and will only consider the areas of loss in terms of excavation for buried bank protection and placement of ungrouted riprap. The biological function of creek bed created from upland areas is of little value, until a natural hydrologic regime and native vegetation are established.

The Corps has included in its previously authorized 404 permit to Valencia Company several special conditions to reduce potential impacts to the arroyo toad and unarmored threespine stickleback within the project area. These conditions include:

1. Low-growing dry wash vegetation will be allowed to establish naturally within bottom of Hasley Creek to compensate for the loss of dry wash habitat along the unnamed drainage. There will be no clearing of any native riparian vegetation that establishes itself within the creek channel unless it grows excessively dense so as to impede water flow. Any vegetative clearing that is necessary within 100 feet of the confluence with Castaic Creek will be done by hand only.
2. The Valencia Company will record in deed the Castaic Creek corridor as a conservation easement for the purpose of retaining and enhancing fish and wildlife values in perpetuity. Copies of these deed restrictions will be furnished to the Corps, the Service, and the California Department of Fish and Game (CDFG). The amount of area of the conservation easement is approximately 146 acres and will be given to the Center for Natural Land Management (M. Subbotin, pers. comm. 2002b).
3. The Valencia Company will require through project conditions, covenants and restrictions, any industrial user which handles toxic or hazardous substances within the Valencia Commerce Center, to build an on-site self-containment system in accordance with applicable local, state, and federal laws that will prevent these substances from accidentally entering Hasley or Castaic creeks. This measure will minimize the potential of contaminating the unarmored threespine stickleback, arroyo toad, and least Bell's vireo habitats in the event of an accident. The construction and operation of these self-containment systems will be verified by the Corps personnel making inspections of the channel each year for the duration of the construction period.
4. Parking lots in the Valencia Commerce Center will have a drainage system to divert non-storm flows to an oil and grease trap that will separate such contaminants before the runoff is diverted to Hasley or Castaic creeks. These parking lot runoff control systems

David J. Castanon (1-8-02-F-43)

6

will be verified by Corps personnel while making annual inspections of the channels for the duration of the construction period.

5. Maintenance vegetative clearing is permitted only in the upper portion of Hasley Creek, and only for emergency repair work to structures within the channel and bank lining. Under such conditions, clearing of vegetation should be kept to a minimum, and the Valencia Company will perform remedial replacement of damaged vegetation (especially from the construction of access roads if they are necessary) immediately upon completion. A general maintenance plan for the subject project was developed in September 1998 and revised in March 2002 (Aquatic Consulting Services 2002). This plan which was signed by the Los Angeles County Department of Public Works and approved by the Corps and the CDFG.
6. Installation of the channel lining and storm drain system will occur during the period of April 1 to November 1 to avoid winter runoff. Erosion and sediment control measures will be established prior to all construction activities in any water course on the project site. In the event that the contractors are not able to finish the construction in this time window, the permittee will inform the Corps in advance of November 1 in writing, and request permission for a one or two month time extension.
7. Bank protection that allows for growth of native herbaceous vegetation will be used along the sides of Castaic Creek as indicated in Appendix A of the biological evaluation. Final construction plans for any phase of the project must be approved by the Corps in coordination with the Service.
8. The new lining along Castaic Creek will be seeded with native herbaceous vegetation and initially irrigated after installation to encourage the development of low-growing riparian growth.
9. The aerial extent and duration of construction activities along Castaic Creek will be minimized as much as possible. Construction zones for the installation of bank protection and haul routes will be flagged and staked in the field to minimize intrusion and disturbance of existing vegetation. All marshaling and equipment storage areas will be located outside of the channel. The staked boundaries of the impact zone will be verified by the Corps prior to the commencement of construction.
10. The Valencia Company will replace all living and dead willow and cottonwood trees that have a diameter at breast height of 6 inches or more, at a ratio of 1.5 new trees for each tree lost. These trees will not be any smaller than those out of five gallon containers, and preferably a mixture of large sizes. Replacement plants will be placed in augered holes in portions of the Castaic Creek channel that appear to have suitable environmental conditions for such trees to establish naturally.

David J. Castanon (1-8-02-F-43)

7

Prior to construction in Castaic Creek, a formal mitigation plan will be submitted to the Corps for review and approval in coordination with the Service. This plan will include the numbers of different species of trees to be planted, the sizes, and locations of planting. The plan will also describe maintenance of the planted area with regard to irrigation (as needed) and weed eradication. These replacement trees will be monitored for five years following completion of the construction phase of the channel, to ensure their successful establishment.

Survey and re-vegetation plan monitoring documents will be submitted to the Corps and the Service in the form of annual reports in December of each year. These will be reviewed and amended as necessary to ensure success. All failed plantings will be replaced. If the agencies determine that restoration has not been successful, the program will be re-assessed, irrigation introduced if necessary, and restoration efforts will continue on a year-to-year basis until success has been demonstrated.

In the event of significant flood flows which wipe out much of the existing and newly planted vegetation within the five year monitoring and maintenance period, the Valencia Company will initiate a site visit with staff from the Corps and the Service to assess damages and re-evaluate the need for further revegetation efforts in the selected mitigation sites.

11. Emergency repair of the channel lining or bridges across Castaic or Hasley creeks will occur as needed. Any sensitive riparian habitat in the vicinity will be staked in advance to minimize the area of adverse impacts to vegetation. Routine maintenance in the form of vegetative clearing within and along Castaic Creek will not occur in vegetated or mitigation areas. All riparian vegetation disturbed by maintenance and repair will be replaced at a ratio of 1 to 1.
12. Excavation of mounds of tailings from past sand and gravel mining operations within the creek may occur, but any trees and shrubs removed in the process that are greater than 6 inches at breast height will be replaced on site at a 1.5 to 1 ratio.
13. A weed eradication and control program will be established as part of the restoration efforts and implemented on a regular basis during the five year restoration period. During monitoring efforts, a crew will examine all disturbed portions, as a result of this project, within Castaic Creek and remove stands of *Arundo donax*, *Tamarisk*, castor bean, and tree tobacco by hand and topical application of approved herbicides.
14. Landscaping along the top of the bank protection will use native drought tolerant plants.

In a letter to the Corps dated May 10, 2002, the Valencia Company proposed several additional measures to reduce the potential impacts to the unarmored threespine stickleback from this project. These measures include:

David J. Castanon (1-8-02-F-43)

8

1. Service-approved biologists will place fish blocking nets across the dewatering discharge at its confluence with non-project flows (flood flows or dam releases) in Castaic Creek or the Santa Clara River in such a manner as to prevent the movement of unarmored threespine stickleback up the channel of flowing water from dewatering operations. During a telephone conversation on July 11, 2002, between Chris Dellith of my staff and Aaron Allen of the Corps, we agreed that Service personnel as stated by Valencia Company, would be changed to Service-approved biologists. A plan to place the blocking nets will be provided to the Service for approval 30 days prior to implementation. In the event that the net fails, the Service will be immediately notified and will conduct a site inspection with the Valencia Companies qualified biologist to determine if fish have moved up the dewatering channel, and methods for rescue or ramping down the discharge to allow fish to escape.
2. Prior to initiating construction of bank stabilization or temporary road crossings, all construction sites and access roads within the river bed, as well as all creek bed areas within 300 feet of the construction site and access road, will be inspected by a Service-approved biologist for the presence of the unarmored threespine stickleback, arroyo chub, Santa Ana sucker, arroyo toad, two-striped garter snake, and southwestern pond turtle. The Corps and the CDFG will be notified of the inspection and will have the option of attending. If either agency is not represented, the biologist will file a written report of the inspection with the agency not in attendance within 15 days of the survey and no sooner than 30 days prior to any construction work in the creek bed.
3. Construction work areas and access roads will be cleared of the species listed in (2) above immediately before the prescribed work is to be carried out, immediately before any equipment is moved into or through the stream or habitat areas, and immediately before diverting any stream water. The removal of such species will be conducted by a Service-approved biologist using procedures approved by the Corps and the Service. Species will be relocated to nearby suitable habitat areas. A plan to relocate these species will be submitted to the Corps and the Service for review and approval no later than 30 days prior to construction. Under no circumstances will the arroyo toads or unarmored threespine stickleback be collected or relocated, unless Service-approved biologists implement this measure.
4. All stream flows traversing a construction site or temporary road crossing will be diverted around the site and under access roads using a temporary culvert or crossings that allow fish passage. A temporary diversion channel will be constructed using the least damaging method possible, such as blading a narrow pilot channel through open sandy creek bottom. The removal of wetland and riparian vegetation to construct the channel will be avoided to the greatest extent feasible. The temporary channel will be connected to a natural channel downstream of the construction site prior to diverting the stream. The integrity of the channel and diversion will be maintained throughout the construction period. The original stream channel alignment will be restored after construction,

David J. Castanon (1-8-02-F-43)

9

provided suitable conditions are present at the work site after construction. A temporary stream diversion plan will be submitted to the Corps and the Service for individual project approvals.

5. A Service-approved biologist will be present when any stream diversion takes place, and will patrol the areas both within, upstream, and downstream of the work area to rescue any species stranded by the diversion of the stream water. Species that are collected will be relocated to suitable areas downstream of the work area.

STATUS OF THE SPECIES

Arroyo Toad

The Service listed the arroyo toad as endangered on December 16, 1994 (59 *Federal Register* 63264). A recovery plan for the species has been published (Service 1999). Critical habitat for the arroyo toad was designated on February 7, 2001 (66 *Federal Register* 9414). On October 30, 2002, the United States District Court for the District of Columbia set aside the designation and ordered the Service to publish a new final rule with respect to the designation of critical habitat for the arroyo toad by July 30, 2004 (*Building Industry Legal Defense Foundation, et al., v. Gale Norton, Secretary of the Interior, et al., and Center for Biological Diversity, Inc. and Defenders of Wildlife, Inc.* Civil Action No. 01-2311 (JDB) (U.S. District Court, District of Columbia)).

The arroyo toad is a small, dark-spotted toad of the family Bufonidae. The parotid glands, located on the top of the head, are oval-shaped and widely separated. A light or pale area or stripe is usually present on these glands and on top of the eyes. The arroyo toad's underside is buff-colored and usually without spots (Stebbins 1985). Recently metamorphosed individuals typically blend in with stream side substrates.

Optimal breeding habitat consists of low-gradient sections of slow-moving streams with shallow pools, nearby sandbars, and adjacent stream terraces. Arroyo toads breed and deposit egg masses in the shallow, sandy pools of these streams, which are usually bordered by sand-gravel flood-terraces. Stream order, elevation, and flood plain width appear to be important factors in determining habitat capability (Sweet 1992, Barto 1999, Griffin 1999). High stream order (*i.e.*, 3rd to 6th order), low elevation (particularly below 3,000 feet), and wide flood plains seem to be positively correlated with arroyo toad population size. However, small arroyo toad populations are found along 1st and 2nd order streams at elevations up to 4,600 feet.

Outside of the breeding season, arroyo toads are essentially terrestrial and are known to use a variety of upland habitats including, but not limited to, sycamore-cottonwood woodlands, oak woodlands, coastal sage scrub, chaparral, and grassland (Holland 1995, Griffin *et al.* 1999).

Arroyo toad tadpoles feed on loose organic material such as interstitial algae, bacteria, and diatoms. They do not forage on macroscopic vegetation (Sweet 1992, Jennings and Hayes 1994).

David J. Castanon (1-8-02-F-43)

10

Juvenile arroyo toads feed on ants almost exclusively (Service 1999). By the time they reach 0.7 to 0.9 inch in length, they consume more beetles, along with the ants (Sweet 1992, Service 1999). Adult arroyo toads probably consume a wide variety of insects and arthropods including ants, beetles, spiders, larvae, caterpillars, and others.

Breeding typically occurs from February to July on streams with persistent water (Griffin *et al.* 1999). Female arroyo toads must feed for a minimum of approximately two months to develop the fat reserves needed to produce a clutch of eggs. Eggs are deposited and larvae develop in shallow pools with minimal current and little or no emergent vegetation. The substrate in these pools is generally sand or fine gravel overlain with silt. The eggs hatch in 4 to 5 days and the tadpoles are essentially immobile for an additional 5 to 6 days. They then begin to disperse from the pool margin into the surrounding shallow water, where they spend an average of 10 weeks. After metamorphosis (June and July), the juvenile arroyo toads remain on the bordering gravel bars until the pool dries out (usually from 8 to 12 weeks depending on the site and rainfall). Most individuals become sexually mature by the following spring (Sweet 1992).

Individuals of this species have been observed moving approximately 1 mile within a stream reach and 0.6 mile away from the stream, into native upland habitats (Sweet 1992, Holland 1995) or agricultural areas (Griffin *et al.* 1999). Movement distances may be regulated by topography and channel morphology. Griffin (1999) reported a female arroyo toad traveling more than 948 feet perpendicular from a stream and Holland (1998) found arroyo toads 0.7 mile from a water course. At Little Rock Creek, on the desert slopes of the San Gabriel Mountains, arroyo toads were found up to approximately 120 feet from the active channel; they burrowed closer to the active stream channel as the time after the last spring rain increased (Ramirez 2000). Arroyo toads are critically dependent on upland terraces and the marginal zones between stream channels and upland terraces during the non-breeding season, especially during periods of inactivity, generally late fall and winter (Sweet 1992).

Arroyo toads have disappeared from approximately 75 percent of the previously occupied habitat in California. They were known historically to occur in coastal drainages in southern California from San Luis Obispo County to San Diego County and in Baja California, Mexico. In Orange and San Diego counties, the species occurred from estuaries to the headwaters of many drainages. In 1996, arroyo toads were discovered on Fort Hunter Liggett, Monterey County. This discovery constituted a northern range expansion for the species. Populations of this species also occur on the desert slopes of both the San Gabriel Mountains (in Little Rock Creek in Los Angeles County) and the San Bernardino Mountains (in the Mojave River and in its tributaries, Little Horsethief and Deep creeks, in San Bernardino County). Arroyo toads now survive primarily in the headwaters of coastal streams as small isolated populations, having been extirpated from much of their historic habitat.

Flood control projects, agriculture, off-highway vehicle use, urbanization, and campgrounds reduced many arroyo toad populations in size or caused their extirpation due to extensive habitat loss from 1920 to 1980 (Service 1999). The loss of habitat, coupled with habitat modifications

David J. Castanon (1-8-02-F-43)

11

due to the manipulation of water levels in many central and southern California streams and rivers, and predation from introduced aquatic species, caused arroyo toads to disappear from a large portion of their previously occupied habitat in California (Jennings and Hayes 1994). Currently, the major threats to arroyo toad populations are from stream alteration, introduction of exotic species, urban and rural development, mining, recreation, grazing, drought, wildfire, and large flood events.

The recovery plan for the arroyo toad divides its range into the northern, southern, and desert recovery units (Service 1999). The recovery plan recommends that the arroyo toad be reclassified as a threatened species when management plans have been developed and implemented to secure the genetic and phenotypic variation of the species in each recovery unit; this goal would be accomplished by conserving the necessary riparian and upland habitats on federally managed lands. Delisting would be pursued when 15 additional self-sustaining populations of arroyo toads are known to exist, including those that occur on lands that are not managed by Federal agencies.

Unarmored threespine stickleback

Unarmored threespine sticklebacks are small fish (up to 2.36 inches) inhabiting slow moving reaches or quiet water microhabitats of streams and rivers. Favorable habitats usually are shaded by dense and abundant vegetation but in more open reaches algal mats or barriers may provide refuge for the species. Unarmored threespine sticklebacks feed primarily on benthic insects, small crustaceans, and snails, and to a lesser degree, on flat worms, nematodes, and terrestrial insects. Unarmored threespine sticklebacks reproduce throughout the year with a minimum of breeding activity occurring from October to January. Reproduction occurs in areas with adequate aquatic vegetation and gentle flow of water where males establish and vigorously defend territories. The male builds a nest of fine plant debris and algal strands and courts all females that enter his territory; a single nest may contain the eggs of several females. Following spawning, the male defends the nest and, after approximately six days, the newly hatched fry. Unarmored threespine sticklebacks are believed to live for only one year (Service 1985).

Unarmored threespine sticklebacks historically were distributed throughout southern California but are now restricted to the upper Santa Clara River and its tributaries in Los Angeles and Ventura counties, Cañada Honda and San Antonio creeks on Vandenberg Air Force Base, Shay Creek (tributary to Baldwin Lake) in San Bernardino County, and San Felipe Creek in San Diego County. The population in Cañada Honda Creek is a transplanted population, as is the small population that may persist in San Felipe Creek.

The unarmored threespine stickleback was listed as endangered in 1970 (35 *Federal Register* 16047) primarily due to competition with or predation by non-native fish, loss of habitat through urbanization and channelization, and introgression with other subspecies of sticklebacks. Critical habitat for the unarmored threespine stickleback was proposed in 1980 for two reaches of the Santa Clara River, and single reaches of both San Francisquito Creek and San Antonio Creek;

David J. Castanon (1-8-02-F-43)

12

designation of critical habitat remains pending (45 *Federal Register* 76012). The recovery plan for the unarmored threespine stickleback (Service 1985) provides additional information on the biology of the species, reasons for its decline, areas of essential habitat, and the actions needed for recovery of the species. The unarmored threespine stickleback is a fully protected species under California law. See California Fish and Game Code, Section 5515 (b)(9).

ENVIRONMENTAL BASELINE

The implementing regulations for section 7(a)(2) define the action area of a consultation as the area that may be directly or indirectly affected by the proposed action (50 Code of Federal Regulations 402.02). Given the topography of the area, the alterations of the flood plain caused by previous human activities, the ecology of the arroyo toad and unarmored threespine stickleback, and the potential effects of the proposed action, we are considering the action area for this biological opinion to generally be the area of the flood plain, creek bed including the stream channel, and the reach of Castaic Creek from Interstate 5 downstream to its confluence with the Santa Clara River. The unarmored threespine stickleback can periodically occur in Castaic Creek during winter storm events and releases from Castaic Lake. Additionally, unarmored threespine stickleback are known to occur downstream of the project site at the confluence with the Santa Clara River. These areas will be directly and indirectly affected by construction and installation of the bank protection.

In average rainfall years, parts of Castaic Creek are dry by mid-summer and remain dry until winter rains recharge the alluvium. Flows in the project area are influenced by the water releases from Castaic Lake approximately three miles upstream of the project area. When water is released from Castaic Lake, the project area supports a single and sometimes two small channels that range from shallow and open to relatively deep and heavily shaded. The main plant communities in the project area are cottonwood-willow riparian scrub, cottonwood forest and chaparral. Riparian vegetation at the project site is dominated by willows (*Salix* spp.), mulefat (*Baccharis salicifolia*) and Fremont cottonwood (*Populus fremontii*). Giant reed and tamarisk are also found in the riparian area at the project site, but are not the dominant species. Willow riparian scrub is found along the banks and bottom of the creek channel and is often subjected to scour during winter storm events. In areas where the active channel is wide, riparian vegetation is sparse or absent and areas of sand, gravel, and cobble are present. Nearly all of the uplands outside the stream banks are either developed or are heavily disturbed through agricultural or pre-grading activities.

Interstate 5 is immediately upstream of the Castaic Creek project site and the surrounding area is rapidly urbanizing. The area immediately surrounding the project site is moderately industrialized with some residential housing tracts and agricultural land.

Hasley Creek runs parallel with the east side of Commerce Center Drive. The Hasley Creek portion of the project begins approximately 900 feet south of where Commerce Center Drive crosses the previously lined Hasley Creek and continues to its confluence with Castaic Creek.

David J. Castanon (1-8-02-F-43)

13

Vegetation occurring within the lower Hasley Creek project site consists of mulefat scrub and non-native grassland. Mulefat scrub and dry open floodplain is found within the drainage itself. The non-native grassland is found on the upland field next to the drainage. One coast live oak (*Quercus agrifolia*) and one cottonwood (*Populus fremontii*) exist within the proposed lower Hasley Creek project site. Hasley Creek has an approximately 20 year old Arizona-type crossing fitted with 12 inch and 16 inch PVC pipelines. The Arizona type crossing is located approximately 600 feet north of the confluence with Castaic Creek.

Arroyo toad

Surveys for the arroyo toad according to Service protocols were conducted from April to June 2001 along the project reach. No arroyo toads, tadpoles, or egg masses were observed in the project reach during the field surveys. However, suitable habitat does exist within the project reach, as well as, suitable habitat located downstream of the highway 126 overpass within Castaic Creek. The downstream suitable habitat has been surveyed for arroyo toads as part of the NRMP which also resulted in no arroyo toads, tadpoles, or egg mass observations (Impact Sciences 2001b). The presence of the arroyo toad has been documented in the Santa Clara River in locations from Castaic Junction upstream to the bridge at Bouquet Canyon (Courtois 2000; Sandburg 2001a and 2001b). Six arroyo toad tadpoles were reported within the NRMP area of the River between the I-5 bridge and Castaic Junction in 2000 (Courtois 2000). Upon further investigation, we found a report in the California Natural Diversity Data Base from 1994 of one individual arroyo toad captured and released upstream of the I-5 bridge over the River. The possibility exists that arroyo toads occurring within the Santa Clara River could colonize the project area via the downstream portion of Castaic Creek. As a result of this possibility, arroyo toads maybe killed or injured by the project activities and are therefore included as a covered species in this biological opinion. Suitable habitat does not exist for the arroyo toad within the Hasley Creek portion of the project area and therefore, those effects will not be addressed in this biological opinion.

Arroyo toads have been recorded at the following locations within the project vicinity; both above and immediately below the Castaic Lake Reservoir on Angeles National Forest and Los Angeles Department of Water and Power land within Castaic Creek; on upper San Francisquito Creek; and within the Santa Clara River adjacent to the Castaic Junction site. We consider the project area to be essential as a dispersal corridor for arroyo toads between upper Castaic Creek and the Santa Clara River.

Unarmored threespine stickleback

Surface flow in Castaic Creek is dependent on water releases from Castaic Lake. Because of the lack of surface flow and intermittent release of water from Castaic Lake, no surveys for unarmored threespine stickleback were conducted. However, unarmored threespine stickleback are known to occur downstream at the confluence with the Santa Clara River and have been observed in Castaic Creek as a result of dewatering operations for construction of the Commerce Center Drive Bridge (C. Dellith, Service, pers. obs.1999).

David J. Castanon (1-8-02-F-43)

14

EFFECTS OF THE ACTION

Arroyo toads

Arroyo toads could be killed or injured, either on the ground surface or in their burrows, by vehicles associated with bank protection installation, repair, and maintenance. Trench excavation and placement of fill for temporary access roads could injure or kill arroyo toads by crushing them at the surface or within their burrows. Foot traffic by workers associated with the construction activities, biological surveys, and restoration activities could kill or injure arroyo toads. Revegetation activities involving the use of augers to dig holes for plantings could kill arroyo toads within burrows. Excavation of mounds of tailings from past sand and gravel mining operations may also kill or injure arroyo toads located in burrows. The potential for arroyo toads to be killed or injured during these activities would be greatest within riparian habitats when workers are concentrated in those areas, or at night along roads and sandy areas when arroyo toads are either actively foraging or moving to or away from Castaic Creek.

Construction activities, such as removal of riparian vegetation and movement of construction equipment in the riparian zone, could affect arroyo toads and their habitat. The project will result in a permanent loss of approximately 12.2 acres of riparian habitat. The permanent habitat loss is from construction and related activities. Approximately 8.3 acres of riparian habitat will be temporarily affected by the project activities. Loss of riparian habitat would diminish available burrowing and foraging habitat for arroyo toads.

Project-related dust, noise, and activity near habitat occupied by arroyo toads could disturb individuals to the extent that foraging and burrowing behavior could be altered. If construction activities are scheduled to occur during nighttime hours, more arroyo toads are likely to be affected due to the nocturnal behavior of this species. Although the site is not expected to be fully restored for several years following construction activities, restoration of the site and removal of invasive, exotic vegetation, as proposed by Valencia Company, would help minimize the long-term effects of the project on the arroyo toad as related to habitat degradation.

When heavy equipment is used in proximity to aquatic habitats, the potential exists that these sensitive areas may be destroyed or degraded. The direct placement of material or runoff of sediments generated by the project into aquatic habitats can result in the loss of habitat values through filling or in the degradation of water quality. Arroyo toads are likely to be particularly sensitive to both direct filling of streams and sedimentation; the shallow pools this species requires for breeding can be destroyed by the addition of relatively small amounts of material, either by direct filling or by the alteration of the sandy and gravelly substrata that the arroyo toad requires. Arroyo toads may also be particularly vulnerable to the release of toxic materials because they generally use aquatic habitats with low flows; under such environmental conditions, toxins may be more concentrated and lethal. Additionally, the slow flows associated with breeding pools may increase the likelihood that fine sediments carried into the pools would remain there smothering eggs and tadpoles. Measures proposed by the Valencia Company to

David J. Castanon (1-8-02-F-43)

15

reduce sedimentation effects include Best Management Practices such as those described in the NRMP (Corps and CDFG 1998). Permanent effects would include loss of riparian habitat due to bank protection placement and soil compaction on the bank protection structure itself.

Runoff from areas where concrete is being used could cause increases in water pH. Substantial increases would kill all life stages of the arroyo toad for some distance downstream of the release; a release of such materials resulted in mortalities of California red-legged frogs and arroyo toads in Mono Creek in the Los Padres National Forest in the early 1990s. The rate of water flow and amount of released material would affect the distance over which the pH would be altered. Because such effects could extend far beyond the actual work area, the number of arroyo toads that may be killed could be substantial. Equipment storage, fueling, and staging areas would be located on upland sites a minimum of 100 feet away from the nearest surface flow; this measure would reduce the potential for arroyo toad mortality and reduce the likelihood that toxic materials would inadvertently reach aquatic habitat.

Employees of Valencia Company and other personnel associated with the project could travel outside of areas where work is occurring; such activities, particularly with vehicles, could kill or injure arroyo toads and damage their habitat. Flagging of the construction areas may help reduce intrusions. Careless workers could release toxic materials, leave garbage that would attract predators of the arroyo toad, or conduct activities outside of designated areas. Valencia Company has proposed to limit construction activities in the creek bed, and define and mark the limits of project disturbance. These measures should be effective in reducing direct mortality or injury of arroyo toads during bank protection installation.

Creek surface flows in the construction area would not be impeded; water flows would be diverted or placed into culverts in the construction area. Because surface flow diversion equipment or culverts are set in place after all arroyo toads have metamorphosed, the likelihood of arroyo toad eggs mass destruction or tadpole deaths would be reduced.

Biologists working in different areas and with different species may transmit diseases. In some cases, these introduced diseases have had catastrophic effects on amphibian populations. Some evidence exists that other environmental stresses, such as the chytrid fungus introduction into San Francisquito Creek, may exacerbate the effects of diseases on amphibians (Rick Farris, Service, pers. comm. 2002).

Arroyo toads in various life stages could be affected by trampling while the site is being accessed, or by installation of fencing material. Impacts to arroyo toad egg masses and tadpoles would be most severe if fencing were installed through breeding pools. The Corps and Valencia Company propose to survey the construction area, including breeding pools, and monitor construction activities in order to avoid arroyo toad egg masses and tadpoles to help reduce the likelihood of arroyo toad deaths.

David J. Castanon (1-8-02-F-43)

16

Following the construction of bank protection, the affected reach of the creek will lack streamside vegetation. This may allow invasive, exotic vegetation to establish and become dominant in the project area, reducing habitat for the arroyo toad. To prevent the spread of exotic vegetation in the project site, the Valencia Company will remove exotic vegetation from the project area during grubbing operations, and monitor and control infestations of exotic vegetation infestation in the project area during the planned restoration and re-vegetation of the riparian habitat.

Summary

In general we expect the number of arroyo toads, tadpoles, or eggs killed or injured to be low. Mortality or injury could vary, depending on weather conditions and the amount of surface flow in Castaic Creek. If more water is present which could provide better habitat for arroyo toads, then the likelihood of effects to arroyo toads could increase. During and after years when rainfall is favorable for breeding, additional arroyo toads may move into the project area.

Ground-disturbing activities, revegetation activities, mound tailings excavation, the removal of exotic vegetation, and surveys or monitoring may cause injury and mortality of arroyo toads. We expect the project will temporarily affect 8.3 acres of arroyo toad habitat and permanently affect 12.2 acres of arroyo toad habitat. Overall, because no arroyo toads have been observed in the project area, we expect that few arroyo toads are likely to be killed or injured by project activities.

Unarmored threespine stickleback

Valencia Company indicates that, depending on the amount of precipitation from the previous winter storm season and the associated elevation of the groundwater in the project area, construction of soil cement bank protection could require substantial dewatering activities. With ongoing and substantial dewatering activities, the discharged nuisance water could connect with the Santa Clara River, allowing unarmored threespine stickleback to migrate upstream into Castaic Creek. In the event that blocking nets as proposed by Valencia Company fail and individual unarmored threespine sticklebacks move into the project area, the proposed construction activities could affect the species.

If blocking nets fail, individual unarmored threespine sticklebacks that enter the project area may be injured or crushed by excavation and construction equipment, construction debris or worker foot traffic during construction activities. The noise and ground vibrations from the operation of heavy equipment during construction activities may disturb unarmored threespine sticklebacks and cause individuals to disperse and possibly be driven into areas where they would be more susceptible to injury or mortality due to predation, vehicular or foot traffic, or falling debris. The dewatering and diversion of water from the project area could result in the direct mortality of unarmored threespine sticklebacks from dessication or crushing. The use of blocking nets, as proposed by the Valencia Company, would lessen the chance for unarmored threespine sticklebacks to enter the project area.

David J. Castanon (1-8-02-F-43)

17

Furthermore, with the termination of the above dewatering activities, unarmored threespine stickleback could become stranded in Castaic Creek as the flow recedes. Percolation rates in Castaic Creek may exceed flow rates stranding unarmored threespine sticklebacks in receding pools and channels once dewatering activities have been terminated. Valencia Company proposes to gradually step-down water discharges once dewatering is no longer needed and monitor for any unarmored threespine stickleback. Service-approved biologists will capture stranded unarmored threespine stickleback and relocate them to a predetermined downstream site.

Disturbance of unarmored threespine sticklebacks would occur while capturing and transporting individuals to suitable habitat. Individuals may also be injured or killed in a seine net should it be used improperly, such as if fish remained trapped in the net or out of water for too long. Mortality following translocation may occur given the uncertainty of the survival of unarmored threespine sticklebacks in unfamiliar sites or from injuries and stress related handling and transportation. These effects would be reduced by the following actions that Valencia Company proposes: clearly marking the boundaries of the work areas, removing unarmored threespine sticklebacks from project areas to suitable habitat out of harm's way immediately prior to any construction activities, rescuing any stranded individuals, and by employing only experienced biologists to capture and handle the species.

Project-related material releases onto channel substrate or into water would result in effects to water quality that may be hazardous to unarmored threespine sticklebacks. Debris falling into the river may also degrade water quality. As proposed by the Valencia Company, the implementation of measures to control pollution, such as refueling at designated areas and containment of spilled substances, would reduce these effects.

Employees of the Valencia Company and other personnel associated with the project could travel outside of areas where work is occurring; such activities, particularly with vehicles, could kill or injure unarmored threespine stickleback. Careless workers could release toxic materials, leave garbage and food-related items that would attract predators of the unarmored threespine stickleback, or conduct construction related activities outside of designated areas. Flagging of the construction areas may help reduce intrusions.

To reduce the likelihood that all of the preceding impacts would occur, the Corps and Valencia Company have proposed to educate workers regarding the presence of the arroyo toad and unarmored threespine stickleback and the importance of keeping work sites clear of trash and remaining within authorized work areas (A. Allen, pers. comm. 2002). Such education programs, when used during other projects that could affect listed species, have been effective in preventing loss and degradation of habitat and loss of individuals.

Summary

Under normal conditions, as determined by controlled water releases from Castaic Lake Reservoir, unarmored threespine stickleback would not occur in Castaic Creek. However, sufficient surface flows from dewatering of the project site could connect at the confluence with

David J. Castanon (1-8-02-F-43)

18

the Santa Clara River allowing unarmored threespine stickleback to swim upstream into the project site. Termination of dewatering operations and stream diversion activities may leave unarmored threespine stickleback stranded in receding stream water and could likely result in mortality or injury of some individuals.

Repeated capturing of unarmored threespine sticklebacks would likely result in mortality or injury of at least some individuals. Even under the worst case scenario, that is, the mortality of a few unarmored threespine sticklebacks from construction activities or seining and handling, the overall population status of the species in the watershed would not be substantially altered by the proposed action.

CUMULATIVE EFFECTS

Cumulative effects include the effects of future State, tribal, local, or private actions that are reasonably certain to occur in the action area considered in this biological opinion. Future Federal actions that are unrelated to the proposed action are not considered in this section because they require separate consultation pursuant to section 7 of the Act.

The habitat and home range of arroyo toads vary in accordance with water flows and individuals may be found throughout the uplands within Castaic Creek. Consequently, the construction of the industrial complexes could effect the population of arroyo toads that could possibly occur in the Commerce Center project area. Upland areas immediately adjacent to the project site will be developed into industrial and commercial uses. The development will include light industrial, manufacturing, research and development, warehouses and distributors. The loss of upland habitat could reduce area needed by arroyo toads for foraging and dispersal.

CONCLUSION

After reviewing the current status of the arroyo toad and unarmored threespine stickleback, the environmental baseline for the action area, the effects of the proposed action, and the cumulative effects, it is our biological opinion that the Castaic Creek bank stabilization project, as proposed, is not likely to jeopardize the continued existence of either of these species. We have reached this conclusion for the following reasons:

1. The number of arroyo toads and unarmored threespine stickleback that could be affected by the Castaic Creek bank stabilization projects is small in relation to the overall distribution of the species. Surveys of the area did not detect arroyo toads or unarmored threespine stickleback within the project site and we do not believe those that could be affected would constitute a substantial portion of the entire species' population to where it would interfere with the species' survival and recovery.
2. The applicant has proposed measures to minimize and avoid some of the adverse effects to the species, including monitoring the project area for arroyo toads or unarmored

David J. Castanon (1-8-02-F-43)

19

threespine sticklebacks by Service-approved biologists; providing procedures for relocating listed species out of harm's way, and restoration of temporary disturbance areas.

3. The applicant has proposed measures to restore disturbed habitats.
4. Blocking nets installed by the applicant should prevent unarmored threespine stickleback from entering project related flows that may contact non-project flows in Castaic Creek or the Santa Clara River. Therefore, the number of individual unarmored threespine sticklebacks expected to be affected is small.

The Incidental Take Statement accompanying this Biological Opinion exempts from the take prohibitions of the Act, take of the unarmored threespine stickleback and arroyo toad carried out in accordance with the terms and conditions of the Incidental Take Statement. It does not address the restrictions or requirements of other applicable laws.

INCIDENTAL TAKE STATEMENT

Section 9 of the Act and Federal regulation pursuant to section 4(d) of the Act prohibit the take of endangered and threatened species, respectively, without special exemption. Take is defined as to harass, harm, pursue, hunt, shoot, wound, kill, trap, capture or collect, or to attempt to engage in any such conduct. Harm is further defined by the Service to include significant habitat modification or degradation that results in death or injury to listed species by significantly impairing essential behavioral patterns, including breeding, feeding, or sheltering. Harass is defined by the Service as intentional or negligent actions that create the likelihood of injury to listed species by annoying it to such an extent as to significantly disrupt normal behavior patterns which include, but are not limited to, breeding, feeding or sheltering. Incidental take is defined as take that is incidental to, and not the purpose of, the carrying out of an otherwise lawful activity. Under the terms of section 7(b)(4) and section 7(o)(2), taking that is incidental to and not intended as part of the agency action is not considered to be prohibited taking under the Act provided that such taking is in compliance with the terms and conditions of this incidental take statement.

The measures described below are non-discretionary, and must be undertaken by the Corps so that they become binding conditions of any grant or permit issued to the Valencia Company, as appropriate, for the exemption in section 7(o)(2) to apply. The Corps has a continuing duty to regulate the activity covered by this incidental take statement. If the Corps (1) fails to assume and implement the terms and conditions or (2) fails to require the Valencia Company to adhere to the terms and conditions of the incidental take statement through enforceable terms that are added to the permit or grant document, the protective coverage of section 7(o)(2) may lapse. To monitor the effect of incidental take, the Corps and Valencia Company must report to the Service the progress of the action and its effect on the species as specified in the incidental take statement. [50 CFR §402.14(i)(3)]

David J. Castanon (1-8-02-F-43)

20

Arroyo toad

The Service anticipates incidental take of the arroyo toad will be difficult to detect for the following reasons: (1) the numbers of individuals that could be present is unclear; (2) the arroyo toad is generally difficult to detect due to its cryptic coloration and small body size; (3) finding a dead or impaired specimen is unlikely; and (4) losses may be masked by seasonal fluctuations in numbers or other causes (*e.g.*, low rainfall years, changes in hydrology unrelated to the projects). However, the following level of take of this species can be anticipated by loss of habitat, temporary construction effects, cumulative effects, changes in hydrology and water quality, and indirect effects:

If arroyo toads have colonized the project area and are present during project activities then all arroyo toads found in the project areas may be subject to take in the form of capture during relocation efforts. An indeterminate number of arroyo toads may be directly killed or injured by construction activities (*e.g.*, placement of bank stabilization materials, heavy equipment movement in the streambed, etc.) along Castaic Creek. Based on the nature of the proposed activities and the protective measures proposed by the applicant, and the likely low abundance of individuals of the species, we anticipate that few arroyo toads will be killed or injured.

If more than one (1) adult, juvenile (metamorph), or larval arroyo toad is killed or injured or if any egg masses are disturbed during implementation of the project along Castaic Creek, regardless of cause, the Corps shall contact our office immediately so we can review the project activities to determine if additional protective measures are needed. Project activities may continue during this review period, provided that all protective measures proposed by the Corps and the terms and conditions of this biological opinion have been and continue to be implemented. No take of arroyo toads is anticipated in Hasley Canyon, as no arroyo toads are expected to be present based upon the lack of suitable habitat.

Unarmored threespine stickleback

No take of unarmored threespine stickleback would occur if the minimization measures proposed by the Corps and Valencia Company are effective. However, if unarmored threespine stickleback are able to breach blocking nets and access the project area, then some level of take is anticipated. Also, if unarmored threespine sticklebacks have entered the project area and are present during dewatering activities then all unarmored threespine sticklebacks found in the project produced flows may be subject to take in the form of capture during relocation efforts. The actual number of unarmored threespine sticklebacks that may be taken cannot be accurately predicted because of their small size and varying abundance in a given location. Because we are unable to anticipate with a great deal of certainty the number that may be killed or injured, the Corps shall contact the Service if more than one (1) unarmored threespine stickleback is killed or injured; the cause of death or injury shall be determined by the authorized biologist. Provided

David J. Castanon (1-8-02-F-43)

21

that the protective measures proposed by the Corps and the terms and conditions of this biological opinion are being fully implemented, construction activities need not cease while the cause of death is being determined. Once the cause of death or injury has been determined, the Service and Corps shall decide whether any additional protective measures are required to address the cause of the loss of the unarmored threespine stickleback.

Take of arroyo toads and unarmored threespine sticklebacks are only exempted within the areas considered to be the action area as defined in the project description section of this biological opinion.

REASONABLE AND PRUDENT MEASURES

The Service believes the following reasonable and prudent measures are necessary and appropriate to minimize take of the arroyo toad and unarmored threespine stickleback:

1. Only Service-approved personnel may handle arroyo toads and unarmored threespine stickleback and only in an appropriate manner and for the minimum time necessary.
2. The Corps shall require that all activities that include diversion or dewatering, including restoration of flows after construction, shall be monitored by an approved biologist to locate and transfer to a safe area any arroyo toads, as well as unarmored threespine stickleback imperiled by the action.
3. The Corps shall require Valencia Company to confine all work to defined areas through barriers and education of workers. The education program shall include information on all relevant aspects of the measures intended to protect the arroyo toad and unarmored threespine stickleback.
4. The Corps shall ensure plans relating to the inadvertent release of hazardous materials are in place prior to the onset of ground-disturbing activities.
5. The Corps shall ensure that protective measures for the arroyo toad and unarmored threespine stickleback are consistently implemented.

TERMS AND CONDITIONS

To be exempt from the prohibitions of section 9 of the Act, the Corps must ensure that Valencia Company complies with the following terms and conditions, which implement the reasonable and prudent measures described above and outline reporting and monitoring requirements. These terms and conditions are non-discretionary.

David J. Castanon (1-8-02-F-43)

22

1. The following terms and conditions implement reasonable and prudent measure 1:
 - a. Only qualified personnel authorized under the auspices of this biological opinion shall handle arroyo toads and unarmored threespine stickleback. The Corps or Valencia Company shall submit the credentials of biologists who they wish to handle arroyo toads and unarmored threespine stickleback to the Service, for its review and written approval, at least 15 days prior to the onset of the activities which they may be authorized to conduct.
 - b. When capturing and removing arroyo toads and unarmored threespine stickleback from work sites, the Service-approved biologist shall minimize the amount of time that animals are held in captivity. During this time, they shall be maintained in a manner that does not expose them to temperatures or any other environmental conditions that could cause injury or undue stress.
 - c. To avoid transferring disease or pathogens between aquatic habitats during the course of surveys and handling of arroyo toads, the Service-approved biologist shall follow the Declining Amphibian Population Task Force's Code of Practice. A copy of this Code of Practice is enclosed. You may substitute a bleach solution (0.5 to 1.0 cup of bleach to 1.0 gallon of water) for the ethanol solution. Care shall be taken so that all traces of the disinfectant are removed before entering the next aquatic habitat.
 - d. With the exception of monitoring geared directly for arroyo toads, biological, hydrological, and other monitoring shall not be conducted within or adjacent to arroyo toad breeding pools or in areas where metamorph arroyo toads are abundant. The determination of abundance of metamorphs shall be made by the Service-approved biologist. The primary criterion to be used in determining if work in a given area must be delayed is whether the monitoring activities are likely to result in mortality of one metamorph. If the Service-approved biologist makes this determination and mortality cannot be avoided through the implementation of site- and instance-specific measures, the monitoring activity shall be delayed until such time when metamorphs are no longer abundant; alternatively, the monitoring shall be moved to another site. When in doubt regarding (1) whether metamorphs should be considered abundant; or, (2) whether the site- and instance-specific protective measures will protect metamorphs, the Service-approved biologist shall contact the Ventura Fish and Wildlife Office and Corps for guidance. Telephone contact may be used to expedite resolution of the issue.
 - e. Arroyo toads and unarmored threespine stickleback shall be removed from the project area within and around all areas where construction or related activities occur. The procedures proposed by Valencia Company, as modified by these

David J. Castanon (1-8-02-F-43)

23

terms and conditions, shall be implemented during the installation of channel lining. The breeding pools within project area shall be inspected during the arroyo toad breeding season for egg masses. If egg masses are found, then pools shall be flagged for avoidance until metamorphs have dispersed.

2. The following terms and conditions implement reasonable and prudent measure 2:
 - a. The service-approved biologist shall assist project personnel in selecting the point(s) at which diversion and dewatering would disrupt the least amount of stream flow necessary to achieve project goals.
 - b. The approved biologist shall be on site when dewatering is terminated in the event that arroyo toad tadpoles or unarmored threespine stickleback could become stranded during this activity.
3. The following terms and conditions implement reasonable and prudent measure 3:
 - a. The service-approved biologist, in conjunction with Valencia Company and any contractors, shall determine the boundaries of work, storage, access, and staging sites. Habitat to be disturbed shall be restricted to the minimum necessary to accomplish the bank protection construction, given topography, project needs, and safety considerations.
 - b. The boundary of work, storage, access, and staging sites shall be clearly marked by flagging or temporary fencing. Vehicles and all construction activities shall remain within the well-defined construction area, designated access roads, and staging areas.
 - c. Intrusion by unauthorized vehicles into the creek bed and outside of construction limits shall be prohibited, with control exercised by an on-site foreman. Access routes to the construction area outside of work hours shall be blocked with physical barriers, such as chain-link fencing, concrete blocks or large equipment.
 - d. A Service-approved biologist(s) shall conduct a training session for all project personnel prior to the onset of any ground-disturbing activities within the action area. At a minimum, the training shall include a description of the arroyo toad and unarmored threespine stickleback and their habitats; the general provisions of the Endangered Species Act; the necessity for adhering to the provisions of the Act; the penalties associated with violating the provisions of the Act; the specific measures that are being implemented to conserve the arroyo toad during construction; and the boundaries within which the specific actions may be accomplished. The program shall also cover the restrictions and guidelines that must be followed by all construction personnel to reduce or avoid effects on these species during project implementation.

David J. Castanon (1-8-02-F-43)

24

4. The following term and condition implements reasonable and prudent measure 4:

Prior to the onset of any ground-disturbing activity from the proposed action within or adjacent to arroyo toad or unarmored threespine stickleback habitat, the Corps shall review Valencia Company's plans to prevent the inadvertent spills of hazardous materials and to remediate any such spill that may occur. These plans shall specifically discuss the implications of spills in habitat of the arroyo toad and unarmored threespine stickleback and include methods to remediate these spills in the least damaging manner.

5. The following terms and conditions implement reasonable and prudent measure 5:

- a. The Service-approved biologist(s) shall have the authority to stop specific work activities until appropriate corrective measures are taken when unintended effects to arroyo toads or unarmored threespine sticklebacks occur. If an arroyo toad or an unarmored threespine stickleback is observed within a designated work area and cannot be avoided, all work shall stop until the animal leaves the work area or until it is captured and relocated by a Service-approved biologist to outside of the work area to avoid injury or mortality.
- b. If Valencia Company does not implement the protective measures for the arroyo toad or unarmored threespine stickleback, the Corps shall suspend work on that particular phase of Castaic/Hasley Creek channel lining project until such time that the Valencia Company is again in full compliance.

REPORTING REQUIREMENTS

The Corps shall provide a written annual report to the Service by January 31 of each year that this biological opinion is in effect. The report shall document the number of arroyo toads and unarmored threespine stickleback killed or injured by project activities. The report shall also provide a summary of the previous year's activities and their effects on the arroyo toad and unarmored threespine stickleback.

The report shall contain information on the following: (1) the type of activities that occurred in the action area (*e.g.*, construction activities, monitoring); (2) the location of these activities; (3) a description of the habitat in which these activities occurred; (4) the number of arroyo toads and unarmored threespine sticklebacks affected; (5) steps taken to avoid or minimize effects; (6) the number of arroyo toads and unarmored threespine sticklebacks relocated (as defined in the reasonable and prudent measures); (7) the locations from which arroyo toads and unarmored threespine sticklebacks were moved and to which they were relocated; (8) the status of removal activities for exotic vegetation; (9) the results of any surveys conducted for the arroyo toad and unarmored threespine stickleback in the previous year; (10) an analysis of the effectiveness of the monitoring plan and action levels and recommendations for any changes to the plan and action levels; and (11) any other pertinent information. The first report will be due the first January after the initiation of ground-disturbing activities.

David J. Castanon (1-8-02-F-43)

25

DISPOSITION OF DEAD OR INJURED SPECIMENS

Upon locating a dead or injured arroyo toad or unarmored threespine stickleback, initial notification must be made in writing to the Service's Division of Law Enforcement in Torrance, California (370 Amapola Avenue, Suite 114, Torrance, California 90501) and by telephone and writing to the Ventura Fish and Wildlife Office in Ventura, California, (2493 Portola Road, Suite B, Ventura, California 93003, (805) 644-1766) within three working days of the finding. The report shall include the date, time, location of the carcass, a photograph, cause of death, if known, and any other pertinent information.

Care shall be taken in handling dead specimens to preserve biological material in the best possible state for later analysis. Should any injured arroyo toads or unarmored threespine stickleback survive, the Service shall be contacted regarding their final disposition. The remains of arroyo toads or unarmored threespine stickleback shall be placed with the University of California at Santa Barbara [Contact: Mark Holmgren, University of California at Santa Barbara, EEMB Department, Santa Barbara, California, 93106, (805) 893-4098]. Arrangements regarding proper disposition of potential museum specimens shall be made with the University of California by the Corps or Valencia Company prior to implementation of any actions.

CONSERVATION RECOMMENDATIONS

Section 7(a)(1) of the Act directs Federal agencies to use their authorities to further the purposes of the Act by carrying out conservation programs for the benefit of endangered and threatened species. Conservation recommendations are discretionary agency activities to minimize or avoid adverse effects of a proposed action on listed species, to help implement recovery plans, or to develop information.

1. The Corps should evaluate the effects of water withdrawals or surface flow diversions on the moisture content of stream side banks to determine whether burrowing arroyo toads may be affected.
2. The Corps should conduct studies to increase our understanding of the population dynamics of the arroyo toad and unarmored threespine stickleback in this area. Such studies could include radio-tagging of adult arroyo toads and full surveys of this reach of the Castaic Creek during the breeding season. This type of research and the data obtained could greatly assist the Corps and Valencia Company in future consultations within arroyo toad habitat.
3. Valencia company should pursue additional vegetation enhancement, exotic plant removal, and African clawed frog control opportunities in the Castaic Creek corridor to further the recovery of the arroyo toad and unarmored threespine stickleback.

David J. Castanon (1-8-02-F-43)

26


The Service requests notification of the implementation of any conservation recommendations so we may be kept informed of actions minimizing or avoiding adverse effects or benefitting listed species or their habitats.

REINITIATION NOTICE

This concludes formal consultation on the Corps proposed Castaic Creek Channel Lining project. As provided in 50 CFR §402.16, reinitiation of formal consultation is required where discretionary Federal agency involvement or control over the action has been retained (or is authorized by law) and if: (1) the amount or extent of incidental take is exceeded; (2) new information reveals effects of the agency action that may affect listed species in a manner or to an extent not considered in this opinion; (3) the agency action is subsequently modified in a manner that causes an effect to the listed species or critical habitat not considered in this opinion; or (4) a new species is listed or critical habitat designated that may be affected by the action. In instances where the amount or extent of incidental take is exceeded, any operations causing such take must cease pending reinitiation.

If you have any questions, please contact Chris Dellith of my staff at (805) 644-1766.

Sincerely,



Carl T. Benz
Assistant Field Supervisor
South Coast/Deserts

Enclosure

cc: Betty Courtney, California Department of Fish and Game

REFERENCE CITED

- Allen, A. 2002. Personal communication. Project Manager, U.S. Army Corps of Engineers Ventura Office. Ventura, California.
- Aquatic Consulting Services. 2002. General maintenance plan Castaic Creek and Hasley Canyon drain. Ventura, California.
- Barto, W.S. 1999. Predicting potential habitat for the arroyo toad (*Bufo microscaphus californicus*) in San Diego County using a habitat suitability model and digital terrain data. Masters Thesis for San Diego State University, San Diego.
- Courtois, L. 2000. Letter to the U.S. Fish and Wildlife Service which included a California Native Species Field Survey documentation of arroyo toad tadpoles in the Santa Clara River, May 9, 2000. Ventura, California.
- Dellith, C. 1999. Personal observation. Fish and Wildlife Biologist, Ventura Fish and Wildlife Office. Ventura, California.
- Farris, R. 2002. Personal communication. Fish and Wildlife Biologist, Ventura Fish and Wildlife Office. Ventura, California.
- Griffin, P.C. 1999. *Bufo californicus*, arroyo toad movement patterns and habitat preferences. Masters Thesis for University of California, San Diego.
- Griffin, P.C., T.J. Case, and R.N. Fisher. 1999. Radio telemetry study of *Bufo californicus*, arroyo toad movement patterns and habitat preferences. Contract Report to California Department of Transportation Southern Biology Pool.
- Holland, D.C. 1995. Sensitive species hydroecological evaluation - Margarita River. Unpublished report.
- Holland, D.C. 1998. Sensitive species of amphibians and reptiles on MCB Camp Pendleton, San Diego County, California, with management recommendations. Prepared for ACServe Environmental Security, Resource Management Division, MCB Camp Pendleton. Contract # Moo681-94-C-0039.
- Impact Sciences. 2001a. Results of focused surveys for arroyo toads and special-status aquatic reptiles and amphibians in portions of Castaic Creek in Castaic Creek within the Valencia Commerce Center Area. Valencia, California. Agoura Hills, California.
- Impact Sciences. 2001b. Results of Focused Surveys for Arroyo Toad and Special-status Aquatic Reptiles and Amphibians within the Natural River Management Plan Area, Valencia, California. Agoura Hills, California.

- Jennings, M.R., and M.P. Hayes. 1994. Amphibian and reptile species of special concern in California. Final report to the California Department of Fish and Game, Inland Fisheries Division, Rancho Cordova, California, under contract 8023.
- Ramirez, R.S. 2000. Arroyo toad (*Bufo californicus*) radio telemetry study, Little Rock Creek, Los Angeles County, California. Prepared for the Angeles National Forest, Arcadia, California.
- Sandburg, N.H. 2001a. Field summary of Santa Clara River surveys for *Bufo californicus*, April 18, 2001. Santa Barbara, California.
- Sandburg, N.H. 2001b. Field summary of Santa Clara River surveys for *Bufo californicus* and *Rana aurora dayton* (sic), May 8 through May 29, 2001. Santa Barbara, California.
- Schroeder, M. 2001. Summary of June 14, 2001 site visit to Transit Mixed Concrete's Soledad Canyon Mine. Memorandum to Brian Mastin, Transit Mixed Concrete, dated July 12. Chambers Group, Inc., Irvine, California.
- Stebbins, R.C. 1985. A field guide to western reptiles and amphibians. Houghton Mifflin Company. Boston, Massachusetts.
- Subbotin, M. 2002a. Letter to the U.S. Army Corps of Engineers requesting that an incidental take statement be included for the unarmored threespine stickleback in the biological consultation, May 10, 2002. Valencia, California.
- Subbotin, M. 2002b. Personal communication. Senior Vice President, Planning and Environmental Resources, Newhall Ranch Division. Valencia, California.
- Sweet, S.S. 1992. Ecology and status of the arroyo toad (*Bufo microscaphus californicus*) on the Los Padres National Forest of southern California, with management recommendations. Report to USDA, Forest Service, Los Padres National Forest, Goleta, California.
- URS Corporation. 2002. Biological evaluation. Valencia Commerce Center Castaic Creek, Los Angeles County. Permit No. 89-419-EV. Permittee: Valencia Company, Valencia, California. Prepared for the U.S. Army Corps of Engineers, Ventura, California. Santa Barbara, California.
- U.S. Army Corps of Engineers and California Department of Fish and Game. 1998. Final environmental impact report/environmental impact statement: 404 permit and 1603 agreement for portions of the Santa Clara River and its tributaries. Prepared for the U.S. Army Corps of Engineers, Ventura Field Office, Ventura, California and the California Department of Fish and Game, Region 5, Long Beach, California by Woodward-Clyde Consultants, Santa Barbara, California.

U.S. Fish and Wildlife Service. 2001. 50 CFR Part 17, Final designation of critical habitat for the arroyo toad; Final Rule.

U.S. Fish and Wildlife Service. 1999. Arroyo southwestern toad (*Bufo microscaphus californicus*) recovery plan. Portland, Oregon.

U.S. Fish and Wildlife Service. 1985. Unarmored threespine stickleback (*Gasterosteus aculeatus williamsoni*) recovery plan. Portland, Oregon.

The Declining Amphibian Populations Task Force Fieldwork Code of Practice

1. Remove mud, snails, algae, and other debris from nets, traps, boots, vehicle tires, and all other surfaces. Rinse cleaned items with sterilized (*e.g.*, boiled or treated) water before leaving each study site.
2. Scrub boots, nets, traps, and other types of equipment used in the aquatic environment with 70 percent ethanol solution or a bleach solution of one-half to one cup of bleach in one gallon of water and rinse clean with sterilized water between study sites. Avoid cleaning equipment in the immediate vicinity of a pond, wetland, or riparian area.
3. In remote locations, clean all equipment with 70 percent ethanol or a bleach solution, and rinse with sterile water upon return to the lab or a "base camp." Elsewhere, when laundry facilities are available, remove nets from poles and wash (in a protective mesh laundry bag) with bleach on a "delicate" cycle.
4. When working at sites with known or suspected disease problems, or when sampling populations of rare or isolated species, wear disposable gloves and change them between handling each animal. Dedicate separate sets of nets, boots, traps, and other equipment to each site being visited. Clean and store them separately at the end of each field day.
5. Safely dispose of used cleaning materials and fluids. Do not dispose of cleaning materials and fluids in or near ponds, wetland, and riparian areas; if necessary, return them to the lab for proper disposal. Safely dispose of used disposable gloves in sealed bags.
6. When amphibians are collected, ensure the separation of animals from different sites and take great care to avoid indirect contact (*e.g.*, via handling or reuse of containers) between them or with other captive animals. Do not expose animals to unsterilized vegetation or soils which have been taken from other sites. Always use disinfected and disposable husbandry equipment.
7. If a dead amphibian is found, place it in a sealable plastic bag and refrigerate (do not freeze). If any captured live amphibians appear unhealthy, retain each animal in a separate plastic container that allows air circulation and provides a moist environment from a damp sponge or sphagnum moss. For each collection of live or dead animals, record the date and time collected, location of collection, name of collector, condition of animal upon collection, and any other relevant environmental conditions observed at the time of collection. Immediately contact the Ventura Fish and Wildlife Office at (805) 644-1766 for further instructions.

The Fieldwork Code of Practice has been produced by the Declining Amphibian Populations Task Force with valuable assistance from Begona Arano, Andrew Cunningham, Tom Langton, Jamie Reaser, and Stan Sessions.

For further information on this Code, or on the Declining Amphibian Populations Task Force, contact John Wilkinson, Biology Department, The Open University, Walton Hall, Milton Keynes, MK7 6AA, UK.

E-mail: DAPTF@open.ac.uk

Fax: +44 (0) 1908-654167